

# **Locke Mountain**

## TETRA TECH, INC.

By: CAH Date: 10/13/2016 Subject: Locke Mountain Road  
Checked By: JB Date: 10/23/2016 PCSM Design and Evaluation

### PURPOSE:

The purpose of these calculations is to design a Post-Construction Stormwater Management (PCSM) Plan for the Locke Mountain Road block valve site as part of the Sunoco Pipeline L.P. Pennsylvania Pipeline Project. The site is located within Frankstown Township, Blair County, Pennsylvania. Permanent stormwater controls will be developed to satisfy PADEP and Frankstown Township's approved Act 167 Plan.

### PCSM DESIGN REQUIREMENTS:

The PCSM design for this project follows the PA Department of Environmental Protection's (PADEP) Pennsylvania Stormwater Best Management Practices Manual (BMP Manual), December 2006; and the standard design criteria from PA Title 25, Chapter 102.8.(g)(2) and (3). The design criteria evaluated for the site are summarized below.

#### Act 167 Consistency

The Locke Mountain Road block valve site is located in Blair County, which does not have a county-wide Act 167 plan adopted. However, Frankstown Township has enacted the Beaverdam Branch Watershed Act 167 Stormwater Management Plan. This plan requires that the post-development runoff rate be less than or equal to the pre-development rate. The PCSM design at the Locke Mountain Road block valve has been designed for consistency with Frankstown Township's approved Act 167 Plan.

#### Recommended Volume Control Guideline

Use of Control Guideline 1 is recommended where site conditions offer the opportunity to reduce the increase in runoff volume as follows:

- Do not increase the post-development total runoff volume for all storms equal to or less than the two-year/24-hour event;
- Existing (pre-development) non-forested pervious areas must be considered meadow (good condition) or its equivalent; and
- 20 percent of existing impervious area, when present, shall be considered meadow (good condition) or its equivalent.

Due to the presence of shallow redoximorphic features in soil logs surrounding the Locke Mountain Road block valve site, it is not possible to infiltrate the 2-year/24-hour stormwater runoff volume increase while maintaining a 2-foot separation to the seasonal high groundwater table. Volume reducing BMPs in the PADEP Stormwater BMP Manual were analyzed on a case-by-case basis but did not meet their respective requirements. As a result, two slow-release BMPs have been proposed.

#### Recommended Peak Rate Control Guideline

The recommended control guideline for peak rate control is:

- Do not increase the peak rate of discharge for the 2-year through 100-year events (at minimum); as necessary, provide additional peak rate control as required by the applicable and approved Act 167 plan.
- The Frankstown Township Act 167 rate requirements mirror PADEP's requirements. Therefore, no additional peak rate control is required under the Act 167 Plan.

This site will utilize two slow-release BMPs with a downslope compacted berm to manage the two-year through 100-year peak rate increases. The proposed BMP will increase the post-construction time of concentration for the drainage area encompassing the block valve.

### **Recommended Water Quality Control Guideline**

Control Guideline 1 will provide water quality control and stream channel protection as well as flood control protection. The use of a slow-release BMP has been approved by PADEP as an appropriate way to meet the requirements of Control Guideline 1 when onsite infiltration is not feasible.

### **Infiltration**

Onsite infiltration testing was conducted in accordance of the PA BMP Manual. Documentation for infiltration testing and design infiltration rates can be found in Attachment 5 of the Site Restoration/Post Construction Stormwater Management Plan. Infiltration test locations and recommended design rates are also labeled on the PCSM Plan Drawings in Attachment 6.

During the onsite infiltration tests, the depth to seasonal high groundwater and shallow bedrock or another confining layer were evaluated. Due to the presence of shallow redoximorphic features which can be indicative of a shallow seasonal high groundwater table, it is not possible to maintain 2 feet of separation between a volume-reducing BMP and the seasonal high groundwater table.

The post-construction stormwater management design utilizes two slow-release BMPs to manage runoff volume due to the presence of shallow seasonal high groundwater.

### **Loading Ratio**

Loading ratio guidelines do not apply because the design does not propose an infiltration BMP.

### **Disturbed Area**

To meet Standard Worksheet 10 guidelines, 90% of the disturbed area is detained by the proposed PCSM BMPs.


### **Karst Topography**

Locke Mountain Road is not located within an area of karst terrain.

### **Special Protection Watershed**

Locke Mountain Road is not located within a special protection watershed, so antidegradation requirements do not apply.

Aerial photograph provided by ESRI's ArcGIS Online World Imagery map service (© 2015 ESRI and its data suppliers).



**Legend**

- Alignment Centerline
- Limit of Disturbance
- 10 Ft. Contour
- 2 Ft. Contour
- Meadow
- Woods
- Drainage Area




**PRE-DEVELOPMENT DRAINAGE AREA MAP**  
 LOCKE MOUNTAIN ROAD  
 PENNSYLVANIA PIPELINE PROJECT  
 SUNOCO LOGISTICS, L.P.  
 BLAIR COUNTY, PENNSYLVANIA

DRAWN BY: S. PAXTON 05/19/16  
 CHECKED BY: J. BRODY 11/09/16  
 APPROVED BY:  
 CONTRACT NUMBER: 112IC05958

FIGURE NUMBER	REV
1	0

Aerial photograph provided by ESRI's ArcGIS Online World Imagery map service (© 2015 ESRI and its data suppliers).




Detained 2  
0.04 acres

Undetained  
1.06 acres

Detained 1  
0.17 acres

**Legend**

- Alignment Centerline
- Limit of Disturbance
- 10 Ft. Contour
- 2 Ft. Contour
- Gravel
- Meadow
- Woods
- Drainage Area



**POST-DEVELOPMENT DRAINAGE AREA MAP**  
 LOCKE MOUNTAIN ROAD  
 PENNSYLVANIA PIPELINE PROJECT  
 SUNOCO LOGISTICS, L.P.  
 BLAIR COUNTY, PENNSYLVANIA

DRAWN BY: S. PAXTON 05/20/16  
 CHECKED BY: J. BRODY 11/09/16  
 APPROVED BY:  
 CONTRACT NUMBER: 112IC05958

FIGURE NUMBER	REV
2	0

**NOAA Atlas 14, Volume 2, Version 3**  
**Location name: Frankstown Twp, Pennsylvania,**  
**USA\***



**Latitude: 40.4314°, Longitude: -78.336°**  
**Elevation: 950.1 ft\*\***



\* source: ESRI Maps  
 \*\* source: USGS

**POINT PRECIPITATION FREQUENCY ESTIMATES**

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M.Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF\\_tabular](#) | [PF\\_graphical](#) | [Maps\\_&aerials](#)

**PF tabular**





<b>PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)<sup>1</sup></b>										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.308 (0.279-0.343)	0.369 (0.334-0.410)	0.450 (0.405-0.499)	0.513 (0.460-0.568)	0.596 (0.532-0.658)	0.662 (0.587-0.729)	0.727 (0.641-0.799)	0.794 (0.696-0.872)	0.888 (0.771-0.973)	0.958 (0.824-1.05)
10-min	0.479 (0.433-0.533)	0.577 (0.521-0.640)	0.700 (0.630-0.775)	0.792 (0.711-0.877)	0.912 (0.813-1.01)	1.00 (0.890-1.10)	1.09 (0.965-1.20)	1.19 (1.04-1.30)	1.31 (1.13-1.43)	1.40 (1.20-1.52)
15-min	0.587 (0.530-0.654)	0.705 (0.637-0.783)	0.859 (0.773-0.952)	0.975 (0.874-1.08)	1.13 (1.00-1.24)	1.24 (1.10-1.37)	1.36 (1.20-1.50)	1.48 (1.29-1.62)	1.63 (1.41-1.78)	1.74 (1.50-1.91)
30-min	0.777 (0.702-0.865)	0.944 (0.852-1.05)	1.18 (1.06-1.30)	1.35 (1.21-1.50)	1.59 (1.42-1.76)	1.77 (1.57-1.95)	1.96 (1.73-2.16)	2.15 (1.89-2.36)	2.41 (2.10-2.64)	2.61 (2.25-2.86)
60-min	0.949 (0.857-1.06)	1.16 (1.05-1.29)	1.48 (1.33-1.64)	1.72 (1.54-1.91)	2.06 (1.84-2.28)	2.34 (2.07-2.58)	2.63 (2.31-2.89)	2.92 (2.56-3.21)	3.34 (2.90-3.66)	3.67 (3.16-4.01)
2-hr	1.09 (0.979-1.23)	1.32 (1.19-1.48)	1.69 (1.51-1.89)	1.98 (1.76-2.21)	2.40 (2.11-2.66)	2.73 (2.39-3.03)	3.09 (2.69-3.42)	3.47 (3.00-3.83)	4.01 (3.43-4.43)	4.45 (3.77-4.92)
3-hr	1.18 (1.06-1.32)	1.43 (1.29-1.59)	1.80 (1.62-2.01)	2.11 (1.89-2.35)	2.55 (2.27-2.82)	2.91 (2.57-3.21)	3.30 (2.89-3.64)	3.71 (3.23-4.08)	4.31 (3.70-4.72)	4.79 (4.07-5.25)
6-hr	1.47 (1.33-1.65)	1.78 (1.60-1.98)	2.22 (2.00-2.47)	2.58 (2.31-2.87)	3.10 (2.76-3.43)	3.54 (3.13-3.90)	4.00 (3.50-4.40)	4.49 (3.90-4.94)	5.20 (4.47-5.70)	5.78 (4.92-6.33)
12-hr	1.82 (1.65-2.04)	2.19 (1.98-2.45)	2.72 (2.45-3.03)	3.16 (2.84-3.52)	3.81 (3.39-4.23)	4.35 (3.84-4.82)	4.94 (4.33-5.45)	5.58 (4.84-6.15)	6.50 (5.57-7.15)	7.27 (6.16-7.99)
24-hr	2.23 (2.04-2.44)	2.67 (2.45-2.93)	3.33 (3.05-3.64)	3.86 (3.53-4.22)	4.64 (4.21-5.06)	5.28 (4.78-5.75)	5.97 (5.37-6.49)	6.71 (5.99-7.29)	7.78 (6.87-8.46)	8.66 (7.57-9.41)
2-day	2.53 (2.33-2.77)	3.04 (2.79-3.33)	3.77 (3.46-4.12)	4.37 (4.00-4.78)	5.24 (4.78-5.72)	5.97 (5.40-6.50)	6.75 (6.07-7.35)	7.58 (6.76-8.25)	8.77 (7.74-9.56)	9.75 (8.52-10.6)
3-day	2.69 (2.48-2.93)	3.22 (2.97-3.51)	3.98 (3.66-4.33)	4.60 (4.23-5.01)	5.51 (5.04-5.98)	6.26 (5.69-6.79)	7.05 (6.38-7.65)	7.91 (7.10-8.58)	9.13 (8.10-9.92)	10.1 (8.89-11.0)
4-day	2.84 (2.63-3.08)	3.39 (3.14-3.69)	4.18 (3.87-4.54)	4.83 (4.46-5.24)	5.77 (5.30-6.24)	6.54 (5.98-7.08)	7.36 (6.69-7.96)	8.24 (7.44-8.92)	9.48 (8.46-10.3)	10.5 (9.27-11.4)
7-day	3.36 (3.13-3.62)	4.01 (3.74-4.32)	4.88 (4.55-5.26)	5.58 (5.19-6.01)	6.55 (6.07-7.04)	7.33 (6.75-7.87)	8.13 (7.46-8.73)	8.96 (8.17-9.64)	10.1 (9.14-10.9)	11.0 (9.87-11.9)
10-day	3.92 (3.66-4.20)	4.65 (4.35-4.99)	5.58 (5.22-5.98)	6.33 (5.91-6.78)	7.35 (6.84-7.87)	8.16 (7.57-8.74)	8.99 (8.30-9.63)	9.84 (9.03-10.6)	11.0 (10.0-11.8)	11.9 (10.8-12.8)
20-day	5.36 (5.08-5.67)	6.32 (5.98-6.69)	7.38 (6.98-7.81)	8.20 (7.74-8.67)	9.26 (8.72-9.79)	10.1 (9.46-10.7)	10.8 (10.2-11.5)	11.6 (10.9-12.3)	12.6 (11.7-13.4)	13.3 (12.3-14.1)
30-day	6.70 (6.35-7.06)	7.85 (7.44-8.27)	9.01 (8.54-9.49)	9.91 (9.38-10.4)	11.0 (10.4-11.6)	11.9 (11.2-12.5)	12.7 (12.0-13.4)	13.5 (12.7-14.2)	14.4 (13.5-15.2)	15.1 (14.1-16.0)
45-day	8.48 (8.06-8.92)	9.92 (9.43-10.4)	11.3 (10.7-11.8)	12.2 (11.6-12.9)	13.4 (12.8-14.1)	14.3 (13.6-15.0)	15.1 (14.3-15.8)	15.8 (14.9-16.6)	16.6 (15.7-17.5)	17.2 (16.2-18.2)
60-day	10.2 (9.75-10.7)	11.9 (11.4-12.5)	13.4 (12.8-14.0)	14.4 (13.8-15.1)	15.7 (15.0-16.4)	16.5 (15.8-17.3)	17.3 (16.5-18.1)	18.0 (17.2-18.9)	18.8 (17.9-19.7)	19.3 (18.4-20.3)

<sup>1</sup> Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

### PF graphical

PDS-based depth-duration-frequency (DDF) curves  
 Latitude: 40.4314°, Longitude: -78.3360°




[Back to Top](#)


### Maps & aerials

#### Small scale terrain







Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)



**WORKSHEET 1. GENERAL SITE INFORMATION**

**Date:** November 11, 2016

**Project Name:** Locke Mountain Road

**Municipality:** Frankstown

**County:** Blair

**Total Area (acres):** 1.27

**Major River Basin:** Susquehanna River

**Watershed:** Frankstown Branch Juniata River

**Sub Basin:** Little Juniata River

**Nearest Surface Water to Receive Runoff:** Tributary #16298 to Robinson Run

**Chapter 93 - Designated Water Use:** Warm Water Fishes (WWF)

**Impaired according to Chapter 303(d) list?** YES   
**List Causes of Impairment:** NO

***Is Project Subject to, or Part of:***

**Municipal Separate Storm Sewer System (MS4) Requirements** YES

NO

**Existing or Planned drinking water supply?** YES

NO

**If yes, distance from proposed discharge (miles):** \_\_\_\_\_

**Approved Act 167 Plan?** YES

NO

**Existing River Conservation Plan?** YES

NO

## Worksheet 2. Sensitive Natural Resources

### INSTRUCTIONS

1. Provide Sensitive Resources Map according to non-structural BMP 5.4.1 in Chapter 5. This map should identify wetlands, woodlands, natural drainage ways, steep slopes, and other sensitive natural areas.

See pre-development drainage area map

2. Summarize the existing extent of each sensitive resource in the Existing Sensitive Resources Table (below, using Acres). If none present, insert 0.

0.00 acres

3. Summarize Total Protected Area as defined under BMPs in Chapter 5.

0.00 acres

4. Do not count any area twice. For example, an area that is both a floodplain and a wetland may only be considered once.

EXISTING NATURAL SENSITIVE RESOURCE	MAPPED? Yes/no/n/a	TOTAL AREA (Ac.)	PROTECTED AREA (Ac.)
Waterbodies	N/A		
Floodplains	N/A		
Riparian Areas	N/A		
Wetlands	N/A		
Woodlands	N/A		
Natural Drainage Ways	N/A		
Steep Slopes, 15% - 25%	N/A		
Steep Slopes, over 25%	N/A		
Other:			
Other:			
<b>TOTAL EXISTING:</b>		<b>0.00</b>	<b>0.00</b>

## Worksheet 3. Nonstructural BMP Credits

### PROTECTED AREA

1.1 Area of Protected Sensitive/Special Value Features (see WS 2)	0.00 Ac.
1.2 Area of Riparian Forest Buffer Protection	0.00 Ac.
3.1 Area of Minimum Disturbance/Reduced Grading	0.00 Ac
<b>TOTAL</b>	<b>0.00 Ac</b>

Site Area	Minus	Protected Area	=	Stormwater Management Area
0.70	-	0	=	0.70
				This is the area that requires stormwater management

### VOLUME CREDITS

#### 3.1 Minimum Soil Compaction (See Chapter 8, page 22 – SW BMP Manual)

Lawn	_____ ft <sup>2</sup>	x 1/4" x 1/12	=	_____ ft <sup>3</sup>
	_____			
Meadow	_____ ft <sup>2</sup>	x 1/3" x 1/12	=	_____ ft <sup>3</sup>

#### 3.3 Protect Existing Trees (See Chapter 8, page 23 – SW BMP Manual)

*For Trees within 100 feet of impervious area:*

Tree Canopy	_____ ft <sup>2</sup>	x 1/2" x 1/12	=	_____ ft <sup>3</sup>
	_____			

#### 5.1 Disconnect Roof Leaders to Vegetated Areas (See Chapter 8 page 25 – SW BMP Manual)

*For runoff directed to areas protected under 5.8.1 and 5.8.2*

Roof Area	_____ ft <sup>2</sup>	x 1/3" x 1/12	=	_____ ft <sup>3</sup>
-----------	-----------------------	---------------	---	-----------------------

*For all other disconnected roof areas*

Roof Area	_____ ft <sup>2</sup>	x 1/4" x 1/12	=	_____ ft <sup>3</sup>
-----------	-----------------------	---------------	---	-----------------------

#### 5.2 Disconnect Non-Roof impervious to Vegetated Areas (See Chapter 8, page 26 – SW BMP Manual)

*For Runoff directed to areas protected under 5.8.1 and 5.8.2*

Impervious Area	_____ ft <sup>2</sup>	x 1/3" x 1/12	=	_____ ft <sup>3</sup>
-----------------	-----------------------	---------------	---	-----------------------

*For all other disconnected roof areas*

Impervious Area	_____ ft <sup>2</sup>	x 1/4" x 1/12	=	_____ ft <sup>3</sup>
-----------------	-----------------------	---------------	---	-----------------------

**TOTAL NON-STRUCTURAL VOLUME CREDIT\*** \_\_\_\_\_ ft<sup>3</sup>

\*For use on Worksheet 5

## WORKSHEET 4. CHANGE IN RUNOFF VOLUME FOR 2-YR STORM EVENT

PROJECT: Locke Mountain Road  
 Drainage Area: 1.27 acres  
 2-Year Rainfall: 2.67 in

Total Site Area: 0.70 acres  
 Protected Site Area: N/A acres  
 Managed Site Area: 0.70 acres

### Existing Conditions

Cover Type/Condition	Soil Type	Area (sf)	Area (ac)	CN	S	Ia (0.2*S)	Q Runoff <sup>1</sup> (in)	Runoff Volume <sup>3</sup> (ft <sup>3</sup> )
Meadow	C	6,970	0.16	71	4.08	0.82	0.58	336
Meadow	D	23,522	0.54	78	2.82	0.56	0.90	1,765
<b>TOTAL:</b>		<b>30,492</b>	<b>0.70</b>					<b>2,100</b>

### Developed Conditions

Cover Type/Condition	Soil Type	Area (sf)	Area (ac)	CN	S	Ia (0.2*S)	Q Runoff <sup>1</sup> (in)	Runoff Volume <sup>3</sup> (ft <sup>3</sup> )
Meadow	C	5,227	0.12	71	4.08	0.82	0.58	252
Meadow	D	18,731	0.43	78	2.82	0.56	0.90	1,405
Impervious - Gravel	C	1,742	0.04	89	1.24	0.25	1.60	233
Impervious - Gravel	D	4,792	0.11	91	0.99	0.20	1.77	705
<b>TOTAL:</b>		<b>30,492</b>	<b>0.70</b>					<b>2,595</b>

2-Year Volume Increase (ft <sup>3</sup> ):	<b>495</b>
--	------------

**2-Year Volume Increase = Developed Conditions Runoff Volume - Existing Conditions Runoff Volume**

1. Runoff (in) =  $Q = (P - 0.2S)^2 / (P + 0.8S)$  where  
 P = 2-Year Rainfall (in)  
 S =  $(1000/CN) - 10$

2. Runoff Volume (CF) =  $Q \times \text{Area} \times 1/12$   
 Q = Runoff (in)  
 Area = Land use area (sq. ft.)

**Note: Runoff Volume must be calculated for EACH land use type/condition and HSGI.  
 The use of a weighted CN value for volume calculations is not acceptable.**

Worksheet 5. Structural BMP Volume Credits

**PROJECT:** Locke Mountain Road  
**SUB-BASIN:** \_\_\_\_\_

<b>Required Control Volume (ft<sup>3</sup>) - from Worksheet 4:</b>	495
<b>Non-structural Volume Credit (ft<sup>3</sup>) - from Worksheet 3:</b> (maximum is 25% of required volume)	N/A
<b>Structural Volume Reqmt (ft<sup>3</sup>):</b> <i>(Required Control Volume minus Non-structural Credit)</i>	495

Proposed BMPs from PA Stormwater Best Management Practices Manual Chapter 6	Area (ft <sup>2</sup> )	Volume Reduction Permanently Removed (ft <sup>3</sup> )
6.4.1 Porous Pavement		
6.4.2 Infiltration Basin		
6.4.3 Infiltration Bed		
6.4.4 Infiltration Trench		
6.4.5 Rain Garden/Bioretenion		
6.4.6 Dry Well/Seepage Pit		
6.4.7 Constructed Filter		
6.4.8 Vegetated Swale		
6.4.9 Vegetated Filter Strip		
6.4.10 Berm		
6.5.1 Vegetated Roof		
6.5.2 Capture and Re-Use		
6.6.1 Constructed Wetlands		
6.6.2 Wet Pond/Retention Basin		
6.7.1 Riparian Buffer/Riparian Forest Buffer Restoration		
6.7.2 Landscape Restoration/Reforestation		
6.7.3 Soil Amendment		
6.8.1 Level Spreader		
6.8.2 Special Storage Areas		
<i>Other:</i> Slow Release Concept	108	719
<b>Total Structural Volume (ft<sup>3</sup>):</b>		<b>719</b>
<b>Structural Volume Requirement (ft<sup>3</sup>):</b>		<b>495</b>
		<b>DIFFERENCE: -224</b>

**VOLUME CREDIT DETERMINATION DETAINED 1**

- 1 Detained area runoff volume from Hydraflow = 800 cf
- 2 Storage volume of the BMP = 540 cf
- 3 Infiltrated volume within 72 hours after the 2-yr/24-hr event  
 (Infiltration Rate/12) x Infiltration Area x 72 hrs = 540 cf  
 Potential infiltrated volume = 3,888 cf. based on slow release dewatering rate. Since this is greater than the storage volume, only the storage volume can be used and assumed to infiltrate within 72 hours.

**VOLUME CREDIT DETERMINATION DETAINED 2**

- 1 Detained area runoff volume from Hydraflow = 179 cf
- 2 Storage volume of the BMP = 432 cf
- 3 Infiltrated volume within 72 hours after the 2-yr/24-hr event  
 (Infiltration Rate/12) x Infiltration Area x 72 hrs = 179 cf  
 Potential infiltrated volume = 3,110 cf. based on slow release dewatering rate. Since this is greater than the storage volume, only the storage volume can be used and assumed to infiltrate within 72 hours.

## WORKSHEET 10. WATER QUALITY COMPLIANCE FOR NITRATE

*Does the site design incorporate the following BMPs to address nitrate pollution? A summary "yes" rating is achieved if at least 2 Primary BMPs for nitrate are provided across the site or 4 secondary BMPs for nitrate are provided across the site (or the*

**PRIMARY BMPs FOR NITRATE:**

	YES	NO
NS BMP 5.4.2 - Protect / Conserve / Enhance Riparian Buffers	<input type="checkbox"/>	<input type="checkbox"/>
NS BMP 5.5.4 - Cluster Uses at Each Site	<input type="checkbox"/>	<input type="checkbox"/>
NS BMP 5.6.1 - Minimize Total Disturbed Area	<input checked="" type="checkbox"/>	<input type="checkbox"/>
NS BMP 5.6.3 - Re-Vegetate / Re-Forest Disturbed Areas (Native Species)	<input checked="" type="checkbox"/>	<input type="checkbox"/>
NS BMP 5.9.1 - Street Sweeping / Vacuuming	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.7.1 - Riparian Buffer Restoration	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.7.2 - Landscape Restoration	<input type="checkbox"/>	<input type="checkbox"/>

**SECONDARY BMPs FOR NITRATE:**

NS BMP 5.4.1 - Protect Sensitive / Special Value Features	<input type="checkbox"/>	<input type="checkbox"/>
NS BMP 5.4.3 - Protect / Utilize Natural Drainage Features	<input type="checkbox"/>	<input type="checkbox"/>
NS BMP 5.6.2 - Minimize Soil Compaction	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.4.5 - Rain Garden / Bioretention	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.4.8 - Vegetated Swale	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.4.9 - Vegetated Filter Strip	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.6.1 - Constructed Wetland	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.7.1 - Riparian Buffer Restoration	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.7.2 - Landscape Restoration	<input type="checkbox"/>	<input type="checkbox"/>
Structural BMP 6.7.3 - Soils Amendment/Restoration	<input checked="" type="checkbox"/>	<input type="checkbox"/>

## Underdrain Dewatering Rate Calculation

Project: Locke Mtn

BMP: 1

Filter Media				
Layer	Media	Thickness - T (ft)	Min. Infiltration Rate - K (ft/min) <sup>1</sup>	Flow Rate (cfs) <sup>2</sup>
1	Clean Gravel	N/A	2	N/A
2	Coarse Sand	2	0.02	0.02
3	Fine Sand	N/A	0.002	N/A
4	Other <sup>3</sup>	N/A	N/A	N/A
<b>Minimum Flow Rate (cfs)</b>				<b>0.015</b>

1. From Principles of Geotechnical Engineering Third Edition, Braja Das, 1994

2.  $Q=KA(Hm+T)/T$

A = Area (square feet) = 60

Hm = Head above media (feet) = 1.5

3. Infiltration rate measured in field or laboratory

Perforated Pipe				
Pipe	Perforation Area (square inch) <sup>4</sup>	# Perforations per Foot N	Pipe Length - L (ft)	Flow Rate (cfs) <sup>5</sup>
1	1.00	1	20	0.91
2	N/A	N/A	N/A	N/A
<b>Total Flow Rate (cfs)</b>				<b>0.91</b>

4. Reference: [PVC: certainteed.com](http://PVC.certainteed.com) [HDPE: ads-pipe.com](http://HDPE.ads-pipe.com)

5.  $Q= N*L*cAo\sqrt{2GH}$

c = Orifice Coefficient = 0.6

Ao= Perforation Area (sq. ft.) 0.007

G= Grav. Accel. (ft/sec<sup>2</sup>) 32.2

H= Average Head (ft) = 3

Pipe Discharge				
Pipe	Pipe Diameter - D (in)	Pipe Roughness Coefficient -n	Pipe Slope - S <sup>6</sup>	Flow Rate (cfs) <sup>7</sup>
1	4	0.012	0.016666667	0.27
2	N/A	N/A	N/A	N/A
<b>Total Flow Rate (cfs)</b>				<b>0.27</b>

6. For flat pipe, use hydraulic grade (pipe diameter/pipe length) for the pipe slope

7. From Manning's equation (attach separate calculation worksheet)

Limiting flow rate from combined underdrain system - Ql (cfs) =	<b>0.015</b>
Berm Ponding Volume (cu-ft) =	<b>540</b>
Total Dewatering Volume including volume in voids(cu-ft) =	<b>588</b>
Dewatering Time (sec) = 2HA/Ql =	<b>39,200</b>
Dewatering Time (hrs) =	<b>10.89</b>

**TIME OF CONCENTRATION ADJUSTMENT DETAINED 1**

POST CONSTRUCTION TC TO BMP (DETAINED TC) BEFORE ADJUSTMENT 6.1 MIN

STRUCTURAL VOLUME PROVIDED BY BMP 540 CF

RATES OF RUNOFF TO THE BMP (FROM HYDRAFLOW REPORT)

Storm Event	Q (CFS)
2 YR/24 HR	0.396
10 YR/24 HR	0.683
50 YR/24 HR	1.031
100 YR/24 HR	1.2

ADDITIONAL RESIDENCE TIME (MIN) = (STRUCTURAL VOLUME PROVIDED BY BMP / RATE OF RUNOFF TO BMP) / 60

Storm Event	Q (CFS)	Additional Residence Time (min.)
2 YR/24 HR	0.396	22.727
10 YR/24 HR	0.683	13.177
50 YR/24 HR	1.031	8.729
100 YR/24 HR	1.200	7.500

ADJUSTED TC = POST CONSTRUCTION TC TO BMP BEFORE ADJUSTMENT + ADDITIONAL RESIDENCE TIME

Storm Event	Q (CFS)	Additional Residence Time (min.)	Adjusted Time of Concentration (min.)
2 YR/24 HR	0.396	22.727	28.827
10 YR/24 HR	0.683	13.177	19.277
50 YR/24 HR	1.031	8.729	14.829
100 YR/24 HR	1.200	7.500	13.600



## Underdrain Dewatering Rate Calculation

Project: Locke Mtn

BMP: 2

Filter Media				
Layer	Media	Thickness - T (ft)	Min. Infiltration Rate - K (ft/min) <sup>1</sup>	Flow Rate (cfs) <sup>2</sup>
1	Clean Gravel	N/A	2	N/A
2	Coarse Sand	2	0.02	0.01
3	Fine Sand	N/A	0.002	N/A
4	Other <sup>3</sup>	N/A	N/A	N/A
<b>Minimum Flow Rate (cfs)</b>				<b>0.012</b>

1. From Principles of Geotechnical Engineering Third Edition, Braja Das, 1994

2.  $Q=KA(Hm+T/T)$

A = Area (square feet) = 48

Hm = Head above media (feet) = 1.5

3. Infiltration rate measured in field or laboratory

Perforated Pipe				
Pipe	Perforation Area (square inch) <sup>4</sup>	# Perforations per Foot N	Pipe Length - L (ft)	Flow Rate (cfs) <sup>5</sup>
1	1.00	1	16	0.73
2	N/A	N/A	N/A	N/A
<b>Total Flow Rate (cfs)</b>				<b>0.73</b>

4. Reference: [PVC: certainteed.com](http://PVC.certainteed.com) [HDPE: ads-pipe.com](http://HDPE.ads-pipe.com)

5.  $Q= N*L*cAo\sqrt{2GH}$

c = Orifice Coefficient = 0.6

Ao= Perforation Area (sq. ft.) 0.007

G= Grav. Accel. (ft/sec<sup>2</sup>) 32.2

H= Average Head (ft) = 3

Pipe Discharge				
Pipe	Pipe Diameter - D (in)	Pipe Roughness Coefficient -n	Pipe Slope - S <sup>6</sup>	Flow Rate (cfs) <sup>7</sup>
1	4	0.012	0.020833333	0.30
2	N/A	N/A	N/A	N/A
<b>Total Flow Rate (cfs)</b>				<b>0.30</b>

6. For flat pipe, use hydraulic grade (pipe diameter/pipe length) for the pipe slope

7. From Manning's equation (attach separate calculation worksheet)

Limiting flow rate from combined underdrain system - Ql (cfs) =	<b>0.012</b>
Detained volume based on 2-year/24-hour storm (cu-ft) =	<b>179</b>
Total Dewatering Volume including volume in voids(cu-ft) =	<b>217</b>
Dewatering Time (sec) = 2HA/Ql =	<b>18,117</b>
Dewatering Time (hrs) =	<b>5.03</b>

**TIME OF CONCENTRATION ADJUSTMENT DETAINED 2**

POST CONSTRUCTION TC TO BMP (DETAINED TC) BEFORE ADJUSTMENT 5.4 MIN

STRUCTURAL VOLUME PROVIDED BY BMP 179 CF

RATES OF RUNOFF TO THE BMP (FROM HYDRAFLOW REPORT)

Storm Event	Q (CFS)
2 YR/24 HR	0.089
10 YR/24 HR	0.155
50 YR/24 HR	0.237
100 YR/24 HR	0.277

ADDITIONAL RESIDENCE TIME (MIN) = (STRUCTURAL VOLUME PROVIDED BY BMP / RATE OF RUNOFF TO BMP) / 60

Storm Event	Q (CFS)	Additional Residence Time (min.)
2 YR/24 HR	0.089	33.521
10 YR/24 HR	0.155	19.247
50 YR/24 HR	0.237	12.588
100 YR/24 HR	0.277	10.770

ADJUSTED TC = POST CONSTRUCTION TC TO BMP BEFORE ADJUSTMENT + ADDITIONAL RESIDENCE TIME


Storm Event	Q (CFS)	Additional Residence Time (min.)	Adjusted Time of Concentration (min.)
2 YR/24 HR	0.089	33.521	38.921
10 YR/24 HR	0.155	19.247	24.647
50 YR/24 HR	0.237	12.588	17.988
100 YR/24 HR	0.277	10.770	16.170

## Underdrain Report

Label	Solve For	Friction Method	Roughness Coefficient
Circular Pipe - 1	Full Flow Capacity	Manning Formula	0.012
Channel Slope (ft/ft)	Normal Depth (ft)	Diameter (ft)	Discharge (ft <sup>3</sup> /s)
0.08600	0.33	0.33	0.60
Flow Area (ft <sup>2</sup> )	Wetted Perimeter (ft)	Hydraulic Radius (ft)	Top Width (ft)
0.09	1.05	0.08	0.00
Critical Depth (ft)	Percent Full (%)	Critical Slope (ft/ft)	Velocity (ft/s)
0.33	100.0	0.07993	6.93

# Watershed Model Schematic

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4



## Legend

Hyd.	Origin	Description
1	SCS Runoff	PRE
2	SCS Runoff	POST UNDETAINED
3	SCS Runoff	POST DETAINED 1
4	SCS Runoff	POST DETAINED 2
5	Diversion1	VOLUME ABSTRACTION
6	Diversion2	POST AFTER BMP
7	Diversion1	VOLUME ABSTRACTION
8	Diversion2	POST AFTER BMP
9	Combine	POST AT POI



# Hydrograph Return Period Recap

Hydroflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SCS Runoff	-----	-----	1.688	-----	-----	3.430	-----	5.756	6.933	PRE
2	SCS Runoff	-----	-----	1.409	-----	-----	2.863	-----	4.805	5.786	POST UNDETAINED
3	SCS Runoff	-----	-----	0.396	-----	-----	0.683	-----	1.031	1.200	POST DETAINED 1
4	SCS Runoff	-----	-----	0.089	-----	-----	0.155	-----	0.237	0.277	POST DETAINED 2
5	Diversion1	3	-----	0.396	-----	-----	0.683	-----	0.584	0.455	VOLUME ABSTRACTION
6	Diversion2	3	-----	0.017	-----	-----	0.668	-----	1.031	1.200	POST AFTER BMP
7	Diversion1	4	-----	0.089	-----	-----	0.155	-----	0.237	0.277	VOLUME ABSTRACTION
8	Diversion2	4	-----	0.000	-----	-----	0.000	-----	0.004	0.009	POST AFTER BMP
9	Combine	2, 6, 8	-----	1.409	-----	-----	3.523	-----	5.805	6.948	POST AT POI

# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	1.688	2	720	3,914	-----	-----	-----	PRE	
2	SCS Runoff	1.409	2	720	3,267	-----	-----	-----	POST UNDETAINED	
3	SCS Runoff	0.396	2	716	800	-----	-----	-----	POST DETAINED 1	
4	SCS Runoff	0.089	2	716	179	-----	-----	-----	POST DETAINED 2	
5	Diversion1	0.396	2	716	542	3	-----	-----	VOLUME ABSTRACTION	
6	Diversion2	0.017	2	806	259	3	-----	-----	POST AFTER BMP	
7	Diversion1	0.089	2	716	179	4	-----	-----	VOLUME ABSTRACTION	
8	Diversion2	0.000	2	n/a	0	4	-----	-----	POST AFTER BMP	
9	Combine	1.409	2	720	3,525	2, 6, 8	-----	-----	POST AT POI	
Locke.gpw					Return Period: 2 Year			Friday, 10 / 21 / 2016		


# Hydrograph Report

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 1.688 cfs
Storm frequency	= 2 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 3,914 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 1

PRE

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 1.409 cfs
Storm frequency	= 2 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 3,267 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 2

POST UNDETAINED

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 0.396 cfs
Storm frequency	= 2 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 800 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.10 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 3

POST DETAINED 1

<u>Description</u>	<u>A</u>		<u>B</u>		<u>C</u>		<u>Totals</u>
<b>Sheet Flow</b>							
Manning's n-value	= 0.240		0.011		0.011		
Flow length (ft)	= 50.0		0.0		0.0		
Two-year 24-hr precip. (in)	= 2.67		0.00		0.00		
Land slope (%)	= 7.00		0.00		0.00		
<b>Travel Time (min)</b>	<b>= 5.44</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>5.44</b>
<b>Shallow Concentrated Flow</b>							
Flow length (ft)	= 90.00		30.00		0.00		
Watercourse slope (%)	= 2.20		3.30		0.00		
Surface description	= Paved		Unpaved		Paved		
Average velocity (ft/s)	=3.02		2.93		0.00		
<b>Travel Time (min)</b>	<b>= 0.50</b>	<b>+</b>	<b>0.17</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>0.67</b>
<b>Channel Flow</b>							
X sectional flow area (sqft)	= 0.09		0.00		0.00		
Wetted perimeter (ft)	= 1.05		0.00		0.00		
Channel slope (%)	= 13.60		0.00		0.00		
Manning's n-value	= 0.012		0.015		0.015		
Velocity (ft/s)	=8.83		0.00		0.00		
Flow length (ft)	{{0}}22.0		0.0		0.0		
<b>Travel Time (min)</b>	<b>= 0.04</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>0.04</b>
<b>Total Travel Time, Tc .....</b>							<b>6.10 min</b>

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.089 cfs
Storm frequency	= 2 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 179 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.40 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 4

POST DETAINED 2

<u>Description</u>	<u>A</u>		<u>B</u>		<u>C</u>		<u>Totals</u>
<b>Sheet Flow</b>							
Manning's n-value	= 0.150		0.011		0.011		
Flow length (ft)	= 50.0		0.0		0.0		
Two-year 24-hr precip. (in)	= 2.67		0.00		0.00		
Land slope (%)	= 3.00		0.00		0.00		
<b>Travel Time (min)</b>	<b>= 5.24</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>5.24</b>
<b>Shallow Concentrated Flow</b>							
Flow length (ft)	= 28.00		0.00		0.00		
Watercourse slope (%)	= 3.60		0.00		0.00		
Surface description	= Paved		Unpaved		Paved		
Average velocity (ft/s)	=3.86		0.00		0.00		
<b>Travel Time (min)</b>	<b>= 0.12</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>0.12</b>
<b>Channel Flow</b>							
X sectional flow area (sqft)	= 0.09		0.00		0.00		
Wetted perimeter (ft)	= 1.05		0.00		0.00		
Channel slope (%)	= 8.60		0.00		0.00		
Manning's n-value	= 0.012		0.015		0.015		
Velocity (ft/s)	=7.02		0.00		0.00		
Flow length (ft)	{{0}}35.0		0.0		0.0		
<b>Travel Time (min)</b>	<b>= 0.08</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>0.08</b>
<b>Total Travel Time, Tc .....</b>							<b>5.40 min</b>

# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.396 cfs
Storm frequency	= 2 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 542 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.017 cfs
Storm frequency	= 2 yrs	Time to peak	= 806 min
Time interval	= 2 min	Hyd. volume	= 259 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft





# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.089 cfs
Storm frequency	= 2 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 179 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.000 cfs
Storm frequency	= 2 yrs	Time to peak	= n/a
Time interval	= 2 min	Hyd. volume	= 0 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
Storm frequency = 2 yrs  
Time interval = 2 min  
Inflow hyds. = 2, 6, 8

Peak discharge = 1.409 cfs  
Time to peak = 720 min  
Hyd. volume = 3,525 cuft  
Contrib. drain. area = 1.060 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	3.430	2	720	7,852	-----	-----	-----	PRE	
2	SCS Runoff	2.863	2	720	6,554	-----	-----	-----	POST UNDETAINED	
3	SCS Runoff	0.683	2	716	1,400	-----	-----	-----	POST DETAINED 1	
4	SCS Runoff	0.155	2	716	318	-----	-----	-----	POST DETAINED 2	
5	Diversion1	0.683	2	716	547	3	-----	-----	VOLUME ABSTRACTION	
6	Diversion2	0.668	2	718	853	3	-----	-----	POST AFTER BMP	
7	Diversion1	0.155	2	716	318	4	-----	-----	VOLUME ABSTRACTION	
8	Diversion2	0.000	2	n/a	0	4	-----	-----	POST AFTER BMP	
9	Combine	3.523	2	718	7,406	2, 6, 8	-----	-----	POST AT POI	
Locke.gpw					Return Period: 10 Year			Friday, 10 / 21 / 2016		

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 3.430 cfs
Storm frequency	= 10 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 7,852 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 2.863 cfs
Storm frequency	= 10 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 6,554 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 0.683 cfs
Storm frequency	= 10 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 1,400 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.10 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.155 cfs
Storm frequency	= 10 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 318 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.40 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040





# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.683 cfs
Storm frequency	= 10 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 547 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.668 cfs
Storm frequency	= 10 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 853 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.155 cfs
Storm frequency	= 10 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 318 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.000 cfs
Storm frequency	= 10 yrs	Time to peak	= n/a
Time interval	= 2 min	Hyd. volume	= 0 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
 Storm frequency = 10 yrs  
 Time interval = 2 min  
 Inflow hyds. = 2, 6, 8

Peak discharge = 3.523 cfs  
 Time to peak = 718 min  
 Hyd. volume = 7,406 cuft  
 Contrib. drain. area = 1.060 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	5.756	2	718	13,180	-----	-----	-----	PRE	
2	SCS Runoff	4.805	2	718	11,001	-----	-----	-----	POST UNDETAINED	
3	SCS Runoff	1.031	2	716	2,157	-----	-----	-----	POST DETAINED 1	
4	SCS Runoff	0.237	2	716	494	-----	-----	-----	POST DETAINED 2	
5	Diversion1	0.584	2	710	596	3	-----	-----	VOLUME ABSTRACTION	
6	Diversion2	1.031	2	716	1,562	3	-----	-----	POST AFTER BMP	
7	Diversion1	0.237	2	716	432	4	-----	-----	VOLUME ABSTRACTION	
8	Diversion2	0.004	2	1042	61	4	-----	-----	POST AFTER BMP	
9	Combine	5.805	2	718	12,623	2, 6, 8	-----	-----	POST AT POI	
Locke.gpw					Return Period: 50 Year			Friday, 10 / 21 / 2016		

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 5.756 cfs
Storm frequency	= 50 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 13,180 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 4.805 cfs
Storm frequency	= 50 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 11,001 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060





# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 1.031 cfs
Storm frequency	= 50 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 2,157 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.10 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.237 cfs
Storm frequency	= 50 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 494 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.40 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.584 cfs
Storm frequency	= 50 yrs	Time to peak	= 710 min
Time interval	= 2 min	Hyd. volume	= 596 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 1.031 cfs
Storm frequency	= 50 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 1,562 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.237 cfs
Storm frequency	= 50 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 432 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.004 cfs
Storm frequency	= 50 yrs	Time to peak	= 1042 min
Time interval	= 2 min	Hyd. volume	= 61 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
Storm frequency = 50 yrs  
Time interval = 2 min  
Inflow hyds. = 2, 6, 8

Peak discharge = 5.805 cfs  
Time to peak = 718 min  
Hyd. volume = 12,623 cuft  
Contrib. drain. area = 1.060 ac



# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	6.933	2	718	15,918	-----	-----	-----	PRE	
2	SCS Runoff	5.786	2	718	13,286	-----	-----	-----	POST UNDETAINED	
3	SCS Runoff	1.200	2	716	2,534	-----	-----	-----	POST DETAINED 1	
4	SCS Runoff	0.277	2	716	582	-----	-----	-----	POST DETAINED 2	
5	Diversion1	0.455	2	706	583	3	-----	-----	VOLUME ABSTRACTION	
6	Diversion2	1.200	2	716	1,951	3	-----	-----	POST AFTER BMP	
7	Diversion1	0.277	2	716	433	4	-----	-----	VOLUME ABSTRACTION	
8	Diversion2	0.009	2	820	149	4	-----	-----	POST AFTER BMP	
9	Combine	6.948	2	718	15,386	2, 6, 8	-----	-----	POST AT POI	
Locke.gpw					Return Period: 100 Year			Friday, 10 / 21 / 2016		



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 6.933 cfs
Storm frequency	= 100 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 15,918 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 5.786 cfs
Storm frequency	= 100 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 13,286 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 1.200 cfs
Storm frequency	= 100 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 2,534 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 6.10 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.277 cfs
Storm frequency	= 100 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 582 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 5.40 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.455 cfs
Storm frequency	= 100 yrs	Time to peak	= 706 min
Time interval	= 2 min	Hyd. volume	= 583 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 1.200 cfs
Storm frequency	= 100 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 1,951 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.277 cfs
Storm frequency	= 100 yrs	Time to peak	= 716 min
Time interval	= 2 min	Hyd. volume	= 433 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.009 cfs
Storm frequency	= 100 yrs	Time to peak	= 820 min
Time interval	= 2 min	Hyd. volume	= 149 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft





# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
Storm frequency = 100 yrs  
Time interval = 2 min  
Inflow hyds. = 2, 6, 8


Peak discharge = 6.948 cfs  
Time to peak = 718 min  
Hyd. volume = 15,386 cuft  
Contrib. drain. area = 1.060 ac





# Watershed Model Schematic

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4



**Legend**

Hyd.	Origin	Description
1	SCS Runoff	PRE
2	SCS Runoff	POST UNDETAINED
3	SCS Runoff	POST DETAINED 1
4	SCS Runoff	POST DETAINED 2
5	Diversion1	VOLUME ABSTRACTION
6	Diversion2	POST AFTER BMP
7	Diversion1	VOLUME ABSTRACTION
8	Diversion2	POST AFTER BMP
9	Combine	POST AT POI



# Hydrograph Return Period Recap

Hydroflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SCS Runoff	-----	-----	1.688	-----	-----	-----	-----	-----	-----	PRE
2	SCS Runoff	-----	-----	1.409	-----	-----	-----	-----	-----	-----	POST UNDETAINED
3	SCS Runoff	-----	-----	0.213	-----	-----	-----	-----	-----	-----	POST DETAINED 1
4	SCS Runoff	-----	-----	0.039	-----	-----	-----	-----	-----	-----	POST DETAINED 2
5	Diversion1	3	-----	0.213	-----	-----	-----	-----	-----	-----	VOLUME ABSTRACTION
6	Diversion2	3	-----	0.024	-----	-----	-----	-----	-----	-----	POST AFTER BMP
7	Diversion1	4	-----	0.039	-----	-----	-----	-----	-----	-----	VOLUME ABSTRACTION
8	Diversion2	4	-----	0.000	-----	-----	-----	-----	-----	-----	POST AFTER BMP
9	Combine	2, 6, 8	-----	1.409	-----	-----	-----	-----	-----	-----	POST AT POI

# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	1.688	2	720	3,914	-----	-----	-----	PRE
2	SCS Runoff	1.409	2	720	3,267	-----	-----	-----	POST UNDETAINED
3	SCS Runoff	0.213	2	730	854	-----	-----	-----	POST DETAINED 1
4	SCS Runoff	0.039	2	738	191	-----	-----	-----	POST DETAINED 2
5	Diversion1	0.213	2	730	541	3	-----	-----	VOLUME ABSTRACTION
6	Diversion2	0.024	2	794	313	3	-----	-----	POST AFTER BMP
7	Diversion1	0.039	2	738	191	4	-----	-----	VOLUME ABSTRACTION
8	Diversion2	0.000	2	n/a	0	4	-----	-----	POST AFTER BMP
9	Combine	1.409	2	720	3,580	2, 6, 8	-----	-----	POST AT POI

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 1.688 cfs
Storm frequency	= 2 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 3,914 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 1

PRE

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 1.409 cfs
Storm frequency	= 2 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 3,267 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060





# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 2

POST UNDETAINED

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>


# Hydrograph Report

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 0.213 cfs
Storm frequency	= 2 yrs	Time to peak	= 730 min
Time interval	= 2 min	Hyd. volume	= 854 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 28.80 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170




# Hydrograph Report

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.039 cfs
Storm frequency	= 2 yrs	Time to peak	= 738 min
Time interval	= 2 min	Hyd. volume	= 191 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 38.90 min
Total precip.	= 2.67 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.213 cfs
Storm frequency	= 2 yrs	Time to peak	= 730 min
Time interval	= 2 min	Hyd. volume	= 541 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.024 cfs
Storm frequency	= 2 yrs	Time to peak	= 794 min
Time interval	= 2 min	Hyd. volume	= 313 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.039 cfs
Storm frequency	= 2 yrs	Time to peak	= 738 min
Time interval	= 2 min	Hyd. volume	= 191 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.000 cfs
Storm frequency	= 2 yrs	Time to peak	= n/a
Time interval	= 2 min	Hyd. volume	= 0 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
Storm frequency = 2 yrs  
Time interval = 2 min  
Inflow hyds. = 2, 6, 8

Peak discharge = 1.409 cfs  
Time to peak = 720 min  
Hyd. volume = 3,580 cuft  
Contrib. drain. area = 1.060 ac








# Watershed Model Schematic

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4



**Legend**

Hyd.	Origin	Description
1	SCS Runoff	PRE
2	SCS Runoff	POST UNDETAINED
3	SCS Runoff	POST DETAINED 1
4	SCS Runoff	POST DETAINED 2
5	Diversion1	VOLUME ABSTRACTION
6	Diversion2	POST AFTER BMP
7	Diversion1	VOLUME ABSTRACTION
8	Diversion2	POST AFTER BMP
9	Combine	POST AT POI



# Hydrograph Return Period Recap

Hydroflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SCS Runoff	-----	-----	-----	-----	-----	3.430	-----	-----	-----	PRE
2	SCS Runoff	-----	-----	-----	-----	-----	2.863	-----	-----	-----	POST UNDETAINED
3	SCS Runoff	-----	-----	-----	-----	-----	0.476	-----	-----	-----	POST DETAINED 1
4	SCS Runoff	-----	-----	-----	-----	-----	0.091	-----	-----	-----	POST DETAINED 2
5	Diversion1	3	-----	-----	-----	-----	0.476	-----	-----	-----	VOLUME ABSTRACTION
6	Diversion2	3	-----	-----	-----	-----	0.438	-----	-----	-----	POST AFTER BMP
7	Diversion1	4	-----	-----	-----	-----	0.091	-----	-----	-----	VOLUME ABSTRACTION
8	Diversion2	4	-----	-----	-----	-----	0.000	-----	-----	-----	POST AFTER BMP
9	Combine	2, 6, 8	-----	-----	-----	-----	2.863	-----	-----	-----	POST AT POI

# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	3.430	2	720	7,852	-----	-----	-----	PRE
2	SCS Runoff	2.863	2	720	6,554	-----	-----	-----	POST UNDETAINED
3	SCS Runoff	0.476	2	724	1,493	-----	-----	-----	POST DETAINED 1
4	SCS Runoff	0.091	2	728	333	-----	-----	-----	POST DETAINED 2
5	Diversion1	0.476	2	724	576	3	-----	-----	VOLUME ABSTRACTION
6	Diversion2	0.438	2	728	917	3	-----	-----	POST AFTER BMP
7	Diversion1	0.091	2	728	333	4	-----	-----	VOLUME ABSTRACTION
8	Diversion2	0.000	2	n/a	0	4	-----	-----	POST AFTER BMP
9	Combine	2.863	2	720	7,471	2, 6, 8	-----	-----	POST AT POI


# Hydrograph Report

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 3.430 cfs
Storm frequency	= 10 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 7,852 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 1

PRE

<u>Description</u>	<u>A</u>		<u>B</u>		<u>C</u>		<u>Totals</u>
<b>Sheet Flow</b>							
Manning's n-value	= 0.240		0.011		0.011		
Flow length (ft)	= 50.0		0.0		0.0		
Two-year 24-hr precip. (in)	= 2.67		0.00		0.00		
Land slope (%)	= 8.00		0.00		0.00		
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>5.15</b>
<b>Shallow Concentrated Flow</b>							
Flow length (ft)	= 343.00		0.00		0.00		
Watercourse slope (%)	= 2.90		0.00		0.00		
Surface description	= Unpaved		Paved		Paved		
Average velocity (ft/s)	=2.75		0.00		0.00		
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>2.08</b>
<b>Channel Flow</b>							
X sectional flow area (sqft)	= 0.00		0.00		0.00		
Wetted perimeter (ft)	= 0.00		0.00		0.00		
Channel slope (%)	= 0.00		0.00		0.00		
Manning's n-value	= 0.015		0.015		0.015		
Velocity (ft/s)	=0.00		0.00		0.00		
Flow length (ft)	{{0}}0.0		0.0		0.0		
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+</b>	<b>0.00</b>	<b>+</b>	<b>0.00</b>	<b>=</b>	<b>0.00</b>
<b>Total Travel Time, Tc .....</b>							<b>7.20 min</b>

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 2.863 cfs
Storm frequency	= 10 yrs	Time to peak	= 720 min
Time interval	= 2 min	Hyd. volume	= 6,554 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 2

POST UNDETAINED

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>




# Hydrograph Report

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 0.476 cfs
Storm frequency	= 10 yrs	Time to peak	= 724 min
Time interval	= 2 min	Hyd. volume	= 1,493 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 19.30 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170




# Hydrograph Report

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.091 cfs
Storm frequency	= 10 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 333 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 24.65 min
Total precip.	= 3.86 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.476 cfs
Storm frequency	= 10 yrs	Time to peak	= 724 min
Time interval	= 2 min	Hyd. volume	= 576 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.438 cfs
Storm frequency	= 10 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 917 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.091 cfs
Storm frequency	= 10 yrs	Time to peak	= 728 min
Time interval	= 2 min	Hyd. volume	= 333 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.000 cfs
Storm frequency	= 10 yrs	Time to peak	= n/a
Time interval	= 2 min	Hyd. volume	= 0 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
 Storm frequency = 10 yrs  
 Time interval = 2 min  
 Inflow hyds. = 2, 6, 8

Peak discharge = 2.863 cfs  
 Time to peak = 720 min  
 Hyd. volume = 7,471 cuft  
 Contrib. drain. area = 1.060 ac








# Watershed Model Schematic

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4



**Legend**

Hyd.	Origin	Description
1	SCS Runoff	PRE
2	SCS Runoff	POST UNDETAINED
3	SCS Runoff	POST DETAINED 1
4	SCS Runoff	POST DETAINED 2
5	Diversion1	VOLUME ABSTRACTION
6	Diversion2	POST AFTER BMP
7	Diversion1	VOLUME ABSTRACTION
8	Diversion2	POST AFTER BMP
9	Combine	POST AT POI



# Hydrograph Return Period Recap

Hydroflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description	
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr		
1	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	5.756	-----	PRE
2	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	4.805	-----	POST UNDETAINED
3	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	0.785	-----	POST DETAINED 1
4	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	0.167	-----	POST DETAINED 2
5	Diversion1	3	-----	-----	-----	-----	-----	-----	-----	0.491	-----	VOLUME ABSTRACTION
6	Diversion2	3	-----	-----	-----	-----	-----	-----	-----	0.785	-----	POST AFTER BMP
7	Diversion1	4	-----	-----	-----	-----	-----	-----	-----	0.167	-----	VOLUME ABSTRACTION
8	Diversion2	4	-----	-----	-----	-----	-----	-----	-----	0.005	-----	POST AFTER BMP
9	Combine	2, 6, 8	-----	-----	-----	-----	-----	-----	-----	5.515	-----	POST AT POI

# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	5.756	2	718	13,180	-----	-----	-----	PRE
2	SCS Runoff	4.805	2	718	11,001	-----	-----	-----	POST UNDETAINED
3	SCS Runoff	0.785	2	722	2,244	-----	-----	-----	POST DETAINED 1
4	SCS Runoff	0.167	2	724	527	-----	-----	-----	POST DETAINED 2
5	Diversion1	0.491	2	714	543	3	-----	-----	VOLUME ABSTRACTION
6	Diversion2	0.785	2	722	1,701	3	-----	-----	POST AFTER BMP
7	Diversion1	0.167	2	724	432	4	-----	-----	VOLUME ABSTRACTION
8	Diversion2	0.005	2	942	94	4	-----	-----	POST AFTER BMP
9	Combine	5.515	2	720	12,796	2, 6, 8	-----	-----	POST AT POI

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 5.756 cfs
Storm frequency	= 50 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 13,180 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 1

PRE

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 4.805 cfs
Storm frequency	= 50 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 11,001 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 2

POST UNDETAINED

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>


# Hydrograph Report

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 0.785 cfs
Storm frequency	= 50 yrs	Time to peak	= 722 min
Time interval	= 2 min	Hyd. volume	= 2,244 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 14.80 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170






# Hydrograph Report

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.167 cfs
Storm frequency	= 50 yrs	Time to peak	= 724 min
Time interval	= 2 min	Hyd. volume	= 527 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 17.99 min
Total precip.	= 5.28 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.491 cfs
Storm frequency	= 50 yrs	Time to peak	= 714 min
Time interval	= 2 min	Hyd. volume	= 543 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.785 cfs
Storm frequency	= 50 yrs	Time to peak	= 722 min
Time interval	= 2 min	Hyd. volume	= 1,701 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.167 cfs
Storm frequency	= 50 yrs	Time to peak	= 724 min
Time interval	= 2 min	Hyd. volume	= 432 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.005 cfs
Storm frequency	= 50 yrs	Time to peak	= 942 min
Time interval	= 2 min	Hyd. volume	= 94 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
Storm frequency = 50 yrs  
Time interval = 2 min  
Inflow hyds. = 2, 6, 8


Peak discharge = 5.515 cfs  
Time to peak = 720 min  
Hyd. volume = 12,796 cuft  
Contrib. drain. area = 1.060 ac





# Watershed Model Schematic

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4



## Legend

Hyd.	Origin	Description
1	SCS Runoff	PRE
2	SCS Runoff	POST UNDETAINED
3	SCS Runoff	POST DETAINED 1
4	SCS Runoff	POST DETAINED 2
5	Diversion1	VOLUME ABSTRACTION
6	Diversion2	POST AFTER BMP
7	Diversion1	VOLUME ABSTRACTION
8	Diversion2	POST AFTER BMP
9	Combine	POST AT POI





# Hydrograph Return Period Recap

Hydroflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	6.933	PRE
2	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	5.786	POST UNDETAINED
3	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	0.916	POST DETAINED 1
4	SCS Runoff	-----	-----	-----	-----	-----	-----	-----	-----	0.211	POST DETAINED 2
5	Diversion1	3	-----	-----	-----	-----	-----	-----	-----	0.383	VOLUME ABSTRACTION
6	Diversion2	3	-----	-----	-----	-----	-----	-----	-----	0.916	POST AFTER BMP
7	Diversion1	4	-----	-----	-----	-----	-----	-----	-----	0.211	VOLUME ABSTRACTION
8	Diversion2	4	-----	-----	-----	-----	-----	-----	-----	0.012	POST AFTER BMP
9	Combine	2, 6, 8	-----	-----	-----	-----	-----	-----	-----	6.595	POST AT POI

# Hydrograph Summary Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description
1	SCS Runoff	6.933	2	718	15,918	-----	-----	-----	PRE
2	SCS Runoff	5.786	2	718	13,286	-----	-----	-----	POST UNDETAINED
3	SCS Runoff	0.916	2	722	2,636	-----	-----	-----	POST DETAINED 1
4	SCS Runoff	0.211	2	722	605	-----	-----	-----	POST DETAINED 2
5	Diversion1	0.383	2	710	544	3	-----	-----	VOLUME ABSTRACTION
6	Diversion2	0.916	2	722	2,092	3	-----	-----	POST AFTER BMP
7	Diversion1	0.211	2	722	433	4	-----	-----	VOLUME ABSTRACTION
8	Diversion2	0.012	2	802	172	4	-----	-----	POST AFTER BMP
9	Combine	6.595	2	718	15,550	2, 6, 8	-----	-----	POST AT POI

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 1

PRE

Hydrograph type	= SCS Runoff	Peak discharge	= 6.933 cfs
Storm frequency	= 100 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 15,918 cuft
Drainage area	= 1.270 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.200 x 71) + (0.950 x 78) + (0.120 x 77)] / 1.270



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 1

PRE

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+ 0.00</b>	<b>+ 0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>

# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4


Friday, 10 / 21 / 2016

## Hyd. No. 2

### POST UNDETAINED

Hydrograph type	= SCS Runoff	Peak discharge	= 5.786 cfs
Storm frequency	= 100 yrs	Time to peak	= 718 min
Time interval	= 2 min	Hyd. volume	= 13,286 cuft
Drainage area	= 1.060 ac	Curve number	= 77*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 7.20 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.140 x 71) + (0.800 x 78) + (0.110 x 77) + (0.010 x 89)] / 1.060



# TR55 Tc Worksheet

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

## Hyd. No. 2

POST UNDETAINED

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
<b>Sheet Flow</b>				
Manning's n-value	= 0.240	0.011	0.011	
Flow length (ft)	= 50.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.67	0.00	0.00	
Land slope (%)	= 8.00	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 5.15</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 5.15</b>
<b>Shallow Concentrated Flow</b>				
Flow length (ft)	= 343.00	0.00	0.00	
Watercourse slope (%)	= 2.90	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.75	0.00	0.00	
<b>Travel Time (min)</b>	<b>= 2.08</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 2.08</b>
<b>Channel Flow</b>				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
<b>Travel Time (min)</b>	<b>= 0.00</b>	<b>+</b> <b>0.00</b>	<b>+</b> <b>0.00</b>	<b>= 0.00</b>
<b>Total Travel Time, Tc .....</b>				<b>7.20 min</b>


# Hydrograph Report

## Hyd. No. 3

### POST DETAINED 1

Hydrograph type	= SCS Runoff	Peak discharge	= 0.916 cfs
Storm frequency	= 100 yrs	Time to peak	= 722 min
Time interval	= 2 min	Hyd. volume	= 2,636 cuft
Drainage area	= 0.170 ac	Curve number	= 86*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 13.60 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.030 x 71) + (0.020 x 78) + (0.030 x 89) + (0.090 x 91)] / 0.170




# Hydrograph Report

## Hyd. No. 4

### POST DETAINED 2

Hydrograph type	= SCS Runoff	Peak discharge	= 0.211 cfs
Storm frequency	= 100 yrs	Time to peak	= 722 min
Time interval	= 2 min	Hyd. volume	= 605 cuft
Drainage area	= 0.040 ac	Curve number	= 85*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 16.20 min
Total precip.	= 5.97 in	Distribution	= Type II
Storm duration	= 24 hrs	Shape factor	= 484

\* Composite (Area/CN) = [(0.020 x 91) + (0.020 x 78)] / 0.040





# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 5

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.383 cfs
Storm frequency	= 100 yrs	Time to peak	= 710 min
Time interval	= 2 min	Hyd. volume	= 544 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 6
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 6

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.916 cfs
Storm frequency	= 100 yrs	Time to peak	= 722 min
Time interval	= 2 min	Hyd. volume	= 2,092 cuft
Inflow hydrograph	= 3 - POST DETAINED 1	2nd diverted hyd.	= 5
Diversion method	= First Flush Volume	Volume Up To	= 540.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 7

### VOLUME ABSTRACTION

Hydrograph type	= Diversion1	Peak discharge	= 0.211 cfs
Storm frequency	= 100 yrs	Time to peak	= 722 min
Time interval	= 2 min	Hyd. volume	= 433 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 8
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report


Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 8

### POST AFTER BMP

Hydrograph type	= Diversion2	Peak discharge	= 0.012 cfs
Storm frequency	= 100 yrs	Time to peak	= 802 min
Time interval	= 2 min	Hyd. volume	= 172 cuft
Inflow hydrograph	= 4 - POST DETAINED 2	2nd diverted hyd.	= 7
Diversion method	= First Flush Volume	Volume Up To	= 432.00 cuft



# Hydrograph Report

Hydraflow Hydrographs Extension for AutoCAD® Civil 3D® 2015 by Autodesk, Inc. v10.4

Friday, 10 / 21 / 2016

## Hyd. No. 9

POST AT POI

Hydrograph type = Combine  
Storm frequency = 100 yrs  
Time interval = 2 min  
Inflow hyds. = 2, 6, 8

Peak discharge = 6.595 cfs  
Time to peak = 718 min  
Hyd. volume = 15,550 cuft  
Contrib. drain. area = 1.060 ac

