



NOTE: FOR EASE OF CONSTRUCTION ASSOCIATED WITH SIDESLOPES, CUSHION GEOTEXTILE CAN BE DEPLOYED ALONG SLOPE RATHER THAN DOWN SLOPE SO LONG AS DEPLOYMENT DOES NOT EXCEED 20 VERTICAL FEET. IN THIS INSTANCE, IT IS NOT NECESSARY THAT THE OVERLAP BETWEEN ADJACENT ROLLS OF CUSHION BE SEAMED SO LONG AS CONSTRUCTION QUALITY ASSURANCE PERSONNEL ENSURE A MINIMUM OF 1 FT. OF CONTINUOUS OVERLAP. IN SUCH INSTANCES, SEEMS SHALL BE SUPPLEMENTED WITH SANDBAGS, DUCT TAPE, HEAT TACKS OR OTHER METHODS APPROVED BY THE QUALITY ASSURANCE ENGINEER TO HELP ENSURE THAT CUSHION GEOTEXTILE DOES NOT ROLL UP AND LOSE ITS OVERLAP DURING PUSHING OF PROTECTIVE COVER.

2 TEMPORARY SIDE SLOPE DIVERSION BERM (OPTION 2) 8C NOT TO SCALE

		REVISIONS		
<u>S</u>				
L L L L L L L L L L L L L L L L L L L				
5				
GR				
Environmental Consultan	ts			
DELAWARE COUNTY SOLID WASTE AUTHORITY ROLLING HILLS LANDFILL SOUTHERN AREA LANDFILL EXPANSION			DATE:	
			09/25/17	
			DRAWN BY:	
			SWH	
EARL TOWNSHIP	BERKS COUNTY	PENNSYLVANIA	CHECKED:	
			КСС	
LANDFILL LINER, CAP AND BERM DETAILS SHEET 3			BAI DRAWING NO:	
			DCSWA-107D017C	
State College Office	D	elaware Valley Office	SHEET NO.	

