



Transcontinental Gas Pipe Line Company, LLC

**Requirement M - Erosion and Sediment Control Plan
Narrative and Drawings**

(as provided in the ESCGP-3 Application)

**Regional Energy Access Expansion Project –
Effort Loop**

April 2021

TABLE OF CONTENTS

Sections

1. Project Description (NOI Checklist Item 3.n)
 - 1.1 MLV-505LD86
 - 1.2 Contractor Yards
2. Topographic Features of the Area (NOI Checklist Item 3.a, 7.a)
3. Receiving Surface Waters (NOI Checklist Item 3.e, 7.e)
4. Types, Depth, Slope, Locations & Limitation of the Soils and Geologic Formations (NOI Checklist Item 3.b, 3.l, 7.b, 7.l)
 - 4.1 Resolutions to Soil Limitations
 - 4.2 Geologic Formations
5. Characterizations of Earth Disturbance Activities, Including Past, Present, and Proposed Land Uses (NOI Checklist Item 3.c, 7.c)
6. Erosion and Sediment Control Best Management Practices (NOI Checklist Item 3.f, 7.f)
7. Recycling and Disposal of Materials (NOI Checklist Item 3.k, 7.k)
8. Thermal Impacts (NOI Checklist Item 3.m, 7.m)
9. Antidegradation Requirements (NOI Checklist Item 3.p, 7.o)
10. Riparian Buffers (NOI Checklist Item 3.o, 7.n)
11. Project Site Runoff (NOI Checklist Item 3.d, 7.d)
 - 11.1 MLV-505LD86
12. Offsite Discharge Analysis
 - 12.1 MLV-505LD86
13. Site Restoration Plan
 - 13.1 Previous Land Use
 - 13.2 Disturbance Activities, Changes to Permanent Topographic Land Cover Along Pipeline Alignment
 - 13.3 Restoration Measures
 - 13.4 Maintenance and Evaluation for Effectiveness
14. The Erosion and Sediment Control Plan Shall be Prepared by a Person Trained and Experienced in Erosion Control Methods and Techniques

Attachments

- 1 Project Location Map
- 2 Soils Map and Report
- 3 E&SC and SR Plan BMP Design Worksheets and Calculations
 - 3.1 Compost Filter Sock
 - 3.2 CN Table
 - 3.3 Channel
 - 3.4 Level Spreader
 - 3.5 Sediment Trap
 - 3.6 Channel Design
 - 3.7 Riprap Apron
- 4 Offsite Discharge Report

Drawings

- 1 of 53 Erosion and Sediment Control Plan - Cover
- 2 of 53 Erosion and Sediment Control Plan - Index
- 3 - 34 of 53 Erosion and Sediment Control Plan - Site Plans
- 35 of 53 Erosion and Sediment Control Plan - Sugar Hollow Main Line Valve Site Plan
- 36 - 38 of 53 Erosion and Sediment Control Plan - Notes
- 39 - 53 of 53 Erosion and Sediment Control Plan - Details

SECTION 2.2.1
NARRATIVE

1. Project Description (NOI Checklist Item 3.n)

Transcontinental Gas Pipe Line Company, LLC (Transco), indirectly owned by the Williams Companies, Inc. (Williams) is seeking authorization from the Federal Energy Regulatory Commission (FERC) under Section 7(c) of the Natural Gas Act and Part 157 of the Commission's regulations, to construct, own, operate, and maintain the proposed Project facilities associated with the Regional Energy Access Expansion Project (Project). The Project is an expansion of Transco's existing natural gas transmission system that will enable Transco to provide an incremental 829,400 dekatherms per day (Dth/d) of year-round firm transportation capacity from the Marcellus Shale production area in northeastern Pennsylvania to multiple delivery points along Transco's Leidy Line in PA and Mainline in PA, NJ, and MD.

The Effort Loop component of the Project will consist of approximately 13.8 miles of 42-inch pipeline co-located with existing Transco Leidy Lines between Mileposts 43.72 and 57.50 in Ross, Chestnuthill and Tunkhannock Townships, Monroe County. The new pipeline will tie-in to the existing 42-in Leidy Line "D" on both ends, completing the segment. With the segment completed, the existing pig traps (industry term for manifolds that launch or receive in-line inspection tools) at both tie-ins will no longer be needed and will therefore be removed, while the existing mainline valves will remain. Transco will be installing a new mainline valve and appurtenant equipment at Milepost 49.6 off of Sugar Hollow Road. The valve installation is a means to isolate gas flows. One Contractor Yard is proposed at the east end of the pipeline at MP 43.72 (CY-MO-001). One remote anode groundbed is proposed at MP 43.72.

The E&SC and SR Plan shall be designed and implemented to be consistent with the Post Construction Stormwater Management (PCSM) Plan under 25 Pa. Code § 102.8 (relating to PCSM requirements). Transco will use and implement the practices, measures and details outlined herein to control soil erosion and off-site sedimentation. The work and disturbed areas are located within Transco property, existing easements or legally obtained workspace. The limit of disturbance (LOD) for the Effort Loop Pipeline will be approximately 262.2 acres. Subject to FERC's certification of the Project and receipt of the necessary permits and authorizations, Transco anticipates construction of the Project to start in third quarter 2022 to meet a proposed in-service date of December 1, 2023.

1.1 MLV-505LD86

The mainline valve site, MLV-505LD86, is located at milepost 49.6 on the Effort Loop Pipeline. During construction of the Effort Loop Pipeline, two temporary freshwater storage tanks

will be placed adjacent to the valve. These tanks will provide water for hydrostatic testing of the pipeline before it is placed into service. The overall temporary earth disturbance at the site is approximately 8.64 acres. Upon completion of construction activities, the majority of the site will be restored to original conditions.

Proposed E&S Best Management Practices (BMP's) for MLV-505LD86 include rock construction entrances, compost filter socks, diversion and collection channels, and level spreaders. E&S BMP's have been designed in accordance with the PaDEP E&S BMP Manual. Design calculations, where needed, are provided in this document as attachments. E&S BMP's are depicted in the Effort Loop E&S Plans.

Upon completion of construction, the increased impervious area of MLV-505LD86 site will utilize several PCSM BMP's to control stormwater runoff, attenuate peak flow rate and volume, and provide infiltration. Excess stormwater runoff will be directed to the basin and berms, via a series of collection channels, for infiltration and controlled discharge. BMP design calculations and drawings are provided in Attachment 4 and PCSM Plan set.

1.2 Contractor Yards

One contractor yard, CY-MO-001, is proposed for the Effort Loop Pipeline project. It is located at the east end of Effort Loop Pipeline at MP 43.72. The yard is a temporary facility with an approximate disturbance of 51 acres.

Proposed E&S BMP's include rock construction entrances, compost filter socks, and compost filter sock sediment traps. E&S BMP's have been designed in accordance with the PaDEP E&S BMP Manual. Design calculations, where needed, are provided in this document as attachments. E&S BMP's are depicted in the Effort Loop E&S Plans.

Upon completion of construction, CY-MO-001 will be restored to original conditions. No permanent features are proposed at the yard.

2. Topographic Features of the Area (NOI Checklist Item 3.a, 7.a)

A Project Location Map for the Effort Loop Pipeline is included in Attachment 1. This map shows the topographical features of the general site vicinity and is based on the USGS 7.5 Minute topographical mapping of the Blakeslee, Brodheads ville, Pocono Pines, and Saylorburg, Pennsylvania quadrangles.

3. Receiving Surface Waters (NOI Checklist Item 3.e, 7.e)

The following table (Table 1) list each watershed located Effort Loop Pipeline Project Area, its Chapter 93 Water Quality Standards, and Pennsylvania Fish and Boat Commission classifications. A Wetland and Watercourse Delineation Report is included in Attachment A of the ESCGP-3 permit application.

Table 1 – Receiving Waters			
Watershed Name	Designated Use	Existing Use	PFBC Classification
Lake Creek	HQ-CWF, MF	-	Naturally Producing Wild Trout Stream
Princess Run	CWF, MF	-	Naturally Producing Wild Trout Stream
Weir Creek	CWF, MF	-	Class A Wild Trout
Trib 04904 to McMichael Creek	HQ-CWF, MF	-	Naturally Producing Wild Trout Stream
McMichael Creek	EV, MF	-	Naturally Producing Wild Trout Stream
Trib 04017 to Weir Creek	CWF, MF	-	Class A Wild Trout
Trib 04910 & 04911 to McMichael Creek	EV, MF	-	Naturally Producing Wild Trout Stream
Trib 04022 to Pohopoco Creek	CWF, MF	-	Class A Wild Trout
Sugar Hollow Creek	CWF, MF	-	Class A Wild Trout
Poplar Creek & Trib 04032 to Poplar Creek	CWF, MF	EV, MF	Class A Wild Trout
Mud Run	HQ-CWF, MF	-	Naturally Producing Wild Trout Stream
Mud Pond Run	HQ-CWF, MF	EV, MF	Naturally Producing Wild Trout Stream
Tunkhannock Creek & Trib 04390 to Tunkhannock Creek	HQ-CWF, MF	-	Naturally Producing Wild Trout Stream
EV: Exceptional Value, MF: Migratory Fishes, HQ-CWF: High Quality- Cold Water fishes			

4. Types, Depth, Slope, Locations & Limitation of the Soils and Geologic Formations (NOI Checklist Item 3.b, 3.i, 7.b, 7.i)

The soil associations on site were identified by soil map units as mapped in the Web Soil Survey website (<https://websoilsurvey.sc.egov.usda.gov/>) by the United States Dept. of Agriculture (USDA), Natural Resources Conservation Service (NRCS). There are 55 soil mapping units located within the LOD, see Table 2 below:

Regional Energy Access Expansion Project
 ESCGP-3 Permit Application
 Transcontinental Gas Pipe Line Company, LLC
 Section 2-2 E&SC/SR Plan Narrative for Effort Loop

Table 2 – Soils mapping units within the LOD	
Soil Mapping Unit	Soil Series
AnB	Allenwood gravelly silt loam, 3 to 8 percent slopes
AwB	Alvira and Watson very stony loams, 0 to 12 percent slopes
BbC	Bath channery silt loam, 8 to 25 percent slopes, extremely stony
BrA	Braceville gravelly loam, 0 to 3 percent slopes
BrB	Braceville gravelly loam, 3 to 8 percent slopes
BxB	Buchanan channery loam, 8 to 25 percent slopes, rubbly
BxC	Buchanan channery loam, 8 to 25 percent slopes, rubbly
ChA	Chenango gravelly loam, 0 to 3 percent slopes
ChB	Chenango gravelly loam, 3 to 8 percent slopes
ChC	Chenango gravelly loam, 8 to 15 percent slopes
CnB	Chippewa and Norwich soils, 0 to 8 percent slopes, extremely stony
CpA	Clymer loam, 0 to 3 percent slopes
CxB	Clymer extremely stony loam, 0 to 8 percent slopes
Cy	Cut and fill land
DxB	Dekalb channery loam, 0 to 8 percent slopes, rubbly
DxC	Dekalb very channery loam, 8 to 25 percent slopes, extremely stony
DxE	Dekalb very stony loam, 25 to 100 percent slopes, very stony
GP	Pit, Shale, and Gravel
HaB	Hartleton channery silt loam, 2 to 8 percent slopes
HaC	Hartleton channery silt loam, 8 to 20 percent slopes
Hy	Holly silt loam
KaB	Kedron silt loam, 2 to 8 percent slopes
KvB	Klinesville channery silt loam, 3 to 8 percent slopes
KvC	Klinesville channery silt loam, 8 to 15 percent slopes
KvD	Klinesville channery silt loam, 15 to 25 percent slopes
LgB	Laidig extremely stony loam, 0 to 8 percent slopes
LgC	Laidig extremely stony loam, 8 to 25 percent slopes
LkB	Leck kill channery silt loam, 2 to 8 percent slopes
LkC	Leck kill channery silt loam, 8 to 15 percent slopes
LkD	Leck kill channery silt loam, 15 to 25 percent slopes
LsC	Lordstown channery silt loam, 8 to 15 percent slopes
LxC	Lordstown channery silt loam, 8 to 25 percent slopes, rubbly
MeA	Meckesville gravelly loam, 0 to 3 percent slopes
MeB	Meckesville gravelly loam, 3 to 8 percent slopes
MeC	Meckesville gravelly loam, 8 to 15 percent slopes
MfB	Meckesville very stony loam, 0 to 8 percent slopes
MoB	Morris channery silt loam, 0 to 8 percent slopes
Pp	Pope silt loam, high bottom

Regional Energy Access Expansion Project
 ESCGP-3 Permit Application
 Transcontinental Gas Pipe Line Company, LLC
 Section 2-2 E&SC/SR Plan Narrative for Effort Loop

ReA	Rexford gravelly silt loam, 0 to 3 percent slopes
SpB	Shelmadine very stony silt loam, 0 to 8 percent slopes
VaE	Very stony land and Rock outcrops, steep
W	Water
WaB	Watson silt loam, 2 to 8 percent slopes
Wb	Wayland silt clay loam
WeB3	Weikert channery silt loam, 3 to 8 percent slopes, eroded
WeC3	Weikert channery silt loam, 8 to 15 percent slopes, eroded
WeD3	Weikert channery silt loam, 15 to 25 percent slopes, eroded
WhB	Weiker-Hartleton channery silt loams, 3 to 8 percent slopes
WhC	Weiker-Hartleton channery silt loams, 8 to 15 percent slopes
WhD	Weiker-Hartleton channery silt loams, 15 to 25 percent slopes
WKE	Weikert and Klinesville soils, steep
WyA	Wyoming gravelly sandy loam, 0 to 3 percent slopes
WyB	Wyoming gravelly sandy loam, 3 to 8 percent slopes
WyC	Wyoming gravelly sandy loam, 8 to 15 percent slopes
WyD	Wyoming gravelly sandy loam, 15 to 25 percent slopes

Detailed descriptions and mapping of soil mapping units are provided in the Attachment 2. Soil use limitations (outlined in Table 3) were reviewed in relation to the Effort Loop Pipeline and resolutions were identified in Section 4.1.

SOIL NAME	SOIL WITH SLOPE CLASS	CUTBANKS CAVE	CORROSIVE TO CONCRETE/STEEL	DROUGHTY	EASILY ERODIBLE	FLOODING	DEPTH TO SATURATED ZONE/ SEASONAL HIGH WATER TABLE	HYDRIC/ HYDRIC INCLUSIONS	LOW STRENGTH / LANDSLIDE PRONE	SLOW PERCOLATION	PIPING	POOR SOURCE OF TOPSOIL	FROST ACTION	SHRINK - SWELL	POTENTIAL SINKHOLE	PONDING	WETNESS
Allenwood	AnB	X	C/S					X	X	X	X	X	X				
Alvira	AwB	X	C/S	X	X		X	X	X	X	X	X	X				X
Bath	BbC	X	C/S				X	X		X		X	X				
Braceville	BrA, BrB	X	C/S	X	X		X	X	X	X	X	X	X				X
Buchanan	BxB, BxC	X	C/S	X	X		X	X	X	X	X	X	X				X
Chenango	ChA, ChB, ChC	X	C	X		X	X	X		X	X	X	X				
Chippewa	CnB	X	C/S	X	X		X	X	X	X	X		X	X		X	

Table 3 – Limitations of Pennsylvania Soils Pertaining to Earth Disturbance Projects (Erosion and Sediment Control Best Management Practice (BMP) Manual – Technical Guidance Number 363-3134-008/Page 401)

SOIL NAME	SOIL WITH SLOPE CLASS	CUTBANKS CAVE	CORROSIVE TO CONCRETE/STEEL	DROUGHTY	EASILY ERODIBLE	FLOODING	DEPTH TO SATURATED ZONE/ SEASONAL HIGH WATER TABLE	HYDRIC/ HYDRIC INCLUSIONS	LOW STRENGTH / LANDSLIDE PRONE	SLOW PERCOLATION	PIPING	POOR SOURCE OF TOPSOIL	FROST ACTION	SHRINK - SWELL	POTENTIAL SINKHOLE	PONDING	WETNESS
Clymer	CpA, CxB	X	C	X	X			X	X	X	X	X	X				X
Cut and Fill	Cy																
Dekalb	DxB, DxC, DxE	X	C	X					X	X	X	X	X				
Pit, Shale and Gravel	GP																
Hartleton	HaB, HaC	X	C	X					X	X	X	X	X				
Holly	Hy	X	C/S			X	X	X	X	X	X	X	X			X	X
Kedron	KaB	X	C/S				X	X	X	X	X	X	X				X
Klinesville	KvB, KvC, KvD	X	C/S	X	X			X		X		X	X				
Laidig	LgB, LgC	X	C/S	X	X		X	X	X	X	X	X	X				
Leck Kill	LkB, LkC, LkD	X	C						X	X	X	X	X				X
Lordstown	LsC, LxC	X	C	X	X				X	X	X		X				
Meckesville	MeA, MeB, MeC, MfB	X	C/S				X		X	X	X	X	X				X
Morris	MoB	X	C/S	X	X		X	X	X	X		X	X				X
Pope	Pp	X	C/S		X	X		X	X	X	X	X	X				
Rexford	ReA	X	C/S	X		X	X	X	X	X	X	X	X				X
Shelmadine	SpB	X	C/S	X			X	X	X	X	X	X	X				
Very Stony	VaE																
Water	W																
Watson	WaB	X	C/S	X			X	X	X	X	X		X	X			
Wayland	Wb	X	S		X	X	X	X	X	X	X	X	X			X	X
Weikert	WeB3, WeC3, WeD3, WhB, WhC, WhD, WKE	X	C/S	X				X	X	X	X	X	X				
Wyoming	WyA, WyB, WyC, WyD	X	C	X				X		X		X					

4.1 Resolution of Soil Limitations

Transco proposes the following resolutions to compensate for soil limitations summarized in Table 3 above:

1. To offset the caving of cutbanks, trenching operations will be conducted in accordance with the OSHA Technical Manual for Trenching.

2. Preventative coatings shall be used to prevent corrosion of concrete and/ or steel.
3. When bedrock is encountered it will be removed by mechanical methods or blasting. Blasting operations will conform with local, state, and federal regulations.
4. Precautions will be taken to prevent slope failure when working within low strength soils by flattening cut / fill slopes, not overloading, maintaining lateral support, and preventing saturation of soils. Low strength soils will not be used for roadway construction.
5. Excavation in soils prone to flooding, slow percolation, ponding, wetness, located in a seasonal high water table, or which are hydric, will likely encounter water. Compensation will involve dewatering with appropriate means such as pump water filter bags, sediment traps, etc.
6. Soils that have the potential to swell, shrink, or heave due to frost action may cause damage to roadways or pads. Where foundations are critical, compensation may require removal and replacement of soils with suitable material.
7. In circumstances where soils appear to be a poor source of topsoil, drought or prone to wetness, soil testing will be performed to determine the appropriate applications of soil amendments to promote growth. Soils onsite that are fair sources of topsoil, will be identified, stripped and stockpiled for use during restoration.
8. In order to minimize erosion of soils that are easily erodible, compensation may involve providing a protective lining, to apply seed, mulch, erosion control blankets (either in rolls or hydraulically applied), tracking slopes, upstream diversions, waterbars, etc. to minimize soil erosion.

4.2 Geologic Formations

Transco retained Civil & Environmental Consultants, Inc. (CEC) of Pittsburgh, PA to perform a geohazard assessment, the following is provided from their 2020 report. Transco utilized United States Geological Survey (USGS), Geologic Map of Pennsylvania - Map 1, dated 1980 (online), to evaluate geologic hazards on the Project. The desktop analysis completed for the Project by CEC revealed that the Effort Loop Pipeline does not cross any known, mapped, or inferred faults. No mines or Karst formations were identified in the site vicinity. However, the analysis outlined that Effort Loop Pipeline lies within a zone of moderate to high landslide incidence and susceptibility.

Due to the moderate to high landslide incidence and susceptibility, a Geological Hazard Assessment and Mitigation Plan was completed by CEC and is submitted with this application (Attachment B). The Geological Hazard Assessment and Mitigation Plan identifies appropriate best management practices to avoid and mitigate for conditions encountered during construction.

5. Characterizations of Earth Disturbance Activities, Including Past, Present, and Proposed Land Uses (NOI Checklist Item 3.c, 7.c)

The Effort Loop Pipeline will consist of approximately 13.8 miles of 42-inch pipeline co-located with existing Transco Leidy Lines between Mileposts 43.72 and 57.50 in Ross, Chestnuthill and Tunkhannock Townships, Monroe County. The new pipeline will tie-in to the existing 42-in Leidy Line “D” on both ends, completing the segment. With the segment completed, the existing pig traps (industry term for manifolds that launch or receive in-line inspection tools) at both tie-ins will no longer be needed and will therefore be removed, while the existing mainline valves will remain. Transco will be installing a new mainline valve and appurtenant equipment at Milepost 49.6 off Sugar Hollow Road. The valve installation is a means to isolate gas flows. One Contractor Yard is proposed at the east end of the pipeline at MP 43.72 (CY-MO-001).

Work and disturbed areas are located within Transco property, existing easements, or legally obtained workspace where the past, present, and proposed land use is primarily an existing pipeline ROW. Along the edges of the ROW land use is primarily forested. The proposed contractor yard and staging areas will be used temporarily and subsequently removed after the completion of the Project. Staging areas will be used for parking, equipment turn-arounds, and temporary storage of equipment. Transco will use a contractor yard for parking, contractor offices, and the storage of construction equipment and pipes. This contractor yard consists of an agricultural field. Disturbed areas within these temporary workspaces will be restored to the original contours. Transco will use and implement the practices, measures, and details to control soil erosion and off-site sedimentation during construction. Using data taken from Google Earth and Multi-Resolution Land Characteristics (MRLC) Consortium website (<https://www.mrlc.gov/viewer/>), it appears that the Effort Loop Pipeline site has been an existing and maintained gas pipeline right-of-way for the past 20 years and will continue to be an existing and maintained gas pipeline right-of-way once the Project is complete. Based on the surrounding land characteristics, land use prior to ROW construction within the past 50 years likely would have been either forested land or meadow.

6. Erosion and Sediment Control Best Management Practices (NOI Checklist Item 3.f, 7.f)

Various erosion and sediment control measures will be used during the construction of the Effort Loop Pipeline. BMPs proposed to be used at the Site to control soil erosion and sediment pollution are listed below. Details of BMPs proposed to be used at the Project location is included in the Erosion and Sedimentation Control Plan sheets. BMP's listed will be used at the Project location at the discretion of the environmental inspector, when found necessary to comply with 25 PA Code Chapter 102 and to adequately address potential erosion and sediment control issues.

Rock Construction Entrances

Rock construction entrances shall be installed whenever sediment tracking onto road surfaces is a potential or if required by the county conservation district or other agency. Soil erosion control measures shall be installed, if required and as needed. In special protection watersheds, either a 100' long rock construction entrance or a standard 50' rock construction entrance with a wash rack will be used at the construction entrance to wash construction vehicle wheels before they enter the public roadway. The wash rack will discharge to a 24" compost filter sock (min.). Rock construction entrance thickness shall be constantly maintained to the specified dimensions by adding rock. Sediment deposited on roadways shall be removed and returned to the construction site immediately.

Compost Filter Sock

Compost filter sock shall be placed downslope of disturbed areas to serve as a sediment barrier and filter. Filter sock shall be placed at existing level grade, parallel to contours, with both ends of the sock extended up slope at a 45 degree angle. Socks can be used on both steep and rocky slopes. Socks can range in size from 12 inch to 32 inch diameter depending on the site conditions. The Maximum Permissible Slope Lengths Above Compost Filter Socks will be used to determine the sizes of compost filter.

Compost Filter Sock Sediment Trap

Runoff may be directed into the Compost Filter Sock Sediment Traps of sheet flow into the trap. Compost sock sediment traps shall not exceed three socks in height and shall be stacked in pyramidal form. Minimum trap height is one 24" diameter sock. Additional storage may be provided by means of an excavated sump 12" deep extending 1 to 3 feet upslope of the socks along the lower side of the trap. The maximum tributary drainage area is 5.0 acres. Since compost socks are "flow-through," no spillway is required. Installation of an excavated sump immediately

above the socks may increase trap efficiency where soil conditions permit their construction.

Broad Based Dips

Broad-based dips may be used to direct runoff from access roads to well-vegetated areas. In HQ/EV watersheds, sump with compost filter sock should be utilized at the discharge end of the broad-based dip.

Waterbars

Waterbars will be aligned along the pipeline ROW to direct runoff towards the downslope side of the disturbed area and to avoid backflow into the ROW. Compost filter sock shall be installed along the edge of the limit of disturbance to slow run off. Compost filter sock hooks shall be installed at an upslope angle and shall discharge to a well-vegetated area. Upslope of the CFS, a sump shall be constructed to reduce velocity and provide a sheet flow condition to the CFS. Permanent waterbars within the ROW shall be left in place after permanent stabilization has been achieved.

Compost Filter Sock Waterbar Discharge / Waterbar Sump

An 18" Compost Filter Sock shall be installed at the edge of the LOD where waterbar cross the LOD. Upslope of the CFS a 24" x 24" sump shall be constructed to reduce velocity and provide a sheet flow condition to the CFS. The sump shall be filled and stabilized when the CFS is removed after site stabilization.

Diversion Channels / Mountable Berms

Diversion channels or mountable berms shall be used to divert runoff from disturbed areas and convey it to appropriate BMPs such as a sedimentation basin sediment trap or clean water crossing.

Trench Plug

These will be placed at the banks of waterbodies in order to maintain stable working conditions and keep sediment from entering the waterways. Earth filled sacks will be used to secure the plug. The spacing of these structures varies based on the site and the slope of the dig location, as indicated in the plan drawings.

Erosion Control Blankets

A suitable erosion control blanket or soil stabilizer shall be used wherever earth disturbance occurs within 50 feet of surface waters, or 100 feet if special protection water, especially if site conditions make use of conventional E&S BMPs difficult. Erosion control blankets

should be used on finished slopes greater than 3:1.

Timber Mats

Timber mats can be used for temporary wetland crossings. The timber mats are placed over the wetland to allow equipment to cross and then are removed.

Temporary Equipment Bridges

A temporary bridge equipment crossing will be built in order to cross any streams along the pipeline installation. The bridge equipment crossing will utilize geotextile material, timber mats, and a timber or metal bridge with side rails any may include instream supports (where necessary). Culvert Equipment crossings may be used in areas where equipment must cross stream channels. Culverts shall be placed in the stream channel sized appropriately to convey the flow within the channel and shall be placed at least one-half their diameter apart. Coarse aggregate may be used for fill surrounding the culverts. Upon completion, all material placed in the stream channel shall be completely removed.

Flumed Crossing/ Dam and Pump Crossing

These may be used when work is to be completed in a waterway. A flumed crossing involves the placement of a flume pipe within the waterway and using diversion structures up and down gradient to divert flow through the flume pipe and out of the work area. A dam and pump crossing involves placing sandbag barriers on the upstream and downstream sides of the workspace to prevent water from entering the maintenance area. A pump shall be placed to move any water from the upstream side, around the workspace and back to the downstream side of the work area. Trench plugs may be used on the banks of the stream to keep water from leaving the bed and banks limit of the waterway.

Pumped Water Filter Bag

Filter bags shall be placed in well-vegetated grassy areas and discharge onto stable, erosion resistant areas, and staked if the slope is greater than 5 percent. In the event that this is not possible, a geotextile path will be provided. A compost filter sock shall be placed below the filter bag when placed within 50 of streams or wetlands located within a HQ/EV watershed.

Trench Dewatering

Trench dewatering may be required, depending on the site conditions during the excavation. Water shall be pumped out and discharged into a filter bag or a dewatering structure when deemed necessary.

Safety Fence

Safety fence shall be installed to protect sensitive environmental features as depicted on the plan drawings. The fencing shall remain in place during the phases of construction.

Silttron Pollution Prevention Fence

Silttron Pollution Prevention Fence may be used throughout the project where environmental features make it necessary in lieu of Compost Filter Sock (CFS). The site specific sediment barriers will be selected by the environmental inspector on a site by site basis. These barriers will be placed at existing level grade, with both ends of the barrier extending at least 8' upslope at a 45 degree angle. Sediment must be removed when accumulations reach ½ the above ground height of the fence. The size and type of fence will be selected based on slope lengths as determined in the maximum slope length for Multi-Layer Geotextile Filter Fence figures. The 16-inch filter fence is equivalent to an 18-inch compost filter sock, the 21-inch filter fence is equivalent to a 24-inch compost filter sock, and a 28-inch filter fence is equivalent to a 32-inch compost filter sock. Approved for use as an Alternative E&S and PCSM BMP by PA DEP on 8/22/18.

Rock Filter Outlet

Rock filter outlets may be used to address areas where concentrated flows intersect sediment barriers. They may also be used in instances where sediment barriers such as silt fence or compost filter socks have failed due to concentrated flow.

Wetland Installation Procedures

During the course of pipeline maintenance and replacement within wetland areas, BMP's including slope breakers, equipment mats, sediment barriers, and trench plugs may be used to prevent altering the hydrology of the wetland and to prevent sediment from entering the wetland. Work within the wetland boundaries shall be limited to the extent possible. Upon completion of work the wetland area shall be restored to pre-construction grades and seeded with an appropriate wetland seed mixture.

Hydrostatic Dewatering Structure

A hydrostatic dewatering structure will be placed on a level, well vegetated site such that water will flow away from the structure and work areas. Flow rates through discharge and diverter pipes will be such that structures will not overflow. Contractor will properly remove and dispose of the dewatering structure immediately upon completion of dewatering operations.

Bored Road Crossing/Trenched Road Crossing

These may be used where pipeline installation or maintenance under a bored road is necessary. Sediment barriers shall be used around the work area. Culverts will be placed where required to maintain water flow for stormwater ditches.

Riprap Apron

Riprap aprons may be used at pipe or channel outfalls. The aprons will help dissipate flow velocity before entering vegetated areas and/or receiving stream(s).

Structural Level Spreader

Structural level spreaders are used to collect concentrated runoff in a plunge pool and distribute flow uniformly across a weir to a vegetative surface, such that the velocity of the flow is reduced and the risk of erosion is minimized.

Perforated Pipe Level Spreader

Perforated pipe level spreaders are used to distribute stormwater runoff to established vegetative surfaces as sheet flow using perforated pipes. The perforated pipe is placed subsurface within a gravel bed.

Clean Water Crossings

Temporary diversion channels or mountable berms shall be used to divert runoff from undisturbed upslope areas and convey the runoff around areas of earth disturbance within the pipeline ROW corridor. From the diversion, the flow will outlet to a temporary pipe(s) crossing, which is installed across the right-of-way, and discharge to an outlet basin. Clean water leaving the outlet basin will return to sheet flow downslope of the disturbed ROW.

Revegetation Plan and Procedures

The construction site should be stabilized as soon as possible after completion. Establishment of final cover must be initiated no later than 7 days after reaching final grade. Temporary erosion and sedimentation control BMPs can be removed when the site meets final stabilization. Final stabilization means that soil-disturbing activities are completed, and that either a permanent vegetative cover with a density of 70% or greater has been established or that the surface has been stabilized by hard cover such as pavement or buildings. It should be noted that the 70% requirement refers to the total area vegetated and not just a percent of the site.

Surface Roughening

Surface roughening is the practice of providing a rough soil surface with horizontal

depressions for the purpose of reducing runoff velocity, increasing infiltration, aiding the establishment of vegetation, and reducing erosion. Surface roughening should be applied to slopes 3H:1V or steeper unless a stable rock face is provided or it can be shown that there is not a potential for sediment pollution to surface waters. For roughened surfaces within 50 feet of a surface water, and where blanketing of seeded areas is proposed as the means to achieving permanent stabilization, spray-on type blankets are recommended.

Typical Topsoil Stockpile

The maximum stockpile height shall not exceed 35 feet. Stockpile slopes shall be no steeper than 2H:1V. Stockpiles shall be stabilized in accordance with temporary seeding specifications and mulch is to be maintained until the stockpile is stabilized. Stockpile location shown on the plans are illustrative and may vary in location as construction proceeds.

Typical Channel and Vegetation Restoration

The impacted riparian zone will be restored for a minimum of 15 feet landward of the top of bank. If the pre-impact riparian buffer of native herbaceous and shrub vegetation exceeds 15 feet beyond the top of bank, the area to be seeded should be as follows: 150 feet in High-Quality waters, 100 feet in other waters, or existing width of the riparian zone if it is less than the minimum requirements. Ernst Seed Mix 178 (Riparian Buffer Mix) or similar shall be applied on restored banks and riparian zones. In addition, where existing forested buffers are impacted these shall be replanted outside of the existing maintained ROW, as indicated in forest replanting plans for the Project outlined in the Chapter 105 permit.

7. Recycling and Disposal of Materials (NOI Checklist Item 3.k, 7.k)

The restoration of the pipeline right-of-way will require the removal of the temporary materials. The temporary materials include, but may not be limited to, stone surfaces and associated geotextiles. The contractors are required to dispose of the materials at suitable disposal or recycling sites and in compliance with local, state and federal regulations.

Contractors are required to inventory and manage their construction site materials. The goal is to be aware of the materials on-site, ensure they are properly maintained, used, and disposed of, and to make sure the materials are not exposed to stormwater. The following materials or substances are expected to be present on-site during construction (Note: this list is not an all-inclusive list and the materials management plan can be modified to address additional materials used on-site):

- Acids
- Detergents
- Fertilizers (nitrogen/phosphorus)
- Hydroseeding mixtures
- Petroleum based products
- Sanitary wastes
- Soil stabilization additives
- Solder
- Solvents

These materials must be stored as appropriate and shall not contact storm or non-stormwater discharges. Contractor shall provide a weatherproof container to store chemicals or erodible substances that must be kept on the site. Contractor is responsible for reading, maintaining, and making employees and subcontractors aware of Safety Data Sheets (SDSs).

8. Thermal Impacts (NOI Checklist Item 3.m, 7.m)

Due to the overall nature of the Project, thermal impacts to surface waters are not anticipated. The pipeline installation activities will primarily take place within an existing cleared and maintained pipeline right-of-way. There will be no increase in stormwater discharge. The primary means to address thermal impacts on this Project is to limit the size and duration of exposed earth. Revegetation procedures and the Sequence of Construction outline disturbed areas being immediately revegetated.

Stormwater runoff associated with the installation of the MLV's will be routed through the stormwater BMP's designed to retain and infiltrate the first surge of water from the site. The first surge of water will be the warmest water for the duration of the storm event and will quickly cool as the storm event progresses. The BMPs are designed to capture and infiltrate this warmest surge of stormwater. Based on routing calculations, stormwater is not discharged from the BMPs for the first 8 hours during a 100-year/24-hour storm event. The retention period is longer for less intense storms. Therefore, as a result of these measures, no significant thermal impact to the receiving waters is anticipated.

9. Antidegradation Requirements (NOI Checklist Item 3.p, 7.o)

Transco evaluated the feasibility of non-discharge alternatives that would be located outside of exceptional value (EV) or high-quality (HQ) watersheds. Hydraulic models were analyzed from an efficiency and effectiveness point of view to confirm and minimize the necessary pipeline lengths and diameters to meet the Project purpose and need. In order for the Project to

meet the required purpose and need, siting the Effort Loop Pipeline outside of EV and HQ watersheds, is not feasible.

Therefore, Transco determined that there are no cost-effective and environmental sound viable non-discharge alternatives for the project. Transco has minimized project impacts to EV and HQ watersheds through the use of co-location with existing pipelines and protecting riparian buffers within the project workspace. Earth disturbance will be minimized to the extent practical and will be phased or sequenced to only disturbed portions that are necessary for the specific scope of work. Wherever possible, the LOD was decreased to avoid disturbing additional ground and will be kept to the minimum width and depth necessary to safely complete construction activities.

Anti-Degradation Best Available Combination of Technologies (ABACT) standards have been proposed for the Effort Loop Pipeline because there are no viable non-discharge alternatives. The Erosion and Sediment Control Plan prepared for the Project outlines a more stringent design and E&S BMPs that meet ABACT standards.

Pipeline installation activities along the pipeline ROW and at the contractor yards/staging areas will not result in increase in discharge of stormwater to surface waters. The existing / designated use of the streams within the Project area are to be protected through E&S and PCSM measures taken by Transco.

The MLV-505LD86 site will result in increased discharge of stormwater to surface waters which will be mitigated by the implementation of post-construction stormwater management (PCSM) BMPs. Proposed PCSM BMPs are designed with stormwater volume reduction and water quality treatment maximized to the extent practicable within the site constraints to maintain and protect existing water quality and existing and designated uses.

10. Riparian Buffers (NOI Checklist Item 3.o, 7.n)

Pipeline installation will take place within an existing cleared and maintained pipeline ROW and forested areas. Due to the linear nature of the project, temporary impacts within riparian buffers are unavoidable. At locations where it was impossible to avoid riparian impacts due to safety issues, Transco will implement BMPs to minimize the impacts. After completing the construction activities, areas used for pipeline installation and as contractor yards/staging areas will be restored back to pre-existing contours and reseeded with a riparian seed mix in areas where slopes are less than 10%. At MLV-505LD86, where permanent increase in impervious area

is proposed, no riparian buffers were identified. Tree and shrub plantings will occur in forested riparian buffers outside of the maintained ROW as outlined in riparian reforestation plans outlined in the Chapter 105 permit.

Linear projects including pipelines are eligible for the Riparian Buffer Waiver under 25 PA Code §102.14(d)(2)(ii) if riparian buffers are undisturbed to the extent practicable. As such, a Riparian Buffer Waiver has been requested along with this ESCGP-3 application (Section 1-7).

11. Project Site Runoff (NOI Checklist Item 3.d, 7.d)

Changes in Project site runoff are not anticipated for the Project except at the MLV-505LD86 site, where increase in the impervious area is proposed. The Project site is primarily existing and maintained pipeline right-of-way in meadow condition with a forested fringe. The ROW will be restored to meadow condition upon the completion of construction. Proposed BMPs were sized based on the maximum tributary drainage area anticipated during construction. An analysis of pre- and post-development stormwater runoff was performed for the MLV site. The installation of the valves and associated access road will increase the volume of stormwater runoff due to the increase in the type and size of the impervious area. The contractor will construct stormwater BMPs to mitigate the increase in volume and peak rates associated with construction. Refer to the Post-Construction Stormwater Management (PCSM) Plan for additional information (Section 3 of this ESCGP-3 Application). Changes in stormwater runoff between pre- and post-development conditions for 2-year rainfall event and changes in peak discharge rates for 1-, 2-, 10-, 25-, 50- and 100-yr storms are given in the tables below.

11.1 MLV-505LD86

Pre- and Post-Construction Stormwater Volume for 2-yr Rainfall event

Pre-construction (cf)	Post-construction before BMPs (cf)	Post-construction after BMPs (cf)	Net (cf)
15,039	19,167	12,129	-2,910

DA-1: Pre-Construction Peak Discharge Rates (cfs)

1-year	2-year	10-year	25-year	50-year	100-year
0.00	0.01	0.37	2.41	5.89	11.47

DA-2: Pre-Construction Peak Discharge Rates(cfs)

1-year	2-year	10-year	25-year	50-year	100-year
2.29	4.51	12.49	19.56	26.58	35.41

DA-1: Post-Construction w/ BMPs Peak Discharge Rates (cfs)

1-year	2-year	10-year	25-year	50-year	100-year
0.00	0.01	0.31	1.94	4.21	8.28

DA-1: Difference between Pre-Construction and Post-Construction w/ BMPs

	1-year	2-year	10-year	25-year	50-year	100-year
NET Difference	-0.00	-0.00	-0.06	-0.20	-1.68	-3.19

DA-2: Post-Construction w/ BMPs Peak Discharge Rates (cfs)

1-year	2-year	10-year	25-year	50-year	100-year
2.25	3.97	12.28	18.40	24.35	31.74

DA-2: Difference between Pre-Construction and Post-Construction w/ BMPs

	1-year	2-year	10-year	25-year	50-year	100-year
NET Difference	-0.04	-0.54	-0.21	-1.16	-2.23	-3.67

12. Offsite Discharge Analysis

The stormwater BMP's being constructed at the MLV-505LD86 site are in areas that will discharge stormwater to offsite non-surface water. These areas have been analyzed to reduce the likelihood that these discharges will be erosive to adjacent property owners. The analysis has been performed in accordance with PADEP Document 3150-FS-DEP4124, "Off-Site Discharges of Stormwaters to Areas That Are Not Surface Waters". The full analysis is presented in Attachment 4 – Offsite Discharge Report. A summary of the findings is presented below.

12.1 MLV-505LD86

The MLV-505LD86 site utilizes infiltration berms and an infiltration basin. A series of collection channels along the access road direct water to discharge locations on both the north and south sides of the access road. On the south side of the access road, water from collection channels enter and discharge from an infiltration berm near the southeastern part of the site's Limits of Disturbance and from another infiltration berm near the site entrance. Additional collection channels on the north side of the access road direct water into an infiltration basin and is discharged from a basin outlet near the site entrance, where it then leaves the site via a Sugar Hollow roadside ditch south of the Limits of Disturbance. A diversion channel north of the access road also directs water to a level spreader near the northern part of the Limits of Disturbance.

The infiltration berms discharge water as sheet flow which travels along a vegetative flow path, eventually entering Sugar Hollow Creek. The area downstream of the outfall is over 90% vegetated. In the E&S and PCSM Narrative, site calculations are provided that show the Pre- and Post-Construction runoff flow rates and volume. These calculations show a reduction in the post-construction discharge rates and volumes. Calculations indicated that the discharge velocity at

the proposed infiltration berms are 0.7 fps and 0.8 fps for the 25 year, 24-hour storm event. Since the outlet velocity is below 2.5 fps downstream erosion will be minimal if not negligible.

The infiltration basin discharges water through a basin outlet, and it flows into the adjacent forested area near the site entrance. The stormwater is discharged as sheet flow and travels along a vegetative flow path until it enters a Sugar Hollow roadside ditch near the site entrance and then a road culvert south of the Limits of Disturbance. The area downstream of the outfall is over 90% vegetated. In the E&S and PCSM Narrative, site calculations are provided that show the Pre- and Post-Construction runoff flow rates and volume. These calculations show a reduction in the post-construction discharge rates and volumes. Calculations indicated that the discharge velocity at the proposed infiltration basin outlet is 0.0 fps for the for the 25 year, 24-hour storm event. Since the outlet velocity is below 2.5 fps downstream erosion will be minimal if not negligible.

13. Site Restoration Plan

13.1 Previous Land Use

The Project sites are primarily existing and maintained pipeline right-of-way in meadow condition with a forested fringe. Using data taken from Google Earth and Multi-Resolution Land Characteristics (MRLC) Consortium website (<https://www.mrlc.gov/viewer/>), it appears that the Regional Energy Access Expansion sites have been an existing and maintained gas pipeline right-of-way for the past 20 years and will continue to be an existing and maintained gas pipeline right-of-way once the Project is complete. Based on the surrounding land characteristics, land use prior to ROW construction within the past 50 years likely would have been either forested land or meadow.

13.2 Disturbance Activities, Changes to Permanent Topographic Land Cover Along Pipeline Alignment

The Effort Loop Pipeline will consist of approximately 13.8 miles of 42-inch pipeline co-located with existing Transco Leidy Lines between Mileposts 43.72 and 57.50 in Ross, Chestnuthill and Tunkhannock Townships, Monroe County. The new pipeline will tie-in to the existing 42-in Leidy Line "D" on both ends, completing the segment. With the segment completed, the existing pig traps (industry term for manifolds that launch or receive in-line inspection tools) at both tie-ins will no longer be needed and will therefore be removed, while the existing mainline valves will remain. Transco will be installing a new mainline valve, MLV-505LD86, and appurtenant equipment at Milepost 49.6 off Sugar Hollow Road. The valve installation is a means

to isolate gas flows. One Contractor Yard is proposed at the east end of the pipeline at MP 43.72 (CY-MO-001).

The work and disturbed areas are located within Transco property, existing easements, or legally obtained workspace where the past, present, and proposed land use is primarily an existing pipeline ROW. Along the edges of the ROW land use is primarily forested. The proposed contractor yard and staging areas will be used temporarily and subsequently removed after the completion of the Project. Staging areas will be used for parking, equipment turn-arounds, and temporary storage of equipment. Transco will use a contractor yard for parking, contractor offices, and the storage of construction equipment and pipes. This contractor yard consists of an agricultural field. Disturbed areas within these temporary workspaces will be restored to the original contours. In addition to the E&S BMP measures listed in Section 6.0 Transco will use and implement the following practices, measures, and details to control soil erosion and off-site sedimentation during construction.

13.3 Restoration Measures

Pipeline components of the Project will take place within or adjacent to a previously disturbed pipeline ROW. Stormwater controls which will be installed during construction have been designed to avoid impacts to natural drainage features. These controls will only have temporary impacts while installed and will be removed once the site is stabilized with vegetation. Minimal impacts to wetland resources are anticipated, as these functions are generally limited when compared to watercourses. The Regional Energy Access Expansion workspaces will be restored by to pre-construction contours.

Cleanup operations will commence immediately following backfill operations. Final grading, topsoil replacement, and installation of permanent erosion control structures will be completed within 20 days after backfilling the trench (10 days in residential areas). Construction debris will be removed from construction work areas unless the landowner or land managing agency approves leaving materials onsite for beneficial reuse, stabilization, or habitat restoration. Rock in excess of four inches from at least the top 12 inches of soil in cultivated or rotated cropland, managed pastures, hayfields, and residential areas, as well as other areas will be removed at the landowner's request. Construction right-of-way will be graded to restore pre-construction contours and leave the soil in the proper condition for planting. Temporary sediment barriers will be removed and replaced by permanent erosion control measures or when revegetation is successful.

Wetland Restoration Procedures

The wetlands will be revegetated with annual ryegrass at 40 lbs / acre pure live seed and with the recommended wetland seed mix, unless standing water is present. Lime, fertilizer or mulch will not be used in wetland areas. In the event that final seeding and mulching is deferred more than 20 days after the trench is backfilled, slopes adjacent to wetlands shall be blanketed for a minimum of 100 feet on each side of the crossing.

Specific procedures will be developed in coordination with the appropriate land management or state agency, where necessary, to prevent the invasion or spread of undesirable exotic vegetation (such as purple loose strife and phragmites). It will be ensured that disturbed areas permanently revegetate.

Equipment mats will be removed upon completion of construction, as well as temporary sediment barriers located at the boundary between wetland and adjacent upland areas after upland revegetation and stabilization of adjacent upland areas are successful.

Permanent Erosion Control Measures

Trench plugs are intended to slow the flow of subsurface water along the trench. Trench plugs may be constructed of materials such as sandbags or polyurethane foam. Do not use topsoil in trench breakers. At a minimum, install a trench breaker at the base of slopes greater than 5 percent where the base of the slope is less than 50 feet from a waterbody or wetland and where needed to avoid draining a waterbody or wetland. Trench breakers will be installed in wetlands to prevent water from traveling along the trench and altering micro-watersheds within the wetlands.

Waterbars are intended to reduce runoff velocity, divert water and prevent sediment deposition into sensitive resources. Waterbars shall be constructed using spacing recommendations outlined below. In the absence of written recommendations, use the following spacing unless closer spacing is necessary to avoid excessive erosion on the construction right-of-way:

Slope (%)	Spacing (feet)
<5	250
5-15	150
>15-30	100
>30	50

Waterbars will be constructed to divert surface flow to a stable area without causing water to pool or erode behind the breaker. In the absence of a stable area, construct appropriate energy-dissipating devices at the end of the waterbar.

Soil Compaction Measures

Topsoil and subsoil will be tested for compaction at regular intervals in agricultural and residential areas disturbed by construction activities. Tests will be conducted on the same soil type under similar moisture conditions in undisturbed areas to approximate preconstruction conditions. Penetrometers or other appropriate devices will be used to conduct tests.

Severely compacted agricultural areas will be plowed with a paraplow or other deep tillage implement. In areas where topsoil has been segregated, plow the subsoil before replacing the segregated topsoil. If subsequent construction and cleanup activities result in further compaction, conduct additional tilling. Refer to the Transco Project-specific Agricultural Construction and Monitoring Plan. Appropriate soil compaction mitigation will be performed in severely compacted residential areas.

Revegetation Plan and Procedures

The construction site should be stabilized as soon as possible after completion. Establishment of final cover must be initiated no later than 7 days after reaching final grade. Temporary erosion and sedimentation control BMPs can be removed when the site meets final stabilization. Final stabilization means that soil-disturbing activities are completed, and that either a permanent vegetative cover with a density of 70% or greater has been established or that the surface has been stabilized by hard cover such as pavement or buildings. It should be noted that the 70% requirement refers to the total area vegetated and not just a percent of the site.

Surface Roughening

Surface roughening is the practice of providing a rough soil surface with horizontal depressions for the purpose of reducing runoff velocity, increasing infiltration, aiding the establishment of vegetation, and reducing erosion. Surface roughening should be applied to slopes 3H:1V or steeper unless a stable rock face is provided or it can be shown that there is not a potential for sediment pollution to surface waters. For roughened surfaces within 50 feet of a surface water, and where blanketing of seeded areas is proposed as the means to achieving permanent stabilization, spray-on type blankets are recommended.

Typical Channel and Vegetation Restoration

The impacted riparian zone will be restored for a minimum of 15 feet landward of the top of bank. If the pre-impact riparian buffer of native herbaceous and shrub vegetation exceeds 15 feet beyond the top of bank, the area to be seeded should be as follows: 150 feet or the existing width of the riparian zone if it is less than the minimum requirements. Ernst Seed Mix 178 (Riparian Buffer Mix) or similar shall be applied on restored banks and riparian zones. In addition, where existing forested buffers are impacted these shall be replanted outside of the existing maintained ROW, as indicated in forest replanting plans for the Project outlined in the Chapter 105 permit.

13.4 Maintenance and Evaluation for Effectiveness

Follow-up inspections of disturbed areas will be conducted as necessary, to determine the success of revegetation and address landowner concerns. At a minimum, conduct inspections after the first and second growing seasons. Revegetation in non-agricultural areas shall be considered successful if upon visual survey the density and cover of non-nuisance vegetation are similar in density and cover to adjacent undisturbed lands. In agricultural areas, revegetation shall be considered successful when upon visual survey, crop growth and vigor are similar to adjacent undisturbed portions of the same field, unless the easement agreement specifies otherwise. Continue revegetation efforts until revegetation is successful.

BMPs should be properly maintained to ensure their effectiveness. Sheet flow conditions and infiltration must be sustained throughout the life of the BMP. BMPs should be inspected for clogging from sediment or debris, damage by foot or vehicular traffic, and flow channelization. Inspections should be made on a quarterly basis for the first two years following installation, and then twice per year thereafter. Inspections should also be made after every storm event greater than 1 inch during the establishment period.

Channel linings should be inspected for signs of erosion or dislodging, as applicable. Channels should be inspected for debris, overgrown vegetation, and other blockages. Vegetated areas will be inspected weekly and after runoff events until permanent vegetation is achieved. Once the vegetation is established, inspections of health, diversity, and density should be performed at least twice per year, during both the growing and non-growing season. Vegetative cover should be sustained at 85% and reestablished if damage greater than 50% is observed. Damaged BMPs will be repaired as soon as possible upon discovery. Repairs will be made to restore to BMPs to the original design condition.

Drainage and irrigation systems problems resulting from pipeline construction in agricultural areas will be monitored and corrected until restoration is successful. Restoration will be considered successful when the surface condition is similar to adjacent undisturbed lands, construction debris is removed, revegetation is successful, and proper drainage has been restored.

Vegetated areas will be inspected weekly and after runoff events until permanent vegetation is achieved. Once the vegetation is established, inspections of health, diversity, and density should be performed at least twice per year, during both the growing and non-growing season. Vegetative cover should be sustained at 85% and reestablished if damage greater than 50% is observed. Damaged BMPs will be repaired as soon as possible upon discovery. Repairs will be made to restore damaged BMPs to the original design condition.

Routine vegetation mowing or clearing over the full width of the permanent right-of-way in uplands will not be done more frequently than every three years. Transco will limit routine vegetation mowing or clearing within wetlands and adjacent to waterbodies. A 10-foot-wide herbaceous corridor will be maintained over the center of the pipeline within the wetland and riparian buffer areas. Trees and other woody vegetation will also be allowed to reestablish naturally within the construction ROWs that were cleared for construction of the pipeline. However, trees within 15 feet of the centerline and between existing pipelines will be removed to maintain the integrity of the pipeline. In no case will routine vegetation mowing or clearing occur during the migratory bird nesting season between April 15 and August 1 of any year unless specifically approved in writing by the responsible land management agency or the U.S. Fish and Wildlife Service. Transco will not use herbicides or pesticides in or within 100 feet of a waterbody except as allowed by the appropriate land management or state agency.

Efforts to control unauthorized off-road vehicle use, in cooperation with the landowner, shall continue throughout the life of the project. Maintain signs, gates, and permanent access roads as necessary.

Wetlands and waterbodies will be protected through use of waterbars, diversion/collection channels, trench plugs, and erosion control blankets. Broad-based dips may be used to direct runoff from access roads to well-vegetated areas. In HQ/EV watersheds, sump with compost filter sock should be utilized at the discharge end of the waterbar. Diversion channels shall be used to divert runoff from disturbed areas and convey it to appropriate BMPs such as a sedimentation

basin sediment trap or clean water crossing. These will be placed at the banks of waterbodies in order to maintain stable working conditions and keep sediment from entering the waterways. Earth filled sacks will be used to secure the plug. The spacing of these structures varies based on the site and the slope of the dig location, as indicated in the plan drawings. A suitable erosion control blanket or soil stabilizer shall be used wherever earth disturbance occurs in close proximity of surface waters especially if site conditions make use of conventional E&S BMPs difficult. Erosion control blankets should be used on finished slopes greater than 3:1.

Post-Construction Wetland and Watercourse Monitoring shall occur annually for a period of five years following construction and include wetlands and watercourses impacted by the Project, and a monitoring report submitted thereafter. Each monitoring report will include, at a minimum, the following information:

- Information describing the presence or absence of hydrology at the time of inspection and a narrative comparison to hydrology present in the wetland or watercourse during pre-permitting field investigation(s);
- Photographic Documentation;
- Vegetation data including inventory of plant species, percent coverage of native hydrophytic species (wetlands), and stem counts survival; and
- Identification of any problems or concerns that require remedial measures, including loss of hydrology, and a plan to address the deficiencies.


Contractor shall provide a weatherproof container to store chemicals or erodible substances that must be kept on the site. Contractor is responsible for reading, maintaining, and making employees and subcontractors aware of Safety Data Sheets (SDSs).

14. Erosion and Sediment Control Plan Shall be Prepared by a Person Trained and Experienced in Erosion Control Methods and Techniques

These plans and narrative were prepared by Kevin C. Clark, PE (BAI Group, LLC) of State College, PA in accordance with the Pennsylvania Department of Environmental Protection Erosion and Sediment Pollution Control Program Manual, March 2012. Plan preparer's resume is provided in Attachment C of the ESCGP-3 permit package).

ATTACHMENT 1
PROJECT LOCATION MAP


M:\GIS\PROJECTS\REGIONAL_ENERGY_ACCESS\PROJECT_LOCATION_MAPPING\REVISED_MAPPING_APRIL_2020\REA_EffortLoop_ProjectLocation_08262020.mxd



- ◆ Mile Post
- ★ Proposed Facility Modification/Addition
- Proposed Pipeline
- Existing Transco Pipelines
- Proposed Limits of Disturbance
- Municipal Boundaries

Notes:
 1. Maps Reduced from USGS 7.5 Minute Quadrangles:
 Blakeslee, Brodheads ville, Pocono Pines, & Saylorburg

1 Inch = 2,000 Feet



TRANSCONTINENTAL GAS PIPE LINE COMPANY, LLC
REGIONAL ENERGY ACCESS EXPANSION PROJECT
PROPOSED 42" EFFORT LOOP
PROJECT LOCATION MAP


CHESTNUT HILL & ROSS TOWNSHIP

MONROE COUNTY

PENNSYLVANIA

Date:	3/26/2021
Drawn By:	FTN
Figure Number:	EL-1

M:\GIS\PROJECTS\REGIONAL_ENERGY_ACCESS\PROJECT_LOCATION_MAPPING\REVISED_MAPPING_APRIL_2020\REA_EffortLoop_ProjectLocation_08262020.mxd



- Mile Post
- Proposed Facility Modification/Addition
- Proposed Pipeline
- Existing Transco Pipelines
- Proposed Limits of Disturbance
- Municipal Boundaries

Notes:
 1. Maps Reduced from USGS 7.5 Minute Quadrangles:
 Blakeslee, Brodheads ville, Pocono Pines, & Saylorburg

1 Inch = 2,000 Feet
 0 2,000 4,000 Feet
 Copyright © 2019 National Geographic Society, Reused



TRANSCONTINENTAL GAS PIPE LINE COMPANY, LLC
REGIONAL ENERGY ACCESS EXPANSION PROJECT
PROPOSED 42" EFFORT LOOP
PROJECT LOCATION MAP


CHESTNUT HILL & TUNKHANNOCK TOWNSHIP

MONROE COUNTY

PENNSYLVANIA

Date:	3/26/2021
Drawn By:	FTN
Figure Number:	EL-2

M:\GIS\PROJECTS\REGIONAL_ENERGY_ACCESS\PROJECT LOCATION MAPPING\REVISED_MAPPING_APRIL_2020\REA_EffortLoop_ProjectLocation_08262020.mxd



TRANSCONTINENTAL GAS PIPE LINE COMPANY, LLC
REGIONAL ENERGY ACCESS EXPANSION PROJECT
PROPOSED 42" EFFORT LOOP
PROJECT LOCATION MAP

TUNKHANNOCK TOWNSHIP

MONROE COUNTY

PENNSYLVANIA

Date:	3/26/2021
Drawn By:	FTN
Figure Number:	EL-3

ATTACHMENT 2
SOILS MAP AND REPORT




United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for **Monroe County, Pennsylvania**



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	6
Soil Map	9
Soil Map.....	10
Legend.....	11
Map Unit Legend.....	12
Map Unit Descriptions.....	14
Monroe County, Pennsylvania.....	16
AnB—Allenwood gravelly silt loam, 3 to 8 percent slopes.....	16
AwB—Alvira and Watson very stony loams, 0 to 12 percent slopes.....	17
BbC—Bath channery silt loam, 8 to 25 percent slopes, extremely stony....	18
BrA—Braceville gravelly loam, 0 to 3 percent slopes.....	20
BrB—Braceville gravelly loam, 3 to 8 percent slopes.....	21
BxB—Buchanan extremely stony loam, 0 to 8 percent slopes.....	22
BxC—Buchanan channery loam, 8 to 25 percent slopes, rubbly.....	23
ChA—Chenango gravelly loam, 0 to 3 percent slopes.....	25
ChB—Chenango gravelly loam, 3 to 8 percent slopes.....	26
ChC—Chenango gravelly loam, 8 to 15 percent slopes.....	28
CnB—Chippewa and Norwich soils, 0 to 8 percent slopes, extremely stony.....	29
CpA—Clymer loam, 0 to 3 percent slopes.....	31
CxB—Clymer extremely stony loam, 0 to 8 percent slopes.....	32
Cy—Cut and fill land.....	33
DxB—Dekalb channery loam, 0 to 8 percent slopes, rubbly.....	34
DxC—Dekalb very channery loam, 8 to 25 percent slopes, extremely stony.....	35
DxE—Dekalb very stony loam, 25 to 100 percent slopes, very stony.....	37
GP—Pit, Shale, and Gravel.....	38
HaB—Hartleton channery silt loam, 2 to 8 percent slopes.....	39
HaC—Hartleton channery silt loam, 8 to 20 percent slopes.....	40
Hy—Holly silt loam.....	41
KaB—Kedron silt loam, 2 to 8 percent slopes.....	42
KvB—Klinesville channery silt loam, 3 to 8 percent slopes.....	43
KvC—Klinesville channery silt loam, 8 to 15 percent slopes.....	44
KvD—Klinesville channery silt loam, 15 to 25 percent slopes.....	45
LgB—Laidig extremely stony loam, 0 to 8 percent slopes.....	46
LgC—Laidig extremely stony loam, 8 to 25 percent slopes.....	47
LkB—Leck kill channery silt loam, 2 to 8 percent slopes.....	48
LkC—Leck kill channery silt loam, 8 to 15 percent slopes.....	49
LkD—Leck kill channery silt loam, 15 to 25 percent slopes.....	50
LsC—Lordstown channery silt loam, 8 to 15 percent slopes.....	51
LxC—Lordstown channery silt loam, 8 to 25 percent slopes, rubbly.....	52
MeA—Meckesville gravelly loam, 0 to 3 percent slopes.....	54
MeB—Meckesville gravelly loam, 3 to 8 percent slopes.....	55

Custom Soil Resource Report

MeC—Meckesville gravelly loam, 8 to 15 percent slopes.....	56
MfB—Meckesville very stony loam, 0 to 8 percent slopes.....	57
MoB—Morris channery silt loam, 0 to 8 percent slopes, extremely stony...	58
Pp—Pope silt loam, high bottom.....	59
ReA—Rexford gravelly silt loam, 0 to 3 percent slopes.....	60
SpB—Shelmadine very stony silt loam, 0 to 8 percent slopes.....	62
VaE—Very stony land and Rock outcrops, steep.....	63
W—Water.....	64
WaB—Watson silt loam, 2 to 8 percent slopes.....	65
Wb—Wayland silty clay loam.....	66
WeB3—Weikert channery silt loam, 3 to 8 percent slopes, eroded.....	67
WeC3—Weikert channery silt loam, 8 to 15 percent slopes, eroded.....	68
WeD3—Weikert channery silt loam, 15 to 25 percent slopes, eroded.....	69
WhB—Weikert-Hartleton channery silt loams, 3 to 8 percent slopes.....	70
WhC—Weikert-Hartleton channery silt loams, 8 to 15 percent slopes.....	72
WhD—Weikert-Hartleton channery silt loams, 15 to 25 percent slopes.....	74
WKE—Weikert and Klinesville soils, steep.....	76
WyA—Wyoming gravelly sandy loam, 0 to 3 percent slopes.....	78
WyB—Wyoming gravelly sandy loam, 3 to 8 percent slopes.....	79
WyC—Wyoming gravelly sandy loam, 8 to 15 percent slopes.....	80
WyD—Wyoming gravelly sandy loam, 15 to 25 percent slopes.....	82
References	84

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and


Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map




Map Scale: 1:106,000 if printed on A portrait (8.5" x 11") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 18N WGS84

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)




















Soils







 Soil Map Unit Polygons

 Soil Map Unit Lines


 Soil Map Unit Points

Special Point Features






-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Monroe County, Pennsylvania
 Survey Area Data: Version 15, Jun 5, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Sep 20, 2010—Aug 8, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AnB	Allenwood gravelly silt loam, 3 to 8 percent slopes	0.2	0.1%
AwB	Alvira and Watson very stony loams, 0 to 12 percent slopes	3.6	1.4%
BbC	Bath channery silt loam, 8 to 25 percent slopes, extremely stony	1.0	0.4%
BrA	Braceville gravelly loam, 0 to 3 percent slopes	2.7	1.0%
BrB	Braceville gravelly loam, 3 to 8 percent slopes	1.4	0.5%
BxB	Buchanan extremely stony loam, 0 to 8 percent slopes	16.9	6.4%
BxC	Buchanan channery loam, 8 to 25 percent slopes, rubbly	0.3	0.1%
ChA	Chenango gravelly loam, 0 to 3 percent slopes	2.4	0.9%
ChB	Chenango gravelly loam, 3 to 8 percent slopes	3.3	1.2%
ChC	Chenango gravelly loam, 8 to 15 percent slopes	0.0	0.0%
CnB	Chippewa and Norwich soils, 0 to 8 percent slopes, extremely stony	1.4	0.5%
CpA	Clymer loam, 0 to 3 percent slopes	4.3	1.6%
CxB	Clymer extremely stony loam, 0 to 8 percent slopes	16.2	6.2%
Cy	Cut and fill land	8.5	3.2%
DxB	Dekalb channery loam, 0 to 8 percent slopes, rubbly	3.0	1.1%
DxC	Dekalb very channery loam, 8 to 25 percent slopes, extremely stony	8.7	3.3%
DxE	Dekalb very stony loam, 25 to 100 percent slopes, very stony	3.7	1.4%
GP	Pit, Shale, and Gravel	0.3	0.1%
HaB	Hartleton channery silt loam, 2 to 8 percent slopes	18.1	6.9%
HaC	Hartleton channery silt loam, 8 to 20 percent slopes	4.8	1.8%
Hy	Holly silt loam	0.6	0.2%
KaB	Kedron silt loam, 2 to 8 percent slopes	1.6	0.6%

Custom Soil Resource Report

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
KvB	Klinesville channery silt loam, 3 to 8 percent slopes	11.7	4.4%
KvC	Klinesville channery silt loam, 8 to 15 percent slopes	2.2	0.8%
KvD	Klinesville channery silt loam, 15 to 25 percent slopes	1.0	0.4%
LgB	Laidig extremely stony loam, 0 to 8 percent slopes	11.8	4.5%
LgC	Laidig extremely stony loam, 8 to 25 percent slopes	5.6	2.1%
LkB	Leck kill channery silt loam, 2 to 8 percent slopes	23.8	9.0%
LkC	Leck kill channery silt loam, 8 to 15 percent slopes	7.9	3.0%
LkD	Leck kill channery silt loam, 15 to 25 percent slopes	4.4	1.7%
LsC	Lordstown channery silt loam, 8 to 15 percent slopes	1.1	0.4%
LxC	Lordstown channery silt loam, 8 to 25 percent slopes, rubbly	3.0	1.1%
MeA	Meckesville gravelly loam, 0 to 3 percent slopes	0.5	0.2%
MeB	Meckesville gravelly loam, 3 to 8 percent slopes	9.4	3.6%
MeC	Meckesville gravelly loam, 8 to 15 percent slopes	0.9	0.4%
MfB	Meckesville very stony loam, 0 to 8 percent slopes	9.4	3.6%
MoB	Morris channery silt loam, 0 to 8 percent slopes, extremely stony	0.9	0.3%
Pp	Pope silt loam, high bottom	0.6	0.2%
ReA	Rexford gravelly silt loam, 0 to 3 percent slopes	1.8	0.7%
SpB	Shelmadine very stony silt loam, 0 to 8 percent slopes	1.2	0.5%
VaE	Very stony land and Rock outcrops, steep	0.5	0.2%
W	Water	0.4	0.2%
WaB	Watson silt loam, 2 to 8 percent slopes	1.5	0.6%
Wb	Wayland silty clay loam	1.2	0.5%
WeB3	Weikert channery silt loam, 3 to 8 percent slopes, eroded	0.4	0.1%
WeC3	Weikert channery silt loam, 8 to 15 percent slopes, eroded	0.4	0.1%
WeD3	Weikert channery silt loam, 15 to 25 percent slopes, eroded	0.7	0.3%

Custom Soil Resource Report

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
WhB	Weikert-Hartleton channery silt loams, 3 to 8 percent slopes	25.6	9.7%
WhC	Weikert-Hartleton channery silt loams, 8 to 15 percent slopes	14.2	5.4%
WhD	Weikert-Hartleton channery silt loams, 15 to 25 percent slopes	2.5	1.0%
WKE	Weikert and Klinesville soils, steep	6.8	2.6%
WyA	Wyoming gravelly sandy loam, 0 to 3 percent slopes	0.0	0.0%
WyB	Wyoming gravelly sandy loam, 3 to 8 percent slopes	6.5	2.5%
WyC	Wyoming gravelly sandy loam, 8 to 15 percent slopes	2.5	0.9%
WyD	Wyoming gravelly sandy loam, 15 to 25 percent slopes	0.5	0.2%
Totals for Area of Interest		263.9	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not

Custom Soil Resource Report

mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Monroe County, Pennsylvania

AnB—Allenwood gravelly silt loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9y90
Elevation: 490 to 1,130 feet
Mean annual precipitation: 34 to 51 inches
Mean annual air temperature: 40 to 50 degrees F
Frost-free period: 100 to 160 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Allenwood and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Allenwood

Setting

Landform: Valley sides
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Linear
Parent material: Old till derived from sedimentary rock

Typical profile

H1 - 0 to 9 inches: gravelly silt loam
H2 - 9 to 59 inches: gravelly silty clay loam
H3 - 59 to 72 inches: very gravelly clay loam

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to high
(0.06 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Moderate (about 8.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: B
Hydric soil rating: No

AwB—Alvira and Watson very stony loams, 0 to 12 percent slopes

Map Unit Setting

National map unit symbol: 9y94
Elevation: 660 to 1,940 feet
Mean annual precipitation: 34 to 56 inches
Mean annual air temperature: 40 to 54 degrees F
Frost-free period: 100 to 160 days
Farmland classification: Not prime farmland

Map Unit Composition

Alvira and similar soils: 55 percent
Watson and similar soils: 35 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Alvira

Setting

Landform: Hillslopes
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Interfluve
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Till

Typical profile

H1 - 0 to 10 inches: gravelly loam
H2 - 10 to 21 inches: gravelly silt loam
H3 - 21 to 60 inches: very gravelly silt loam

Properties and qualities

Slope: 0 to 12 percent
Surface area covered with cobbles, stones or boulders: 1.6 percent
Depth to restrictive feature: 15 to 28 inches to fragipan
Drainage class: Somewhat poorly drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 6 to 18 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: D
Hydric soil rating: No

Description of Watson

Setting

Landform: Valley sides
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Old till derived from sedimentary rock

Typical profile

H1 - 0 to 10 inches: gravelly loam
H2 - 10 to 27 inches: gravelly silty clay loam
H3 - 27 to 60 inches: gravelly clay loam

Properties and qualities

Slope: 0 to 12 percent
Surface area covered with cobbles, stones or boulders: 1.6 percent
Depth to restrictive feature: 18 to 32 inches to fragipan
Drainage class: Moderately well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 18 to 36 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: C/D
Hydric soil rating: No

Minor Components

Shelmadine

Percent of map unit: 10 percent
Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

BbC—Bath channery silt loam, 8 to 25 percent slopes, extremely stony

Map Unit Setting

National map unit symbol: 2v31v
Elevation: 330 to 2,460 feet
Mean annual precipitation: 31 to 70 inches

Custom Soil Resource Report

Mean annual air temperature: 39 to 52 degrees F

Frost-free period: 105 to 180 days

Farmland classification: Not prime farmland

Map Unit Composition

Bath, extremely stony, and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Bath, Extremely Stony

Setting

Landform: Hills, mountains

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Interfluvium, side slope, nose slope

Down-slope shape: Linear, convex

Across-slope shape: Linear

Parent material: Loamy till derived mainly from gray and brown siltstone, sandstone, and shale

Typical profile

O_e - 0 to 1 inches: moderately decomposed plant material

A - 1 to 3 inches: channery silt loam

B_w1 - 3 to 15 inches: channery silt loam

B_w2 - 15 to 25 inches: channery loam

E - 25 to 29 inches: channery loam

B_x - 29 to 52 inches: very channery silt loam

C - 52 to 72 inches: very channery silt loam

Properties and qualities

Slope: 8 to 25 percent

Surface area covered with cobbles, stones or boulders: 7.0 percent

Depth to restrictive feature: 26 to 38 inches to fragipan

Drainage class: Well drained

Capacity of the most limiting layer to transmit water (K_{sat}): Very low to moderately low (0.00 to 0.14 in/hr)

Depth to water table: About 24 to 36 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum content: 15 percent

Available water capacity: Low (about 4.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: C

Ecological site: F140XY030NY - Well Drained Dense Till

Hydric soil rating: No

Minor Components

Mardin, extremely stony

Percent of map unit: 5 percent

Landform: Hills, mountains

Landform position (two-dimensional): Summit, shoulder, backslope

Landform position (three-dimensional): Interfluvium, side slope

Down-slope shape: Convex, concave

Custom Soil Resource Report

Across-slope shape: Convex, linear
Hydric soil rating: No

Swartswood, extremely stony

Percent of map unit: 5 percent
Landform: Hills
Landform position (two-dimensional): Footslope, backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex, linear
Across-slope shape: Linear, convex
Hydric soil rating: No

BrA—Braceville gravelly loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 9y9f
Elevation: 160 to 1,970 feet
Mean annual precipitation: 36 to 56 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 145 to 175 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Braceville and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Braceville

Setting

Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear, convex
Across-slope shape: Linear, concave
Parent material: Coarse-loamy outwash

Typical profile

H1 - 0 to 3 inches: gravelly loam
H2 - 3 to 30 inches: gravelly silt loam
H3 - 30 to 55 inches: very gravelly loam
H4 - 55 to 60 inches: stratified sand and gravel

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: 18 to 30 inches to fragipan
Drainage class: Moderately well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.60 in/hr)
Depth to water table: About 18 to 36 inches

Custom Soil Resource Report

Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 3.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: C
Ecological site: F140XY020NY - Dense Outwash
Hydric soil rating: No

Minor Components

Rexford, pd

Percent of map unit: 10 percent
Landform: Depressions
Hydric soil rating: Yes

BrB—Braceville gravelly loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9y9g
Elevation: 160 to 1,970 feet
Mean annual precipitation: 34 to 56 inches
Mean annual air temperature: 40 to 54 degrees F
Frost-free period: 100 to 175 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Braceville and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Braceville

Setting

Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Coarse-loamy outwash

Typical profile

H1 - 0 to 3 inches: gravelly loam
H2 - 3 to 30 inches: gravelly silt loam
H3 - 30 to 55 inches: very gravelly loam
H4 - 55 to 60 inches: stratified sand and gravel

Properties and qualities

Slope: 3 to 8 percent

Custom Soil Resource Report

Depth to restrictive feature: 18 to 30 inches to fragipan
Drainage class: Moderately well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.60 in/hr)
Depth to water table: About 18 to 36 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 3.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: C
Ecological site: F140XY020NY - Dense Outwash
Hydric soil rating: No

Minor Components

Rexford, poorly drained

Percent of map unit: 5 percent
Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

BxB—Buchanan extremely stony loam, 0 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9y9j
Elevation: 600 to 2,500 feet
Mean annual precipitation: 34 to 55 inches
Mean annual air temperature: 40 to 57 degrees F
Frost-free period: 100 to 180 days
Farmland classification: Not prime farmland

Map Unit Composition

Buchanan and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Buchanan

Setting

Landform: Valley sides, mountain slopes
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank, base slope
Down-slope shape: Concave, linear
Across-slope shape: Concave, linear
Parent material: Mountain slope colluvium derived from sedimentary rock

Custom Soil Resource Report

Typical profile

H1 - 0 to 4 inches: channery loam
H2 - 4 to 25 inches: gravelly loam
H3 - 25 to 60 inches: gravelly loam

Properties and qualities

Slope: 0 to 8 percent
Surface area covered with cobbles, stones or boulders: 15.0 percent
Depth to restrictive feature: 20 to 36 inches to fragipan
Drainage class: Moderately well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 18 to 36 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: C
Hydric soil rating: No

Minor Components

Hazleton

Percent of map unit: 5 percent
Landform: Mountain slopes
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Upper third of mountainflank
Down-slope shape: Convex, linear
Across-slope shape: Linear, convex
Hydric soil rating: No

Shelmadine

Percent of map unit: 5 percent
Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

BxC—Buchanan channery loam, 8 to 25 percent slopes, rubbly

Map Unit Setting

National map unit symbol: 2z1nb
Elevation: 430 to 2,220 feet
Mean annual precipitation: 37 to 50 inches
Mean annual air temperature: 50 to 55 degrees F
Frost-free period: 155 to 177 days

Custom Soil Resource Report

Farmland classification: Not prime farmland

Map Unit Composition

Buchanan and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Buchanan

Setting

Landform: Hillslopes

Landform position (two-dimensional): Backslope, footslope

Landform position (three-dimensional): Side slope, base slope

Down-slope shape: Concave, linear

Across-slope shape: Concave, linear

Parent material: Fine-loamy colluvium derived from sandstone and shale

Typical profile

O_i - 0 to 2 inches: slightly decomposed plant material

O_e - 2 to 2 inches: moderately decomposed plant material

A - 2 to 4 inches: channery loam

BE - 4 to 12 inches: channery loam

Bt₁ - 12 to 20 inches: channery loam

Bt₂ - 20 to 29 inches: channery loam

Btx₁ - 29 to 35 inches: channery loam

Btx₂ - 35 to 50 inches: channery loam

C - 50 to 71 inches: very channery loam

R - 71 to 81 inches: bedrock

Properties and qualities

Slope: 8 to 25 percent

Surface area covered with cobbles, stones or boulders: 25.0 percent

Depth to restrictive feature: 24 to 30 inches to fragipan; 60 to 79 inches to lithic bedrock

Drainage class: Moderately well drained

Runoff class: High

Capacity of the most limiting layer to transmit water (K_{sat}): Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 15 to 24 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 3.7 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: C/D

Hydric soil rating: No

Minor Components

Andover

Percent of map unit: 5 percent

Landform: Hillslopes

Landform position (two-dimensional): Footslope, toeslope

Landform position (three-dimensional): Side slope, base slope

Down-slope shape: Convex

Custom Soil Resource Report

Across-slope shape: Convex, linear
Hydric soil rating: Yes

Laidig

Percent of map unit: 4 percent
Landform: Hillslopes
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Convex, linear
Hydric soil rating: No

Shelmadine

Percent of map unit: 1 percent
Landform: Hillslopes
Landform position (two-dimensional): Footslope, toeslope
Landform position (three-dimensional): Side slope, base slope
Down-slope shape: Convex
Across-slope shape: Convex, linear
Hydric soil rating: Yes

ChA—Chenango gravelly loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 9y9l
Elevation: 600 to 1,800 feet
Mean annual precipitation: 30 to 56 inches
Mean annual air temperature: 40 to 54 degrees F
Frost-free period: 100 to 180 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Chenango and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chenango

Setting

Landform: Outwash terraces
Landform position (three-dimensional): Riser
Down-slope shape: Convex, linear
Across-slope shape: Convex, linear
Parent material: Gravelly outwash

Typical profile

H1 - 0 to 8 inches: gravelly loam
H2 - 8 to 32 inches: gravelly fine sandy loam
H3 - 32 to 72 inches: very gravelly loamy coarse sand

Custom Soil Resource Report

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Very low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 4.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2s
Hydrologic Soil Group: A
Ecological site: F140XY021NY - Dry Outwash
Hydric soil rating: No

Minor Components

Braceville

Percent of map unit: 5 percent
Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear, convex
Across-slope shape: Linear, concave
Hydric soil rating: No

Rexford, somewhat poorly drained

Percent of map unit: 5 percent
Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: No

ChB—Chenango gravelly loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9y9m
Elevation: 600 to 1,800 feet
Mean annual precipitation: 30 to 56 inches
Mean annual air temperature: 40 to 54 degrees F
Frost-free period: 100 to 180 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Chenango and similar soils: 90 percent
Minor components: 10 percent

Custom Soil Resource Report

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chenango

Setting

Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Gravelly outwash

Typical profile

H1 - 0 to 8 inches: gravelly loam
H2 - 8 to 32 inches: gravelly fine sandy loam
H3 - 32 to 72 inches: very gravelly loamy coarse sand

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 4.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: A
Ecological site: F140XY021NY - Dry Outwash
Hydric soil rating: No

Minor Components

Braceville

Percent of map unit: 5 percent
Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear, convex
Across-slope shape: Linear, concave
Hydric soil rating: No

Rexford, somewhat poorly drained

Percent of map unit: 5 percent
Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: No

ChC—Chenango gravelly loam, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 9y9n

Elevation: 600 to 1,800 feet

Mean annual precipitation: 30 to 56 inches

Mean annual air temperature: 40 to 54 degrees F

Frost-free period: 100 to 180 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Chenango and similar soils: 93 percent

Minor components: 7 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chenango

Setting

Landform: Outwash terraces

Landform position (three-dimensional): Riser

Down-slope shape: Convex, linear

Across-slope shape: Convex, linear

Parent material: Gravelly outwash

Typical profile

H1 - 0 to 8 inches: gravelly loam

H2 - 8 to 32 inches: gravelly fine sandy loam

H3 - 32 to 72 inches: very gravelly loamy coarse sand

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 4.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: A

Ecological site: F140XY021NY - Dry Outwash

Hydric soil rating: No

Minor Components

Braceville

Percent of map unit: 5 percent
Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear, convex
Across-slope shape: Linear, concave
Hydric soil rating: No

Rexford, somewhat poorly drained

Percent of map unit: 2 percent
Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: No

CnB—Chippewa and Norwich soils, 0 to 8 percent slopes, extremely stony

Map Unit Setting

National map unit symbol: 2vcjj
Elevation: 330 to 2,460 feet
Mean annual precipitation: 31 to 70 inches
Mean annual air temperature: 39 to 52 degrees F
Frost-free period: 105 to 180 days
Farmland classification: Not prime farmland

Map Unit Composition

Chippewa, extremely stony, and similar soils: 41 percent
Norwich, extremely stony, and similar soils: 39 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Chippewa, Extremely Stony

Setting

Landform: Depressions
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Loamy till dominated by siltstone, sandstone, and shale fragments

Typical profile

Oe - 0 to 1 inches: moderately decomposed plant material
A - 1 to 5 inches: channery silt loam
Eg - 5 to 15 inches: channery silt loam
Bxg - 15 to 45 inches: channery silt loam

Custom Soil Resource Report

C - 45 to 72 inches: channery silt loam

Properties and qualities

Slope: 0 to 8 percent

Surface area covered with cobbles, stones or boulders: 7.0 percent

Depth to restrictive feature: 8 to 20 inches to fragipan

Drainage class: Poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.14 in/hr)

Depth to water table: About 0 to 6 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum content: 15 percent

Available water capacity: Low (about 3.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: D

Ecological site: F140XY016NY - Mineral Wetlands

Hydric soil rating: Yes

Description of Norwich, Extremely Stony

Setting

Landform: Depressions

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Base slope

Down-slope shape: Concave

Across-slope shape: Concave

Parent material: Loamy till dominated by reddish sandstone, siltstone and shale fragments

Typical profile

Oe - 0 to 1 inches: moderately decomposed plant material

A - 1 to 5 inches: channery silt loam

Eg - 5 to 10 inches: channery silt loam

Bg - 10 to 16 inches: channery silt loam

Bgx - 16 to 46 inches: channery silt loam

C - 46 to 72 inches: channery silt loam

Properties and qualities

Slope: 0 to 8 percent

Surface area covered with cobbles, stones or boulders: 7.0 percent

Depth to restrictive feature: 10 to 24 inches to fragipan

Drainage class: Poorly drained

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.14 in/hr)

Depth to water table: About 0 to 6 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 3.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: D

Custom Soil Resource Report

Ecological site: F140XY016NY - Mineral Wetlands
Hydric soil rating: Yes

Minor Components

Chippewa, extremely stony, very poorly drained

Percent of map unit: 5 percent
Landform: Depressions
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Norwich, extremely stony, very poorly drained

Percent of map unit: 5 percent
Landform: Depressions
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Volusia, extremely stony

Percent of map unit: 5 percent
Landform: Hills, mountains
Landform position (two-dimensional): Footslope, summit
Landform position (three-dimensional): Base slope, interfluve, side slope
Down-slope shape: Concave
Across-slope shape: Linear
Hydric soil rating: No

Morris, extremely stony

Percent of map unit: 5 percent
Landform: Hills, mountains
Landform position (two-dimensional): Backslope, footslope
Landform position (three-dimensional): Head slope, interfluve, side slope
Down-slope shape: Concave
Across-slope shape: Linear
Hydric soil rating: No

CpA—Clymer loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 9y9r
Elevation: 670 to 1,950 feet
Mean annual precipitation: 34 to 51 inches
Mean annual air temperature: 40 to 50 degrees F
Frost-free period: 100 to 160 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Clymer and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Clymer

Setting

Landform: Mountains

Landform position (two-dimensional): Summit

Landform position (three-dimensional): Side slope

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Residuum weathered from sandstone

Typical profile

H1 - 0 to 9 inches: loam

H2 - 9 to 49 inches: loam

H3 - 49 to 72 inches: channery clay loam

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

Runoff class: Low

*Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)*

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Moderate (about 6.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 1

Hydrologic Soil Group: B

Hydric soil rating: No

CxB—Clymer extremely stony loam, 0 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9y9v

Elevation: 800 to 2,900 feet

Mean annual precipitation: 36 to 60 inches

Mean annual air temperature: 46 to 59 degrees F

Frost-free period: 110 to 180 days

Farmland classification: Not prime farmland

Map Unit Composition

Clymer and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Clymer

Setting

Landform: Mountains
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Residuum weathered from sandstone

Typical profile

H1 - 0 to 9 inches: very channery loam
H2 - 9 to 49 inches: loam
H3 - 49 to 72 inches: channery clay loam

Properties and qualities

Slope: 0 to 8 percent
Surface area covered with cobbles, stones or boulders: 9.0 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Moderate (about 6.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: B
Hydric soil rating: No

Cy—Cut and fill land

Map Unit Setting

National map unit symbol: 9y9x
Elevation: 590 to 1,970 feet
Mean annual precipitation: 34 to 51 inches
Mean annual air temperature: 40 to 50 degrees F
Frost-free period: 100 to 160 days
Farmland classification: Not prime farmland

Map Unit Composition

Udorthents, cut and fill, and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Udorthents, Cut And Fill

Setting

Parent material: Man made and altered materials from mixed rock types

Properties and qualities

Slope: 0 to 25 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Depth to water table: About 12 to 72 inches
Frequency of flooding: None
Frequency of ponding: None

DxB—DeKalb channery loam, 0 to 8 percent slopes, rubbly

Map Unit Setting

National map unit symbol: 2xvd8
Elevation: 790 to 1,950 feet
Mean annual precipitation: 37 to 50 inches
Mean annual air temperature: 50 to 55 degrees F
Frost-free period: 155 to 177 days
Farmland classification: Not prime farmland

Map Unit Composition

DeKalb and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of DeKalb

Setting

Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Crest, side slope
Down-slope shape: Linear, convex
Across-slope shape: Convex
Parent material: Residuum weathered from sandstone and shale

Typical profile

Oa - 0 to 1 inches: highly decomposed plant material
A - 1 to 4 inches: channery loam
E - 4 to 6 inches: very channery sandy loam
Bw - 6 to 19 inches: very channery loam
C - 19 to 24 inches: extremely channery sandy loam
R - 24 to 34 inches: bedrock

Properties and qualities

Slope: 0 to 8 percent
Surface area covered with cobbles, stones or boulders: 25.0 percent
Depth to restrictive feature: 20 to 32 inches to lithic bedrock
Drainage class: Somewhat excessively drained
Runoff class: Very low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.57 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None

Custom Soil Resource Report

Frequency of ponding: None
Available water capacity: Very low (about 2.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: A
Other vegetative classification: Dry Uplands (DU2)
Hydric soil rating: No

Minor Components

Hazleton

Percent of map unit: 5 percent
Landform: Hillslopes
Landform position (two-dimensional): Backslope, shoulder, summit
Landform position (three-dimensional): Side slope, crest
Down-slope shape: Convex
Across-slope shape: Convex, linear
Hydric soil rating: No

Weikert

Percent of map unit: 3 percent
Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Crest, side slope
Down-slope shape: Linear, convex
Across-slope shape: Convex
Other vegetative classification: Droughty Shales (SD2)
Hydric soil rating: No

Lordstown

Percent of map unit: 2 percent
Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Crest, side slope
Down-slope shape: Linear, convex
Across-slope shape: Convex
Hydric soil rating: No

DxC—DeKalb very channery loam, 8 to 25 percent slopes, extremely stony

Map Unit Setting

National map unit symbol: 2x8wh
Elevation: 530 to 2,200 feet
Mean annual precipitation: 37 to 50 inches
Mean annual air temperature: 50 to 55 degrees F
Frost-free period: 155 to 177 days
Farmland classification: Not prime farmland

Map Unit Composition

Dekalb and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Dekalb

Setting

Landform: Mountain slopes

Landform position (two-dimensional): Summit, backslope, shoulder

Landform position (three-dimensional): Interfluve

Down-slope shape: Convex

Across-slope shape: Convex, linear

Parent material: Residuum weathered from sandstone and shale

Typical profile

O_i - 0 to 1 inches: slightly decomposed plant material

A - 1 to 4 inches: very channery loam

E - 4 to 7 inches: very channery loam

B_w - 7 to 26 inches: very channery sandy loam

C - 26 to 34 inches: extremely channery sandy loam

R - 34 to 44 inches: bedrock

Properties and qualities

Slope: 8 to 25 percent

Surface area covered with cobbles, stones or boulders: 9.0 percent

Depth to restrictive feature: 20 to 40 inches to lithic bedrock

Drainage class: Well drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (K_{sat}): Moderately high to high
(0.57 to 5.95 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 3.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A

Hydric soil rating: No

Minor Components

Hazleton

Percent of map unit: 5 percent

Landform: Mountain slopes on mountains

Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Interfluve

Down-slope shape: Convex

Across-slope shape: Convex, linear

Hydric soil rating: No

Clymer

Percent of map unit: 5 percent

Landform: Mountain slopes

Custom Soil Resource Report

Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Convex
Across-slope shape: Convex
Hydric soil rating: No

DxE—Dekalb very stony loam, 25 to 100 percent slopes, very stony

Map Unit Setting

National map unit symbol: 2w6nl
Elevation: 370 to 2,070 feet
Mean annual precipitation: 39 to 43 inches
Mean annual air temperature: 50 to 53 degrees F
Frost-free period: 155 to 177 days
Farmland classification: Not prime farmland

Map Unit Composition

Dekalb and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Dekalb

Setting

Landform: Mountain slopes
Landform position (two-dimensional): Shoulder, backslope
Landform position (three-dimensional): Mountainflank
Down-slope shape: Convex, linear
Across-slope shape: Linear
Parent material: Residuum weathered from sandstone and shale

Typical profile

O_i - 0 to 1 inches: slightly decomposed plant material
A - 1 to 4 inches: very channery loam
E - 4 to 7 inches: very channery loam
B_w - 7 to 26 inches: very channery sandy loam
C - 26 to 34 inches: extremely channery sandy loam
R - 34 to 44 inches: bedrock

Properties and qualities

Slope: 25 to 100 percent
Surface area covered with cobbles, stones or boulders: 1.6 percent
Depth to restrictive feature: 20 to 40 inches to lithic bedrock
Drainage class: Well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (K_{sat}): Moderately high to high
(0.57 to 5.95 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None

Custom Soil Resource Report

Available water capacity: Very low (about 2.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: A

Hydric soil rating: No

Minor Components

Clymer

Percent of map unit: 5 percent

Landform: Mountain slopes

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Mountainflank

Down-slope shape: Convex, linear

Across-slope shape: Linear

Hydric soil rating: No

Hazleton

Percent of map unit: 5 percent

Landform: Mountain slopes

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Mountainflank

Down-slope shape: Convex, linear

Across-slope shape: Linear

Hydric soil rating: No

GP—Pit, Shale, and Gravel

Map Unit Setting

National map unit symbol: bqyf

Mean annual precipitation: 36 to 46 inches

Mean annual air temperature: 46 to 56 degrees F

Frost-free period: 135 to 170 days

Farmland classification: Not prime farmland

Map Unit Composition

Pits, shale: 51 percent

Pits, gravel: 49 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Pits, Shale

Typical profile

C - 0 to 1 inches: channers

R - 1 to 2 inches: bedrock

Properties and qualities

Slope: 0 to 40 percent

Depth to restrictive feature: 0 to 2 inches to paralithic bedrock

Custom Soil Resource Report

Drainage class: Excessively drained
Runoff class: Medium

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 8e
Hydric soil rating: No

Description of Pits, Gravel

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 8e
Hydric soil rating: No

HaB—Hartleton channery silt loam, 2 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9yb2
Elevation: 500 to 1,500 feet
Mean annual precipitation: 36 to 46 inches
Mean annual air temperature: 45 to 55 degrees F
Frost-free period: 140 to 175 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Hartleton and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hartleton

Setting

Landform: — error in exists on —
Landform position (two-dimensional): Shoulder, backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Linear, concave
Across-slope shape: Linear, concave
Parent material: Residuum weathered from sandstone and shale

Typical profile

H1 - 0 to 8 inches: channery silt loam
H2 - 8 to 37 inches: very channery silt loam
H3 - 37 to 50 inches: very channery loam
R - 50 to 54 inches: weathered bedrock

Properties and qualities

Slope: 2 to 8 percent
Depth to restrictive feature: 40 to 80 inches to lithic bedrock
Drainage class: Well drained
Runoff class: Medium

Custom Soil Resource Report

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2e

Hydrologic Soil Group: B

Hydric soil rating: No

HaC—Hartleton channery silt loam, 8 to 20 percent slopes

Map Unit Setting

National map unit symbol: 9yb3

Elevation: 500 to 1,500 feet

Mean annual precipitation: 36 to 46 inches

Mean annual air temperature: 45 to 55 degrees F

Frost-free period: 140 to 175 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Hartleton and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Hartleton

Setting

Landform: — error in exists on —

Landform position (two-dimensional): Shoulder, backslope

Landform position (three-dimensional): Side slope

Down-slope shape: Linear, concave

Across-slope shape: Linear, concave

Parent material: Residuum weathered from sandstone and shale

Typical profile

H1 - 0 to 8 inches: channery silt loam

H2 - 8 to 37 inches: very channery silt loam

H3 - 37 to 50 inches: very channery loam

R - 50 to 54 inches: weathered bedrock

Properties and qualities

Slope: 8 to 20 percent

Depth to restrictive feature: 40 to 80 inches to lithic bedrock

Drainage class: Well drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Custom Soil Resource Report

Frequency of ponding: None
Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: B
Hydric soil rating: No

Hy—Holly silt loam

Map Unit Setting

National map unit symbol: 9yb6
Elevation: 800 to 840 feet
Mean annual precipitation: 30 to 40 inches
Mean annual air temperature: 48 to 54 degrees F
Frost-free period: 133 to 187 days
Farmland classification: Not prime farmland

Map Unit Composition

Holly and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Holly

Setting

Landform: Backswamps, depressions on flood plains
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Linear
Parent material: Loamy alluvium derived from sandstone and shale

Typical profile

H1 - 0 to 8 inches: silt loam
H2 - 8 to 28 inches: very fine sandy loam
H3 - 28 to 41 inches: loam
H4 - 41 to 60 inches: stratified gravelly sand to silt loam

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Poorly drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)
Depth to water table: About 0 to 6 inches
Frequency of flooding: FrequentNone
Frequency of ponding: None
Available water capacity: High (about 10.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Custom Soil Resource Report

Land capability classification (nonirrigated): 3w
Hydrologic Soil Group: B/D
Hydric soil rating: Yes

KaB—Kedron silt loam, 2 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9yb7
Elevation: 520 to 1,100 feet
Mean annual precipitation: 34 to 51 inches
Mean annual air temperature: 40 to 50 degrees F
Frost-free period: 100 to 160 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Kedron and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Kedron

Setting

Landform: Drainageways
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Colluvium and/or till derived from sandstone, siltstone, and shale

Typical profile

H1 - 0 to 10 inches: silt loam
H2 - 10 to 24 inches: silt loam
H3 - 24 to 60 inches: gravelly loam

Properties and qualities

Slope: 2 to 8 percent
Depth to restrictive feature: 20 to 32 inches to fragipan
Drainage class: Moderately well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 6 to 36 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2w
Hydrologic Soil Group: C/D
Hydric soil rating: No

Minor Components

Shelmadine

Percent of map unit: 5 percent
Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

KvB—Klinesville channery silt loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9ybb
Elevation: 300 to 1,300 feet
Mean annual precipitation: 36 to 50 inches
Mean annual air temperature: 46 to 57 degrees F
Frost-free period: 130 to 200 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Klinesville, frost churned, and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Klinesville, Frost Churned

Setting

Landform: Ridges, valleys
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Residuum weathered from siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam
H2 - 6 to 15 inches: very channery silt loam
H3 - 15 to 40 inches: channers
R - 40 to 44 inches: unweathered bedrock

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 20 to 60 inches to lithic bedrock
Drainage class: Somewhat excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None

Custom Soil Resource Report

Available water capacity: Very low (about 1.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: D

Hydric soil rating: No

KvC—Klinesville channery silt loam, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 9ybc

Elevation: 300 to 1,300 feet

Mean annual precipitation: 36 to 50 inches

Mean annual air temperature: 46 to 57 degrees F

Frost-free period: 130 to 200 days

Farmland classification: Not prime farmland

Map Unit Composition

Klinesville, frost churned, and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Klinesville, Frost Churned

Setting

Landform: Ridges, valleys

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Side slope

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Residuum weathered from siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam

H2 - 6 to 15 inches: very channery silt loam

H3 - 15 to 40 inches: channers

R - 40 to 44 inches: unweathered bedrock

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 20 to 60 inches to lithic bedrock

Drainage class: Somewhat excessively drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Very low (about 1.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Custom Soil Resource Report

Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: D
Hydric soil rating: No

KvD—Klinesville channery silt loam, 15 to 25 percent slopes

Map Unit Setting

National map unit symbol: 9ybd
Elevation: 300 to 1,300 feet
Mean annual precipitation: 36 to 50 inches
Mean annual air temperature: 46 to 57 degrees F
Frost-free period: 130 to 200 days
Farmland classification: Not prime farmland

Map Unit Composition

Klinesville, frost churned, and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Klinesville, Frost Churned

Setting

Landform: Valleys, ridges
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Residuum weathered from siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam
H2 - 6 to 15 inches: very channery silt loam
H3 - 15 to 40 inches: channers
R - 40 to 44 inches: unweathered bedrock

Properties and qualities

Slope: 15 to 25 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 20 to 60 inches to lithic bedrock
Drainage class: Somewhat excessively drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 1.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: D
Hydric soil rating: No

LgB—Laidig extremely stony loam, 0 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9ybm
Elevation: 400 to 3,800 feet
Mean annual precipitation: 34 to 40 inches
Mean annual air temperature: 50 to 57 degrees F
Frost-free period: 120 to 175 days
Farmland classification: Not prime farmland

Map Unit Composition

Laidig and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Laidig

Setting

Landform: Mountains
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Colluvium derived from sandstone and siltstone

Typical profile

H1 - 0 to 6 inches: very gravelly loam
H2 - 6 to 33 inches: gravelly loam
H3 - 33 to 65 inches: very gravelly loam

Properties and qualities

Slope: 0 to 8 percent
Surface area covered with cobbles, stones or boulders: 9.0 percent
Depth to restrictive feature: 30 to 50 inches to fragipan
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.02 to 0.60 in/hr)
Depth to water table: About 30 to 48 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: B
Hydric soil rating: No

LgC—Laidig extremely stony loam, 8 to 25 percent slopes

Map Unit Setting

National map unit symbol: 9ybn
Elevation: 400 to 3,800 feet
Mean annual precipitation: 34 to 40 inches
Mean annual air temperature: 50 to 57 degrees F
Frost-free period: 120 to 175 days
Farmland classification: Not prime farmland

Map Unit Composition

Laidig and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Laidig

Setting

Landform: Mountains
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Colluvium derived from sandstone and siltstone

Typical profile

H1 - 0 to 6 inches: very gravelly loam
H2 - 6 to 33 inches: gravelly loam
H3 - 33 to 65 inches: very gravelly loam

Properties and qualities

Slope: 8 to 25 percent
Surface area covered with cobbles, stones or boulders: 9.0 percent
Depth to restrictive feature: 30 to 50 inches to fragipan
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.02 to 0.60 in/hr)
Depth to water table: About 30 to 48 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: B
Hydric soil rating: No

LkB—Leck kill channery silt loam, 2 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9ybq
Elevation: 500 to 1,500 feet
Mean annual precipitation: 38 to 46 inches
Mean annual air temperature: 45 to 54 degrees F
Frost-free period: 140 to 170 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Leck kill and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Leck Kill

Setting

Landform: Mountains
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Mountainflank
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Reddish residuum derived from sedimentary rock

Typical profile

H1 - 0 to 10 inches: channery silt loam
H2 - 10 to 27 inches: channery silty clay loam
H3 - 27 to 48 inches: very channery silt loam
R - 48 to 52 inches: unweathered bedrock

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: 40 to 60 inches to lithic bedrock
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 5.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: A
Hydric soil rating: No

LkC—Leck kill channery silt loam, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 9ybr

Elevation: 500 to 1,500 feet

Mean annual precipitation: 38 to 46 inches

Mean annual air temperature: 45 to 54 degrees F

Frost-free period: 140 to 170 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Leck kill and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Leck Kill

Setting

Landform: Mountains

Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Mountainflank

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Reddish residuum derived from sedimentary rock

Typical profile

H1 - 0 to 10 inches: channery silt loam

H2 - 10 to 27 inches: channery silty clay loam

H3 - 27 to 48 inches: very channery silt loam

R - 48 to 52 inches: unweathered bedrock

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: 40 to 60 inches to lithic bedrock

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 5.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: A

Hydric soil rating: No

LkD—Leck kill channery silt loam, 15 to 25 percent slopes

Map Unit Setting

National map unit symbol: 9ybs
Elevation: 300 to 2,800 feet
Mean annual precipitation: 34 to 50 inches
Mean annual air temperature: 45 to 57 degrees F
Frost-free period: 120 to 200 days
Farmland classification: Not prime farmland

Map Unit Composition

Leck kill and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Leck Kill

Setting

Landform: Hillslopes
Landform position (two-dimensional): Summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Linear, convex
Across-slope shape: Convex, linear
Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 10 inches: channery silt loam
H2 - 10 to 43 inches: channery silt loam
H3 - 43 to 58 inches: very channery silt loam
R - 58 to 62 inches: unweathered bedrock

Properties and qualities

Slope: 15 to 25 percent
Depth to restrictive feature: 40 to 80 inches to lithic bedrock
Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Moderate (about 7.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: A
Hydric soil rating: No

Minor Components

Calvin

Percent of map unit: 10 percent
Hydric soil rating: No

Klinesville

Percent of map unit: 5 percent
Hydric soil rating: No

Meckesville

Percent of map unit: 5 percent
Landform: Mountain valleys
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank
Down-slope shape: Concave
Across-slope shape: Linear
Hydric soil rating: No

LsC—Lordstown channery silt loam, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 2wz1
Elevation: 330 to 2,460 feet
Mean annual precipitation: 31 to 70 inches
Mean annual air temperature: 39 to 52 degrees F
Frost-free period: 105 to 180 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Lordstown and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Lordstown

Setting

Landform: Mountains, hills
Landform position (two-dimensional): Shoulder, backslope
Landform position (three-dimensional): Mountaintop, crest, nose slope
Down-slope shape: Convex
Across-slope shape: Linear
Parent material: Loamy till derived from sandstone and siltstone

Typical profile

Ap - 0 to 9 inches: channery silt loam
Bw1 - 9 to 17 inches: channery silt loam
Bw2 - 17 to 24 inches: very channery silt loam
C - 24 to 30 inches: extremely channery silt loam
2R - 30 to 40 inches: bedrock

Custom Soil Resource Report

Properties and qualities

Slope: 8 to 15 percent
Surface area covered with cobbles, stones or boulders: 0.0 percent
Depth to restrictive feature: 20 to 40 inches to lithic bedrock
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.14 to 1.42 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Maximum salinity: Nonsaline (0.0 to 1.9 mmhos/cm)
Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: C
Hydric soil rating: No

Minor Components

Mardin

Percent of map unit: 5 percent
Landform: Mountains, hills
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Interflue, side slope
Down-slope shape: Convex
Across-slope shape: Convex
Hydric soil rating: No

Arnot

Percent of map unit: 5 percent
Landform: Mountains, hills
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Mountaintop, interflue, crest
Down-slope shape: Convex
Across-slope shape: Convex
Hydric soil rating: No

LxC—Lordstown channery silt loam, 8 to 25 percent slopes, rubbly

Map Unit Setting

National map unit symbol: 2wzm9
Elevation: 330 to 2,460 feet
Mean annual precipitation: 31 to 70 inches
Mean annual air temperature: 39 to 52 degrees F
Frost-free period: 105 to 180 days
Farmland classification: Not prime farmland

Map Unit Composition

Lordstown, rubbly, and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Lordstown, Rubbly

Setting

Landform: Mountains, hills

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Mountainflank, crest, nose slope, side slope

Down-slope shape: Convex, linear

Across-slope shape: Linear

Parent material: Loamy till derived from sandstone and siltstone

Typical profile

Oe - 0 to 1 inches: moderately decomposed plant material

A - 1 to 5 inches: channery highly organic silt loam

Bw1 - 5 to 17 inches: channery silt loam

Bw2 - 17 to 24 inches: very channery silt loam

C - 24 to 30 inches: extremely channery silt loam

2R - 30 to 40 inches: bedrock

Properties and qualities

Slope: 8 to 25 percent

Surface area covered with cobbles, stones or boulders: 15.0 percent

Depth to restrictive feature: 20 to 40 inches to lithic bedrock

Drainage class: Well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.14 to 1.42 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Maximum salinity: Nonsaline (0.0 to 1.9 mmhos/cm)

Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7s

Hydrologic Soil Group: C

Hydric soil rating: No

Minor Components

Arnot, very stony

Percent of map unit: 5 percent

Landform: Mountains, hills

Landform position (two-dimensional): Shoulder, backslope, summit

Landform position (three-dimensional): Mountaintop, mountainflank, crest, nose slope, interfluve

Down-slope shape: Convex

Across-slope shape: Linear, convex

Hydric soil rating: No

Bath, rubbly

Percent of map unit: 5 percent
Landform: Hills, mountains
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Interfluve, side slope, nose slope
Down-slope shape: Convex, linear
Across-slope shape: Linear
Hydric soil rating: No

Cadosia, extremely stony

Percent of map unit: 5 percent
Landform: Ridges
Landform position (two-dimensional): Backslope, footslope
Landform position (three-dimensional): Side slope
Down-slope shape: Concave
Across-slope shape: Linear
Hydric soil rating: No

MeA—Meckesville gravelly loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 9yc4
Elevation: 600 to 2,800 feet
Mean annual precipitation: 34 to 48 inches
Mean annual air temperature: 46 to 55 degrees F
Frost-free period: 130 to 190 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Meckesville and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Meckesville

Setting

Landform: Mountain valleys
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank
Down-slope shape: Concave
Across-slope shape: Linear
Parent material: Sandstone, siltstone and shale colluvium derived from sedimentary rock

Typical profile

H1 - 0 to 9 inches: gravelly loam
H2 - 9 to 36 inches: channery loam
H3 - 36 to 60 inches: channery loam
H4 - 60 to 64 inches: very channery loam

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: 25 to 48 inches to fragipan
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: About 30 to 48 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 5.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 1
Hydrologic Soil Group: C
Hydric soil rating: No

MeB—Meckesville gravelly loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9yc5
Elevation: 600 to 2,800 feet
Mean annual precipitation: 34 to 48 inches
Mean annual air temperature: 46 to 55 degrees F
Frost-free period: 130 to 190 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Meckesville and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Meckesville

Setting

Landform: Mountain valleys
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank
Down-slope shape: Concave
Across-slope shape: Linear
Parent material: Sandstone, siltstone and shale colluvium derived from sedimentary rock

Typical profile

H1 - 0 to 9 inches: gravelly loam
H2 - 9 to 36 inches: channery loam
H3 - 36 to 60 inches: channery loam
H4 - 60 to 64 inches: very channery loam

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: 25 to 48 inches to fragipan

Custom Soil Resource Report

Drainage class: Well drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)
Depth to water table: About 30 to 48 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 5.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C
Hydric soil rating: No

MeC—Meckesville gravelly loam, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 9yc6
Elevation: 600 to 2,800 feet
Mean annual precipitation: 34 to 48 inches
Mean annual air temperature: 46 to 55 degrees F
Frost-free period: 130 to 190 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Meckesville and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Meckesville

Setting

Landform: Mountain valleys
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank
Down-slope shape: Concave
Across-slope shape: Linear
Parent material: Sandstone, siltstone and shale colluvium derived from sedimentary rock

Typical profile

H1 - 0 to 9 inches: gravelly loam
H2 - 9 to 36 inches: channery loam
H3 - 36 to 60 inches: channery loam
H4 - 60 to 64 inches: very channery loam

Properties and qualities

Slope: 8 to 15 percent
Depth to restrictive feature: 25 to 48 inches to fragipan
Drainage class: Well drained
Runoff class: Medium

Custom Soil Resource Report

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)

Depth to water table: About 30 to 48 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 5.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: C

Hydric soil rating: No

MfB—Meckesville very stony loam, 0 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9yc7

Elevation: 600 to 2,800 feet

Mean annual precipitation: 34 to 48 inches

Mean annual air temperature: 46 to 55 degrees F

Frost-free period: 130 to 190 days

Farmland classification: Not prime farmland

Map Unit Composition

Meckesville and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Meckesville

Setting

Landform: Mountain valleys

Landform position (two-dimensional): Footslope

Landform position (three-dimensional): Lower third of mountainflank

Down-slope shape: Concave

Across-slope shape: Linear

Parent material: Sandstone, siltstone and shale colluvium derived from sedimentary rock

Typical profile

H1 - 0 to 9 inches: gravelly loam

H2 - 9 to 36 inches: channery loam

H3 - 36 to 60 inches: channery loam

Properties and qualities

Slope: 0 to 8 percent

Surface area covered with cobbles, stones or boulders: 1.6 percent

Depth to restrictive feature: 25 to 48 inches to fragipan

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high (0.20 to 0.60 in/hr)

Depth to water table: About 30 to 48 inches

Custom Soil Resource Report

Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 4.5 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6s
Hydrologic Soil Group: C
Hydric soil rating: No

MoB—Morris channery silt loam, 0 to 8 percent slopes, extremely stony

Map Unit Setting

National map unit symbol: 2vxct
Elevation: 330 to 2,460 feet
Mean annual precipitation: 31 to 70 inches
Mean annual air temperature: 39 to 52 degrees F
Frost-free period: 105 to 180 days
Farmland classification: Not prime farmland

Map Unit Composition

Morris, extremely stony, and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Morris, Extremely Stony

Setting

Landform: Hills, mountains
Landform position (two-dimensional): Summit, footslope
Landform position (three-dimensional): Interfluve, base slope
Down-slope shape: Concave
Across-slope shape: Linear
Parent material: Loamy till from reddish sandstone, siltstone, and shale

Typical profile

Oe - 0 to 1 inches: moderately decomposed plant material
A - 1 to 5 inches: channery silt loam
Bw - 5 to 12 inches: channery silt loam
Eg - 12 to 16 inches: channery silt loam
Bx - 16 to 60 inches: channery silt loam
C - 60 to 72 inches: channery loam

Properties and qualities

Slope: 0 to 8 percent
Surface area covered with cobbles, stones or boulders: 7.0 percent
Depth to restrictive feature: 10 to 22 inches to fragipan
Drainage class: Somewhat poorly drained
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.14 in/hr)
Depth to water table: About 6 to 18 inches
Frequency of flooding: None

Custom Soil Resource Report

Frequency of ponding: None
Available water capacity: Very low (about 2.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: D
Hydric soil rating: No

Minor Components

Norwich, extremely stony

Percent of map unit: 5 percent
Landform: Depressions
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: Yes

Wellsboro, extremely stony

Percent of map unit: 5 percent
Landform: Hills, mountains
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Interfluve, side slope, head slope
Down-slope shape: Convex, concave
Across-slope shape: Convex, linear
Hydric soil rating: No

Pp—Pope silt loam, high bottom

Map Unit Setting

National map unit symbol: 9ycp
Elevation: 590 to 1,970 feet
Mean annual precipitation: 30 to 51 inches
Mean annual air temperature: 40 to 54 degrees F
Frost-free period: 100 to 187 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Pope and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Pope

Setting

Landform: Flood plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Coarse-loamy alluvium derived from sandstone and siltstone

Custom Soil Resource Report

Typical profile

H1 - 0 to 10 inches: silt loam
H2 - 10 to 30 inches: silt loam
H3 - 30 to 60 inches: loamy very fine sand

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 2.00 in/hr)
Depth to water table: About 48 to 72 inches
Frequency of flooding: RareNone
Frequency of ponding: None
Available water capacity: Moderate (about 8.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 1
Hydrologic Soil Group: B
Ecological site: F140XY013PA - High Floodplain
Hydric soil rating: No

Minor Components

Holly

Percent of map unit: 10 percent
Landform: Backswamps, depressions on flood plains
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Base slope
Down-slope shape: Concave
Across-slope shape: Linear
Hydric soil rating: Yes

ReA—Rexford gravelly silt loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 9ycq
Elevation: 590 to 1,970 feet
Mean annual precipitation: 34 to 56 inches
Mean annual air temperature: 40 to 54 degrees F
Frost-free period: 100 to 175 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Rexford, somewhat poorly drained, and similar soils: 50 percent
Rexford, poorly drained, and similar soils: 40 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Rexford, Somewhat Poorly Drained

Setting

Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Coarse-loamy outwash derived from sandstone and shale

Typical profile

Ap - 0 to 8 inches: silt loam
Bw - 8 to 18 inches: silt loam
Bx - 18 to 40 inches: gravelly loam
2C - 40 to 63 inches: Error

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: 15 to 24 inches to fragipan
Drainage class: Somewhat poorly drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 2 to 10 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 1.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3w
Hydrologic Soil Group: D
Ecological site: F140XY020NY - Dense Outwash
Hydric soil rating: No

Description of Rexford, Poorly Drained

Setting

Landform: Depressions
Down-slope shape: Concave
Across-slope shape: Concave
Parent material: Coarse-loamy outwash derived from sandstone and shale

Typical profile

Ap - 0 to 8 inches: silt loam
Bw - 8 to 18 inches: silt loam
Bx - 18 to 40 inches: gravelly loam
2C - 40 to 63 inches: Error

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: 15 to 24 inches to fragipan
Drainage class: Poorly drained
Runoff class: Negligible
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 0 inches
Frequency of flooding: None
Frequency of ponding: None

Custom Soil Resource Report

Available water capacity: Very low (about 1.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3w

Hydrologic Soil Group: D

Ecological site: F140XY016NY - Mineral Wetlands

Hydric soil rating: Yes

Minor Components

Braceville

Percent of map unit: 10 percent

Landform: Outwash terraces

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Tread

Down-slope shape: Linear, convex

Across-slope shape: Linear, concave

Hydric soil rating: No

SpB—Shelmadine very stony silt loam, 0 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9ycx

Elevation: 480 to 2,150 feet

Mean annual precipitation: 36 to 46 inches

Mean annual air temperature: 44 to 59 degrees F

Frost-free period: 130 to 180 days

Farmland classification: Not prime farmland

Map Unit Composition

Shelmadine and similar soils: 80 percent

Minor components: 20 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Shelmadine

Setting

Landform: Depressions

Down-slope shape: Concave

Across-slope shape: Concave

Parent material: Loamy till

Typical profile

H1 - 0 to 7 inches: channery silt loam

H2 - 7 to 24 inches: silty clay loam

H3 - 24 to 50 inches: channery loam

H4 - 50 to 70 inches: channery loam

Custom Soil Resource Report

Properties and qualities

Slope: 0 to 3 percent
Surface area covered with cobbles, stones or boulders: 1.6 percent
Depth to restrictive feature: 18 to 30 inches to fragipan
Drainage class: Poorly drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 0 to 6 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: C/D
Hydric soil rating: Yes

Minor Components

Buchanan

Percent of map unit: 10 percent
Hydric soil rating: No

Watson

Percent of map unit: 5 percent
Hydric soil rating: No

Alvira

Percent of map unit: 5 percent
Landform: Hillslopes
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Interfluvium
Down-slope shape: Concave
Across-slope shape: Concave
Hydric soil rating: No

VaE—Very stony land and Rock outcrops, steep

Map Unit Setting

National map unit symbol: 9yd3
Elevation: 1,100 to 2,500 feet
Mean annual precipitation: 36 to 55 inches
Mean annual air temperature: 46 to 55 degrees F
Frost-free period: 100 to 160 days
Farmland classification: Not prime farmland

Map Unit Composition

Dystrochrepts, very stony, and similar soils: 100 percent

Custom Soil Resource Report

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Dystrochrepts, Very Stony

Setting

Landform: Mountain slopes
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Mountainflank
Down-slope shape: Linear, convex
Across-slope shape: Linear, convex

Typical profile

H1 - 0 to 6 inches: very channery loam
H2 - 6 to 32 inches: very channery loam
H3 - 32 to 56 inches: extremely channery loam
H4 - 56 to 60 inches: unweathered bedrock

Properties and qualities

Slope: 25 to 99 percent
Surface area covered with cobbles, stones or boulders: 1.6 percent
Depth to restrictive feature: 40 inches to lithic bedrock
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7s
Hydrologic Soil Group: A
Hydric soil rating: No

W—Water

Map Unit Setting

National map unit symbol: 9ydz
Mean annual precipitation: 34 to 51 inches
Mean annual air temperature: 40 to 50 degrees F
Frost-free period: 100 to 160 days
Farmland classification: Not prime farmland

Map Unit Composition

Water: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

WaB—Watson silt loam, 2 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9yd8
Elevation: 430 to 1,850 feet
Mean annual precipitation: 36 to 46 inches
Mean annual air temperature: 40 to 60 degrees F
Frost-free period: 130 to 180 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Watson and similar soils: 80 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Watson

Setting

Landform: Valley sides
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Base slope
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Old till derived from sedimentary rock

Typical profile

H1 - 0 to 9 inches: silt loam
H2 - 9 to 27 inches: gravelly silty clay loam
H3 - 27 to 45 inches: gravelly clay loam
H4 - 45 to 61 inches: channery loam

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Moderately well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)
Depth to water table: About 18 to 33 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.9 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: C
Hydric soil rating: No

Minor Components

Allenwood

Percent of map unit: 10 percent

Hydric soil rating: No

Shelmadine

Percent of map unit: 5 percent

Landform: Drainageways

Down-slope shape: Concave

Across-slope shape: Concave

Hydric soil rating: Yes

Alvira

Percent of map unit: 5 percent

Landform: Hillslopes

Landform position (two-dimensional): Footslope

Landform position (three-dimensional): Interfluve

Down-slope shape: Concave

Across-slope shape: Concave

Hydric soil rating: No

Wb—Wayland silty clay loam

Map Unit Setting

National map unit symbol: 9yd9

Elevation: 200 to 1,500 feet

Mean annual precipitation: 30 to 40 inches

Mean annual air temperature: 45 to 54 degrees F

Frost-free period: 110 to 180 days

Farmland classification: Not prime farmland

Map Unit Composition

Wayland and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wayland

Setting

Landform: Flood plains

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Talf

Down-slope shape: Concave

Across-slope shape: Linear

Parent material: Recent alluvium

Typical profile

H1 - 0 to 9 inches: silty clay loam

H2 - 9 to 41 inches: silty clay loam

H3 - 41 to 60 inches: very gravelly loam

Properties and qualities

Slope: 0 to 3 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Very poorly drained

Custom Soil Resource Report

Runoff class: Negligible

Capacity of the most limiting layer to transmit water (Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 0 inches

Frequency of flooding: FrequentNone

Frequency of ponding: Frequent

Available water capacity: High (about 10.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4w

Hydrologic Soil Group: C/D

Hydric soil rating: Yes

WeB3—Weikert channery silt loam, 3 to 8 percent slopes, eroded

Map Unit Setting

National map unit symbol: 9ydb

Elevation: 500 to 1,600 feet

Mean annual precipitation: 36 to 50 inches

Mean annual air temperature: 46 to 57 degrees F

Frost-free period: 120 to 200 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Weikert and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Weikert

Setting

Landform: Hills

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Side slope, crest

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam

H2 - 6 to 15 inches: very channery silt loam

H3 - 15 to 45 inches: channers

R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 3 to 8 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 40 to 60 inches to lithic bedrock

Drainage class: Somewhat excessively drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Custom Soil Resource Report

Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: D
Hydric soil rating: No

WeC3—Weikert channery silt loam, 8 to 15 percent slopes, eroded

Map Unit Setting

National map unit symbol: 9ydc
Elevation: 500 to 1,600 feet
Mean annual precipitation: 36 to 50 inches
Mean annual air temperature: 46 to 57 degrees F
Frost-free period: 120 to 200 days
Farmland classification: Not prime farmland

Map Unit Composition

Weikert and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Weikert

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope, crest
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam
H2 - 6 to 15 inches: very channery silt loam
H3 - 15 to 45 inches: channers
R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 8 to 15 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 40 to 60 inches to lithic bedrock
Drainage class: Somewhat excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None

Custom Soil Resource Report

Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: D

Hydric soil rating: No

WeD3—Weikert channery silt loam, 15 to 25 percent slopes, eroded

Map Unit Setting

National map unit symbol: 9ydd

Elevation: 500 to 1,600 feet

Mean annual precipitation: 36 to 50 inches

Mean annual air temperature: 46 to 57 degrees F

Frost-free period: 120 to 200 days

Farmland classification: Not prime farmland

Map Unit Composition

Weikert and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Weikert

Setting

Landform: Hills

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Side slope, crest

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam

H2 - 6 to 15 inches: very channery silt loam

H3 - 15 to 45 inches: channers

R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 15 to 25 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 40 to 60 inches to lithic bedrock

Drainage class: Somewhat excessively drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Custom Soil Resource Report

Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: D
Hydric soil rating: No

WhB—Weikert-Hartleton channery silt loams, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9ydf
Elevation: 300 to 1,600 feet
Mean annual precipitation: 36 to 50 inches
Mean annual air temperature: 45 to 57 degrees F
Frost-free period: 120 to 200 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Weikert and similar soils: 50 percent
Hartleton and similar soils: 40 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Weikert

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope, crest
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam
H2 - 6 to 15 inches: very channery silt loam
H3 - 15 to 45 inches: channers
R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 40 to 60 inches to lithic bedrock
Drainage class: Somewhat excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e

Custom Soil Resource Report

Hydrologic Soil Group: D
Hydric soil rating: No

Description of Hartleton

Setting

Landform: — error in exists on —
Landform position (two-dimensional): Shoulder, backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Linear, concave
Across-slope shape: Linear, concave
Parent material: Residuum weathered from sandstone and shale

Typical profile

H1 - 0 to 8 inches: channery silt loam
H2 - 8 to 37 inches: very channery silt loam
H3 - 37 to 50 inches: very channery loam
R - 50 to 54 inches: weathered bedrock

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: 40 to 80 inches to lithic bedrock
Drainage class: Well drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: A
Hydric soil rating: No

Minor Components

Klinesville, frost churned

Percent of map unit: 5 percent
Landform: Ridges, valleys
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope
Down-slope shape: Convex
Across-slope shape: Convex
Hydric soil rating: No

Leck kill

Percent of map unit: 5 percent
Landform: Mountains
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Mountainflank
Down-slope shape: Convex
Across-slope shape: Convex
Hydric soil rating: No

WhC—Weikert-Hartleton channery silt loams, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 9ydg

Elevation: 300 to 1,600 feet

Mean annual precipitation: 36 to 50 inches

Mean annual air temperature: 45 to 57 degrees F

Frost-free period: 120 to 200 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Weikert and similar soils: 55 percent

Hartleton and similar soils: 35 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Weikert

Setting

Landform: Hills

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Side slope, crest

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam

H2 - 6 to 15 inches: very channery silt loam

H3 - 15 to 45 inches: channers

R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 40 to 60 inches to lithic bedrock

Drainage class: Somewhat excessively drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: D

Custom Soil Resource Report

Hydric soil rating: No

Description of Hartleton

Setting

Landform: — error in exists on —

Landform position (two-dimensional): Shoulder, backslope

Landform position (three-dimensional): Side slope

Down-slope shape: Linear, concave

Across-slope shape: Linear, concave

Parent material: Residuum weathered from sandstone and shale

Typical profile

H1 - 0 to 8 inches: channery silt loam

H2 - 8 to 37 inches: very channery silt loam

H3 - 37 to 50 inches: very channery loam

R - 50 to 54 inches: weathered bedrock

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: 40 to 80 inches to lithic bedrock

Drainage class: Well drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: A

Hydric soil rating: No

Minor Components

Klinesville, frost churned

Percent of map unit: 5 percent

Landform: Ridges, valleys

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Side slope

Down-slope shape: Convex

Across-slope shape: Convex

Hydric soil rating: No

Leck kill

Percent of map unit: 5 percent

Landform: Mountains

Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Mountainflank

Down-slope shape: Convex

Across-slope shape: Convex

Hydric soil rating: No

WhD—Weikert-Hartleton channery silt loams, 15 to 25 percent slopes

Map Unit Setting

National map unit symbol: 9ydh
Elevation: 300 to 1,600 feet
Mean annual precipitation: 36 to 50 inches
Mean annual air temperature: 45 to 57 degrees F
Frost-free period: 120 to 200 days
Farmland classification: Not prime farmland

Map Unit Composition

Weikert and similar soils: 60 percent
Hartleton and similar soils: 30 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Weikert

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope, crest
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam
H2 - 6 to 15 inches: very channery silt loam
H3 - 15 to 45 inches: channers
R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 15 to 25 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 40 to 60 inches to lithic bedrock
Drainage class: Somewhat excessively drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: D

Custom Soil Resource Report

Hydric soil rating: No

Description of Hartleton

Setting

Landform: — error in exists on —

Landform position (two-dimensional): Shoulder, backslope

Landform position (three-dimensional): Side slope

Down-slope shape: Linear, concave

Across-slope shape: Linear, concave

Parent material: Residuum weathered from sandstone and shale

Typical profile

H1 - 0 to 8 inches: channery silt loam

H2 - 8 to 37 inches: very channery silt loam

H3 - 37 to 50 inches: very channery loam

R - 50 to 54 inches: weathered bedrock

Properties and qualities

Slope: 15 to 25 percent

Depth to restrictive feature: 40 to 80 inches to lithic bedrock

Drainage class: Well drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high
(0.60 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 4.1 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: A

Hydric soil rating: No

Minor Components

Leck kill

Percent of map unit: 5 percent

Landform: Mountains

Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Mountainflank

Down-slope shape: Convex

Across-slope shape: Convex

Hydric soil rating: No

Klinesville, frost churned

Percent of map unit: 5 percent

Landform: Ridges, valleys

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Side slope

Down-slope shape: Convex

Across-slope shape: Convex

Hydric soil rating: No

WKE—Weikert and Klinesville soils, steep

Map Unit Setting

National map unit symbol: 9yd7
Elevation: 300 to 2,800 feet
Mean annual precipitation: 34 to 50 inches
Mean annual air temperature: 45 to 57 degrees F
Frost-free period: 120 to 200 days
Farmland classification: Not prime farmland

Map Unit Composition

Weikert and similar soils: 50 percent
Klinesville, frost churned, and similar soils: 30 percent
Minor components: 20 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Weikert

Setting

Landform: Hills
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Side slope, crest
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Residuum weathered from shale and siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam
H2 - 6 to 15 inches: very channery silt loam
H3 - 15 to 45 inches: channers
R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 25 to 80 percent
Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 40 to 60 inches to lithic bedrock
Drainage class: Somewhat excessively drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 7e
Hydrologic Soil Group: D

Custom Soil Resource Report

Hydric soil rating: No

Description of Klinesville, Frost Churned

Setting

Landform: Ridges, valleys

Landform position (two-dimensional): Backslope, shoulder

Landform position (three-dimensional): Side slope

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Residuum weathered from siltstone

Typical profile

H1 - 0 to 6 inches: very channery silt loam

H2 - 6 to 15 inches: very channery silt loam

H3 - 15 to 45 inches: channers

R - 45 to 49 inches: unweathered bedrock

Properties and qualities

Slope: 25 to 80 percent

Depth to restrictive feature: 10 to 20 inches to lithic bedrock; 20 to 60 inches to lithic bedrock

Drainage class: Somewhat excessively drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Very low (about 1.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 7e

Hydrologic Soil Group: D

Hydric soil rating: No

Minor Components

Hartleton

Percent of map unit: 8 percent

Landform: — error in exists on —

Landform position (two-dimensional): Shoulder, backslope

Landform position (three-dimensional): Side slope

Down-slope shape: Linear, concave

Across-slope shape: Linear, concave

Hydric soil rating: No

Leck kill

Percent of map unit: 8 percent

Landform: Mountains

Landform position (two-dimensional): Backslope

Landform position (three-dimensional): Mountainflank

Down-slope shape: Convex

Across-slope shape: Convex

Hydric soil rating: No

Meckesville

Percent of map unit: 4 percent
Landform: Mountain valleys
Landform position (two-dimensional): Footslope
Landform position (three-dimensional): Lower third of mountainflank
Down-slope shape: Concave
Across-slope shape: Linear
Hydric soil rating: No

WyA—Wyoming gravelly sandy loam, 0 to 3 percent slopes

Map Unit Setting

National map unit symbol: 9ydt
Elevation: 400 to 1,800 feet
Mean annual precipitation: 30 to 56 inches
Mean annual air temperature: 45 to 54 degrees F
Frost-free period: 110 to 180 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Wyoming and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wyoming

Setting

Landform: Terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Riser
Down-slope shape: Linear
Across-slope shape: Linear

Typical profile

H1 - 0 to 7 inches: gravelly sandy loam
H2 - 7 to 25 inches: very gravelly sandy loam
H3 - 25 to 60 inches: extremely gravelly loamy coarse sand

Properties and qualities

Slope: 0 to 3 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Somewhat excessively drained
Runoff class: Very low
Capacity of the most limiting layer to transmit water (Ksat): High to very high (6.00 to 20.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3s
Hydrologic Soil Group: A
Hydric soil rating: No

Minor Components

Unadilla

Percent of map unit: 5 percent
Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Hydric soil rating: No

Braceville

Percent of map unit: 5 percent
Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Hydric soil rating: No

WyB—Wyoming gravelly sandy loam, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 9ydv
Elevation: 400 to 1,800 feet
Mean annual precipitation: 30 to 56 inches
Mean annual air temperature: 45 to 54 degrees F
Frost-free period: 110 to 180 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Wyoming and similar soils: 90 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wyoming

Setting

Landform: Terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Riser
Down-slope shape: Linear
Across-slope shape: Linear

Custom Soil Resource Report

Typical profile

H1 - 0 to 7 inches: gravelly sandy loam
H2 - 7 to 25 inches: very gravelly sandy loam
H3 - 25 to 60 inches: extremely gravelly loamy coarse sand

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Somewhat excessively drained
Runoff class: Low
Capacity of the most limiting layer to transmit water (Ksat): High to very high (6.00 to 20.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3s
Hydrologic Soil Group: A
Hydric soil rating: No

Minor Components

Braceville

Percent of map unit: 5 percent
Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Hydric soil rating: No

Unadilla

Percent of map unit: 5 percent
Landform: Outwash terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Linear
Hydric soil rating: No

WyC—Wyoming gravelly sandy loam, 8 to 15 percent slopes

Map Unit Setting

National map unit symbol: 9ydw
Elevation: 400 to 1,800 feet
Mean annual precipitation: 30 to 56 inches
Mean annual air temperature: 45 to 54 degrees F

Custom Soil Resource Report

Frost-free period: 110 to 180 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Wyoming and similar soils: 90 percent

Minor components: 10 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wyoming

Setting

Landform: Terraces

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Riser

Down-slope shape: Linear

Across-slope shape: Linear

Typical profile

H1 - 0 to 7 inches: gravelly sandy loam

H2 - 7 to 25 inches: very gravelly sandy loam

H3 - 25 to 60 inches: extremely gravelly loamy coarse sand

Properties and qualities

Slope: 8 to 15 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Somewhat excessively drained

Runoff class: Low

Capacity of the most limiting layer to transmit water (Ksat): High to very high (6.00 to 20.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water capacity: Low (about 3.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4s

Hydrologic Soil Group: A

Hydric soil rating: No

Minor Components

Unadilla

Percent of map unit: 5 percent

Landform: Outwash terraces

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Hydric soil rating: No

Braceville

Percent of map unit: 5 percent

Landform: Outwash terraces

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Custom Soil Resource Report

Across-slope shape: Linear
Hydric soil rating: No

WyD—Wyoming gravelly sandy loam, 15 to 25 percent slopes

Map Unit Setting

National map unit symbol: 9ydx
Elevation: 400 to 1,800 feet
Mean annual precipitation: 30 to 50 inches
Mean annual air temperature: 45 to 54 degrees F
Frost-free period: 110 to 180 days
Farmland classification: Not prime farmland

Map Unit Composition

Wyoming and similar soils: 95 percent
Minor components: 5 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wyoming

Setting

Landform: Terraces
Landform position (two-dimensional): Toeslope
Landform position (three-dimensional): Riser
Down-slope shape: Linear
Across-slope shape: Linear

Typical profile

H1 - 0 to 7 inches: gravelly sandy loam
H2 - 7 to 25 inches: very gravelly sandy loam
H3 - 25 to 60 inches: extremely gravelly loamy coarse sand

Properties and qualities

Slope: 15 to 25 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Somewhat excessively drained
Runoff class: Medium
Capacity of the most limiting layer to transmit water (Ksat): High to very high (6.00 to 20.00 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Available water capacity: Low (about 3.2 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 4e
Hydrologic Soil Group: A
Hydric soil rating: No

Minor Components

Unadilla

Percent of map unit: 5 percent

Landform: Outwash terraces

Landform position (two-dimensional): Toeslope

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear

Hydric soil rating: No

References

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

ATTACHMENT 3
E&SC AND SR PLAN BMP DESIGN WORKSHEETS
AND CALCULATIONS

TABLE OF CONTENTS

Attachment 3

- 3.1 Compost Filter Sock Worksheets
- 3.2 CN Table – Effort Loop
- 3.3 Channel Design Worksheets – Effort Loop
- 3.4 Level Spreader Design Worksheet
- 3.5 Sediment Trap Worksheet
- 3.6 Channel Design Worksheet – MLV-505LD86
- 3.7 Riprap Apron Design Worksheet

ATTACHMENT 3.1
COMPOST FILTER SOCK WORKSHEETS

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort


LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-CY-001	18	SEE MAP, CY001	4%	360
EL-CFS-CY-002	24	SEE MAP, CY001	4%	611
EL-CFS-CY-003	24	SEE MAP, CY001	4%	611
EL-CFS-CY-004	32	SEE MAP, CY001	3%	986
EL-CFS-CY-005	32	SEE MAP, CY001	3%	986
EL-CFS-CY-006	32	SEE MAP, CY001	3%	986
EL-CFS-CY-007	32	SEE MAP, CY001	3%	897
EL-CFS-CY-008	32	SEE MAP, CY001	3%	897
EL-CFS-CY-009	32	SEE MAP, CY001	3%	897
EL-CFS-CY-010	32	SEE MAP, CY001	3%	897
EL-CFS-CY-011	24	SEE MAP, CY001	3%	811
EL-CFS-CY-012	24	SEE MAP, CY001	3%	811
EL-CFS-CY-013	18	SEE MAP, CY001	2%	630
EL-CFS-CY-014	12	SEE MAP, CY001	3%	462
EL-CFS-CY-015	12	SEE MAP, CY001	3%	462
EL-CFS-CY-016	12	SEE MAP, CY001	3%	462
EL-CFS-CY-017	12	SEE MAP, CY001	3%	462
EL-CFS-CY-018	12	SEE MAP, CY001	3%	462
EL-CFS-CY-019	12	SEE MAP, CY001	2%	246
EL-CFS-CY-020	32	SEE MAP, CY001	3%	1011
EL-CFS-CY-021	32	SEE MAP, CY001	3%	1011
EL-CFS-CY-022	32	SEE MAP, CY001	3%	1011
EL-CFS-CY-023	12	SEE MAP, CY001	5%	242
EL-CFS-CY-024	12	SEE MAP, CY001	5%	242
EL-CFS-CY-025	12	SEE MAP, CY001	5%	242
EL-CFS-CY-026	12	SEE MAP, CY001	5%	242

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**

LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**


Monroe County, Pennsylvania

PREPARED BY: **JB**

DATE: **4/5/2021**

CHECKED BY: **KCC**

DATE: **4/5/2021**




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-CY-027	32	SEE MAP, CY001	6%	487
EL-CFS-CY-028	32	SEE MAP, CY001	6%	487
EL-CFS-CY-029	32	SEE MAP, CY001	6%	487
EL-CFS-CY-030	32	SEE MAP, CY001	6%	487
EL-CFS-CY-031	32	SEE MAP, CY001	6%	487
EL-CFS-CY-032	32	SEE MAP, CY001	6%	487
EL-CFS-CY-033	32	SEE MAP, CY001	6%	487
EL-CFS-CY-034	32	SEE MAP, CY001	6%	487
EL-CFS-CY-035	32	SEE MAP, CY001	6%	487
EL-CFS-CY-036	32	SEE MAP, CY001	6%	487
EL-CFS-CY-037	32	SEE MAP, CY001	6%	487
EL-CFS-CY-038	24	SEE MAP, CY001	5%	466
EL-CFS-CY-039	24	SEE MAP, CY001	5%	466
EL-CFS-CY-040	24	SEE MAP, CY001	5%	466
EL-CFS-CY-041	24	SEE MAP, CY001	5%	466
EL-CFS-CY-042	24	SEE MAP, CY001	5%	466
EL-CFS-CY-043	24	SEE MAP, CY001	5%	466
EL-CFS-CY-044	18	SEE MAP, CY001	3%	574
EL-CFS-CY-045	18	SEE MAP, CY001	3%	574
EL-CFS-CY-046	18	SEE MAP, CY001	3%	574
EL-CFS-CY-047	18	SEE MAP, CY001	3%	574
EL-CFS-CY-048	18	SEE MAP, CY001	4%	373
EL-CFS-CY-049	18	SEE MAP, CY001	4%	373
EL-CFS-CY-050	18	SEE MAP, CY001	4%	373
EL-CFS-CY-051	18	SEE MAP, CY001	4%	373
EL-CFS-CY-052	18	SEE MAP, CY001	4%	373

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-043-009	24	SEE MAP	4%	648
EL-CFS-043-010	24	SEE MAP	4%	469
EL-CFS-043-011	24	SEE MAP	4%	469
EL-CFS-043-012	24	SEE MAP	4%	469
EL-CFS-043-013	24	SEE MAP	4%	469
EL-CFS-043-014	24	SEE MAP	4%	469
EL-CFS-043-015	24	SEE MAP	4%	469
EL-CFS-043-016	24	SEE MAP	4%	469
EL-CFS-043-017	12	SEE MAP	8%	13
EL-CFS-043-018	12	SEE MAP	8%	13
EL-CFS-043-019	12	SEE MAP	8%	13
EL-CFS-043-020	12	SEE MAP	8%	13
EL-CFS-043-021	12	SEE MAP	8%	13
EL-CFS-043-022	12	SEE MAP	7%	15
EL-CFS-043-023	12	SEE MAP	7%	15
EL-CFS-043-024	12	SEE MAP	7%	15
EL-CFS-043-025	12	SEE MAP	7%	15
EL-CFS-043-026	12	SEE MAP	6%	157
EL-CFS-043-027	12	SEE MAP	6%	157
EL-CFS-043-028	12	SEE MAP	6%	157
EL-CFS-043-029	12	SEE MAP	6%	157
EL-CFS-043-030	12	SEE MAP	6%	157
EL-CFS-043-031	12	SEE MAP	6%	157
EL-CFS-043-032	18	SEE MAP	9%	232
EL-CFS-043-033	18	SEE MAP	9%	232
EL-CFS-043-034	18	SEE MAP	9%	232

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-043-035	18	SEE MAP	9%	232
EL-CFS-043-036	18	SEE MAP	9%	232
EL-CFS-043-037	24	SEE MAP	11%	231
EL-CFS-043-038	24	SEE MAP	11%	231
EL-CFS-043-039	24	SEE MAP	11%	231
EL-CFS-043-040	24	SEE MAP	11%	231
EL-CFS-043-041	24	SEE MAP	11%	231
EL-CFS-043-042	24	SEE MAP	11%	231
EL-CFS-043-043	24	SEE MAP	11%	231
EL-CFS-043-044	24	SEE MAP	11%	231
EL-CFS-043-045	24	SEE MAP	11%	231
EL-CFS-043-046	24	SEE MAP	11%	231
EL-CFS-043-047	24	SEE MAP	11%	231
EL-CFS-043-048	24	SEE MAP	11%	231
EL-CFS-043-049	12	SEE MAP	4%	249
EL-CFS-043-050	18	SEE MAP	10%	241
EL-CFS-043-051	18	SEE MAP	10%	241
EL-CFS-043-052	18	SEE MAP	10%	241
EL-CFS-043-053	24	SEE MAP	11%	231
EL-CFS-043-054	24	SEE MAP	11%	231
EL-CFS-043-055	24	SEE MAP	11%	231
EL-CFS-044-001	12	SEE MAP	4%	232
EL-CFS-044-002	12	SEE MAP	4%	232
EL-CFS-044-003	12	SEE MAP	4%	232
EL-CFS-044-004	18	SEE MAP	9%	179
EL-CFS-044-005	18	SEE MAP	9%	179

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-006	18	SEE MAP	9%	179
EL-CFS-044-007	18	SEE MAP	9%	179
EL-CFS-044-008	18	SEE MAP	9%	179
EL-CFS-044-009	18	SEE MAP	9%	179
EL-CFS-044-010	18	SEE MAP	9%	179
EL-CFS-044-011	18	SEE MAP	9%	179
EL-CFS-044-012	18	SEE MAP	9%	179
EL-CFS-044-013	12	SEE MAP	8%	134
EL-CFS-044-014	12	SEE MAP	8%	134
EL-CFS-044-015	12	SEE MAP	8%	134
EL-CFS-044-016	12	SEE MAP	8%	134
EL-CFS-044-017	12	SEE MAP	8%	134
EL-CFS-044-018	12	SEE MAP	8%	134
EL-CFS-044-019	12	SEE MAP	8%	134
EL-CFS-044-020	12	SEE MAP	10%	149
EL-CFS-044-021	12	SEE MAP	10%	149
EL-CFS-044-022	12	SEE MAP	10%	149
EL-CFS-044-023	12	SEE MAP	10%	149
EL-CFS-044-024	12	SEE MAP	10%	149
EL-CFS-044-025	12	SEE MAP	10%	149
EL-CFS-044-026	12	SEE MAP	10%	149
EL-CFS-044-027	12	SEE MAP	10%	149
EL-CFS-044-028	12	SEE MAP	8%	36
EL-CFS-044-029	12	SEE MAP	8%	36
EL-CFS-044-030	18	SEE MAP	29%	58
EL-CFS-044-031	12	SEE MAP	14%	35

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-032	12	SEE MAP	14%	35
EL-CFS-044-033	12	SEE MAP	14%	35
EL-CFS-044-034	18	SEE MAP	10%	163
EL-CFS-044-035	18	SEE MAP	10%	163
EL-CFS-044-036	18	SEE MAP	10%	163
EL-CFS-044-037	24	SEE MAP	5%	465
EL-CFS-044-038	24	SEE MAP	5%	465
EL-CFS-044-039	24	SEE MAP	5%	465
EL-CFS-044-040	24	SEE MAP	5%	465
EL-CFS-044-041	24	SEE MAP	5%	465
EL-CFS-044-042	24	SEE MAP	5%	465
EL-CFS-044-043	24	SEE MAP	5%	465
EL-CFS-044-044	24	SEE MAP	5%	465
EL-CFS-044-045	12	SEE MAP	4%	344
EL-CFS-044-046	24	SEE MAP	5%	550
EL-CFS-044-047	24	SEE MAP	5%	550
EL-CFS-044-048	24	SEE MAP	6%	392
EL-CFS-044-049	18	SEE MAP	8%	250
EL-CFS-044-050	18	SEE MAP	6%	286
EL-CFS-044-051	18	SEE MAP	6%	286
EL-CFS-044-052	18	SEE MAP	6%	286
EL-CFS-044-053	18	SEE MAP	6%	286
EL-CFS-044-054	18	SEE MAP	6%	286
EL-CFS-044-055	12	SEE MAP	3%	348
EL-CFS-044-056	12	SEE MAP	3%	298
EL-CFS-044-057	12	SEE MAP	3%	298

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-058	12	SEE MAP	3%	298
EL-CFS-044-059	24	SEE MAP	15%	212
EL-CFS-044-060	24	SEE MAP	15%	212
EL-CFS-044-061	24	SEE MAP	15%	212
EL-CFS-044-062	24	SEE MAP	15%	212
EL-CFS-044-063	24	SEE MAP	15%	212
EL-CFS-044-064	24	SEE MAP	15%	212
EL-CFS-044-065	12	SEE MAP	13%	94
EL-CFS-044-066	12	SEE MAP	13%	94
EL-CFS-044-067	12	SEE MAP	13%	94
EL-CFS-044-068	12	SEE MAP	13%	94
EL-CFS-044-069	12	SEE MAP	13%	94
EL-CFS-044-070	12	SEE MAP	16%	81
EL-CFS-044-071	12	SEE MAP	16%	81
EL-CFS-044-072	12	SEE MAP	16%	81
EL-CFS-044-073	12	SEE MAP	16%	81
EL-CFS-044-074	12	SEE MAP	16%	81
EL-CFS-044-075	12	SEE MAP	16%	81
EL-CFS-044-076	12	SEE MAP	11%	100
EL-CFS-044-077	12	SEE MAP	11%	100
EL-CFS-044-078	12	SEE MAP	11%	100
EL-CFS-044-079	12	SEE MAP	11%	100
EL-CFS-044-080	12	SEE MAP	11%	100
EL-CFS-044-081	24	SEE MAP	7%	329
EL-CFS-044-082	24	SEE MAP	7%	329
EL-CFS-044-083	24	SEE MAP	7%	329

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-084	24	SEE MAP	7%	329
EL-CFS-044-085	18	SEE MAP	5%	321
EL-CFS-044-086	18	SEE MAP	5%	321
EL-CFS-044-087	18	SEE MAP	5%	321
EL-CFS-044-088	18	SEE MAP	5%	321
EL-CFS-044-089	12	SEE MAP	13%	82
EL-CFS-044-090	12	SEE MAP	13%	82
EL-CFS-044-091	12	SEE MAP	13%	82
EL-CFS-044-092	12	SEE MAP	13%	82
EL-CFS-044-093	12	SEE MAP	9%	145
EL-CFS-044-094	12	SEE MAP	9%	145
EL-CFS-044-095	12	SEE MAP	9%	145
EL-CFS-044-096	12	SEE MAP	9%	145
EL-CFS-044-097	12	SEE MAP	9%	145
EL-CFS-044-098	12	SEE MAP	9%	145
EL-CFS-044-099	12	SEE MAP	9%	145
EL-CFS-044-100	12	SEE MAP	9%	74
EL-CFS-044-101	12	SEE MAP	9%	74
EL-CFS-044-102	12	SEE MAP	10%	110
EL-CFS-044-103	12	SEE MAP	10%	110
EL-CFS-044-104	12	SEE MAP	10%	110
EL-CFS-044-105	12	SEE MAP	10%	110
EL-CFS-044-106	12	SEE MAP	8%	129
EL-CFS-044-107	12	SEE MAP	8%	129
EL-CFS-044-108	12	SEE MAP	8%	129
EL-CFS-044-109	12	SEE MAP	8%	129

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-110	12	SEE MAP	8%	129
EL-CFS-044-111	12	SEE MAP	8%	129
EL-CFS-044-112	12	SEE MAP	4%	146
EL-CFS-044-113	12	SEE MAP	4%	146
EL-CFS-044-114	12	SEE MAP	4%	146
EL-CFS-044-115	12	SEE MAP	6%	110
EL-CFS-044-116	12	SEE MAP	6%	110
EL-CFS-044-117	12	SEE MAP	6%	110
EL-CFS-044-118	24	SEE MAP	8%	406
EL-CFS-044-119	12	SEE MAP	3%	346
EL-CFS-044-120	12	SEE MAP	3%	346
EL-CFS-044-121	32	SEE MAP	15%	272
EL-CFS-044-122	32	SEE MAP	15%	272
EL-CFS-044-123	32	SEE MAP	15%	272
EL-CFS-044-124	24	SEE MAP	7%	367
EL-CFS-044-125	24	SEE MAP	7%	367
EL-CFS-044-126	24	SEE MAP	7%	367
EL-CFS-044-127	24	SEE MAP	7%	367
EL-CFS-044-128	24	SEE MAP	7%	367
EL-CFS-044-129	24	SEE MAP	7%	367
EL-CFS-044-130	24	SEE MAP	7%	367
EL-CFS-044-131	24	SEE MAP	7%	367
EL-CFS-044-132	18	SEE MAP	39%	51
EL-CFS-044-133	18	SEE MAP	39%	51
EL-CFS-044-134	18	SEE MAP	39%	51
EL-CFS-044-135	18	SEE MAP	39%	51

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-136	18	SEE MAP	39%	51
EL-CFS-044-137	18	SEE MAP	39%	51
EL-CFS-044-138	18	SEE MAP	39%	51
EL-CFS-044-139	18	SEE MAP	39%	51
EL-CFS-044-140	18	SEE MAP	39%	51
EL-CFS-044-141	18	SEE MAP	39%	51
EL-CFS-044-142	32	SEE MAP	50%	46
EL-CFS-044-143	32	SEE MAP	50%	46
EL-CFS-044-144	32	SEE MAP	50%	46
EL-CFS-044-145	32	SEE MAP	50%	46
EL-CFS-044-146	32	SEE MAP	50%	46
EL-CFS-044-147	32	SEE MAP	50%	46
EL-CFS-044-148	32	SEE MAP	50%	46
EL-CFS-044-149	32	SEE MAP	50%	46
EL-CFS-044-150	32	SEE MAP	50%	46
EL-CFS-044-151	32	SEE MAP	50%	46
EL-CFS-044-152	32	SEE MAP	52%	44
EL-CFS-044-153	32	SEE MAP	52%	44
EL-CFS-044-154	32	SEE MAP	52%	44
EL-CFS-044-155	32	SEE MAP	52%	44
EL-CFS-044-156	32	SEE MAP	52%	44
EL-CFS-044-157	32	SEE MAP	52%	44
EL-CFS-044-158	32	SEE MAP	52%	44
EL-CFS-044-159	32	SEE MAP	52%	44
EL-CFS-044-160	32	SEE MAP	52%	44
EL-CFS-044-161	32	SEE MAP	52%	44

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-162	32	SEE MAP	52%	44
EL-CFS-044-163	32	SEE MAP	52%	50
EL-CFS-044-164	32	SEE MAP	52%	50
EL-CFS-044-165	32	SEE MAP	52%	50
EL-CFS-044-166	32	SEE MAP	52%	50
EL-CFS-044-167	32	SEE MAP	52%	50
EL-CFS-044-168	32	SEE MAP	52%	50
EL-CFS-044-169	32	SEE MAP	52%	50
EL-CFS-044-170	32	SEE MAP	52%	50
EL-CFS-044-171	32	SEE MAP	52%	50
EL-CFS-044-172	32	SEE MAP	52%	50
EL-CFS-044-173	32	SEE MAP	52%	50
EL-CFS-044-174	32	SEE MAP	52%	50
EL-CFS-044-175	32	SEE MAP	48%	46
EL-CFS-044-176	32	SEE MAP	48%	46
EL-CFS-044-177	32	SEE MAP	48%	46
EL-CFS-044-178	32	SEE MAP	48%	46
EL-CFS-044-179	32	SEE MAP	48%	46
EL-CFS-044-180	32	SEE MAP	48%	46
EL-CFS-044-181	32	SEE MAP	48%	46
EL-CFS-044-182	32	SEE MAP	48%	46
EL-CFS-044-183	32	SEE MAP	48%	46
EL-CFS-044-184	32	SEE MAP	48%	46
EL-CFS-044-185	24	SEE MAP	46%	48
EL-CFS-044-186	24	SEE MAP	46%	48
EL-CFS-044-187	24	SEE MAP	46%	48

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-188	24	SEE MAP	46%	48
EL-CFS-044-189	24	SEE MAP	46%	48
EL-CFS-044-190	24	SEE MAP	46%	48
EL-CFS-044-191	24	SEE MAP	46%	48
EL-CFS-044-192	24	SEE MAP	46%	48
EL-CFS-044-193	24	SEE MAP	46%	48
EL-CFS-044-194	24	SEE MAP	46%	48
EL-CFS-044-195	18	SEE MAP	40%	50
EL-CFS-044-196	18	SEE MAP	40%	50
EL-CFS-044-197	18	SEE MAP	40%	50
EL-CFS-044-198	18	SEE MAP	40%	50
EL-CFS-044-199	18	SEE MAP	40%	50
EL-CFS-044-200	18	SEE MAP	40%	50
EL-CFS-044-201	18	SEE MAP	40%	50
EL-CFS-044-202	18	SEE MAP	40%	50
EL-CFS-044-203	18	SEE MAP	40%	50
EL-CFS-044-204	18	SEE MAP	40%	50
EL-CFS-044-205	18	SEE MAP	34%	50
EL-CFS-044-206	18	SEE MAP	34%	50
EL-CFS-044-207	18	SEE MAP	34%	50
EL-CFS-044-208	18	SEE MAP	34%	50
EL-CFS-044-209	18	SEE MAP	34%	50
EL-CFS-044-210	18	SEE MAP	34%	50
EL-CFS-044-211	18	SEE MAP	34%	50
EL-CFS-044-212	18	SEE MAP	34%	48
EL-CFS-044-213	12	SEE MAP	27%	48

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-214	12	SEE MAP	27%	48
EL-CFS-044-215	12	SEE MAP	27%	48
EL-CFS-044-216	12	SEE MAP	27%	48
EL-CFS-044-217	12	SEE MAP	27%	48
EL-CFS-044-218	12	SEE MAP	27%	48
EL-CFS-044-219	18	SEE MAP	20%	96
EL-CFS-044-220	18	SEE MAP	20%	96
EL-CFS-044-221	18	SEE MAP	20%	96
EL-CFS-044-222	18	SEE MAP	20%	96
EL-CFS-044-223	18	SEE MAP	20%	96
EL-CFS-044-224	18	SEE MAP	20%	96
EL-CFS-044-225	18	SEE MAP	20%	96
EL-CFS-044-226	18	SEE MAP	20%	96
EL-CFS-044-227	18	SEE MAP	20%	96
EL-CFS-044-228	18	SEE MAP	19%	101
EL-CFS-044-229	18	SEE MAP	19%	101
EL-CFS-044-230	18	SEE MAP	19%	101
EL-CFS-044-231	18	SEE MAP	19%	101
EL-CFS-044-232	18	SEE MAP	19%	101
EL-CFS-044-233	18	SEE MAP	19%	101
EL-CFS-044-234	18	SEE MAP	19%	101
EL-CFS-044-235	18	SEE MAP	19%	101
EL-CFS-044-236	18	SEE MAP	19%	101
EL-CFS-044-237	18	SEE MAP	19%	99
EL-CFS-044-238	18	SEE MAP	19%	99
EL-CFS-044-239	18	SEE MAP	19%	99

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-044-240	18	SEE MAP	19%	99
EL-CFS-044-241	18	SEE MAP	19%	99
EL-CFS-044-242	18	SEE MAP	19%	99
EL-CFS-044-243	18	SEE MAP	19%	99
EL-CFS-044-244	18	SEE MAP	19%	99
EL-CFS-044-245	18	SEE MAP	19%	99
EL-CFS-044-246	12	SEE MAP	9%	33
EL-CFS-044-247	12	SEE MAP	9%	33
EL-CFS-044-248	18	SEE MAP	16%	162
EL-CFS-045-001	12	SEE MAP	9%	74
EL-CFS-045-002	12	SEE MAP	9%	74
EL-CFS-045-003	12	SEE MAP	8%	145
EL-CFS-045-004	12	SEE MAP	8%	145
EL-CFS-045-005	12	SEE MAP	8%	145
EL-CFS-045-006	12	SEE MAP	8%	145
EL-CFS-045-007	12	SEE MAP	5%	192
EL-CFS-045-008	12	SEE MAP	5%	192
EL-CFS-045-009	12	SEE MAP	26%	35
EL-CFS-045-010	12	SEE MAP	26%	35
EL-CFS-045-011	12	SEE MAP	26%	35
EL-CFS-045-012	12	SEE MAP	23%	30
EL-CFS-045-013	12	SEE MAP	23%	30
EL-CFS-045-014	12	SEE MAP	23%	30
EL-CFS-045-015	12	SEE MAP	16%	63
EL-CFS-045-016	12	SEE MAP	16%	63
EL-CFS-045-017	12	SEE MAP	42%	12

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-045-018	12	SEE MAP	15%	59
EL-CFS-045-019	12	SEE MAP	3%	147
EL-CFS-045-020	12	SEE MAP	6%	139
EL-CFS-045-021	12	SEE MAP	6%	139
EL-CFS-045-022	12	SEE MAP	10%	89
EL-CFS-045-023	12	SEE MAP	10%	89
EL-CFS-045-024	18	SEE MAP	6%	257
EL-CFS-045-025	18	SEE MAP	6%	257
EL-CFS-045-026	18	SEE MAP	6%	257
EL-CFS-045-027	18	SEE MAP	6%	257
EL-CFS-045-028	12	SEE MAP	2%	124
EL-CFS-045-029	12	SEE MAP	4%	209
EL-CFS-045-030	12	SEE MAP	6%	32
EL-CFS-045-031	12	SEE MAP	6%	32
EL-CFS-045-032	12	SEE MAP	3%	284
EL-CFS-045-033	18	SEE MAP	16%	162
EL-CFS-045-034	18	SEE MAP	16%	162
EL-CFS-045-035	18	SEE MAP	16%	162
EL-CFS-045-036	18	SEE MAP	16%	162
EL-CFS-045-037	18	SEE MAP	16%	162
EL-CFS-045-038	18	SEE MAP	16%	162
EL-CFS-045-039	18	SEE MAP	16%	162
EL-CFS-045-040	18	SEE MAP	16%	162
EL-CFS-045-041	18	SEE MAP	16%	162
EL-CFS-045-042	18	SEE MAP	16%	162
EL-CFS-045-043	18	SEE MAP	16%	162

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-045-044	12	SEE MAP	19%	53
EL-CFS-045-045	12	SEE MAP	19%	53
EL-CFS-045-046	12	SEE MAP	19%	53
EL-CFS-045-047	12	SEE MAP	19%	53
EL-CFS-045-048	12	SEE MAP	19%	53
EL-CFS-045-049	12	SEE MAP	4%	211
EL-CFS-045-050	12	SEE MAP	4%	211
EL-CFS-045-051	12	SEE MAP	11%	135
EL-CFS-045-052	12	SEE MAP	11%	135
EL-CFS-045-053	12	SEE MAP	11%	135
EL-CFS-045-054	12	SEE MAP	11%	135
EL-CFS-045-055	12	SEE MAP	11%	135
EL-CFS-045-056	12	SEE MAP	11%	135
EL-CFS-045-057	12	SEE MAP	11%	135
EL-CFS-045-058	12	SEE MAP	11%	135
EL-CFS-045-059	12	SEE MAP	11%	142
EL-CFS-045-060	12	SEE MAP	11%	142
EL-CFS-045-061	12	SEE MAP	11%	142
EL-CFS-045-062	12	SEE MAP	11%	142
EL-CFS-045-063	12	SEE MAP	11%	142
EL-CFS-045-064	12	SEE MAP	11%	142
EL-CFS-045-065	12	SEE MAP	11%	142
EL-CFS-045-066	12	SEE MAP	11%	142
EL-CFS-045-067	12	SEE MAP	13%	107
EL-CFS-045-068	12	SEE MAP	13%	107
EL-CFS-045-069	12	SEE MAP	13%	107

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-045-070	12	SEE MAP	13%	107
EL-CFS-045-071	12	SEE MAP	13%	107
EL-CFS-045-072	12	SEE MAP	13%	107
EL-CFS-045-073	12	SEE MAP	10%	90
EL-CFS-045-074	12	SEE MAP	10%	90
EL-CFS-045-075	12	SEE MAP	10%	90
EL-CFS-045-076	12	SEE MAP	10%	90
EL-CFS-045-077	18	SEE MAP	11%	166
EL-CFS-045-078	18	SEE MAP	11%	166
EL-CFS-045-079	18	SEE MAP	11%	166
EL-CFS-045-080	18	SEE MAP	11%	166
EL-CFS-045-081	18	SEE MAP	11%	166
EL-CFS-045-082	18	SEE MAP	11%	166
EL-CFS-045-083	18	SEE MAP	11%	166
EL-CFS-045-084	18	SEE MAP	11%	166
EL-CFS-045-085	18	SEE MAP	11%	166
EL-CFS-045-086	18	SEE MAP	11%	166
EL-CFS-045-087	18	SEE MAP	11%	166
EL-CFS-045-088	12	SEE MAP	4%	135
EL-CFS-045-089	12	SEE MAP	4%	135
EL-CFS-045-090	12	SEE MAP	4%	135
EL-CFS-045-091	12	SEE MAP	4%	135
EL-CFS-045-092	24	SEE MAP	14%	253
EL-CFS-045-093	12	SEE MAP	Wetland	
EL-CFS-045-094	24	SEE MAP	12%	287
EL-CFS-045-095	18	SEE MAP	6%	260

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**

LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**


Monroe County, Pennsylvania

PREPARED BY: **JB**

DATE: **4/5/2021**

CHECKED BY: **KCC**

DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-045-096	18	SEE MAP	6%	260
EL-CFS-045-097	12	SEE MAP	5%	223
EL-CFS-045-098	12	SEE MAP	5%	192
EL-CFS-045-099	12	SEE MAP	5%	192
EL-CFS-045-100	12	SEE MAP	5%	192
EL-CFS-045-101	12	SEE MAP	5%	192
EL-CFS-045-102	12	SEE MAP	5%	192
EL-CFS-045-103	12	SEE MAP	5%	192
EL-CFS-045-104	12	SEE MAP	5%	192
EL-CFS-045-105	18	SEE MAP	21%	131
EL-CFS-045-106	18	SEE MAP	21%	131
EL-CFS-045-107	18	SEE MAP	21%	131
EL-CFS-045-108	18	SEE MAP	21%	131
EL-CFS-045-109	18	SEE MAP	21%	131
EL-CFS-045-110	18	SEE MAP	21%	131
EL-CFS-045-111	18	SEE MAP	21%	131
EL-CFS-045-112	18	SEE MAP	21%	131
EL-CFS-045-113	18	SEE MAP	21%	131
EL-CFS-045-114	18	SEE MAP	21%	131
EL-CFS-045-115	18	SEE MAP	21%	131
EL-CFS-045-116	18	SEE MAP	21%	131
EL-CFS-045-117	18	SEE MAP	21%	131
EL-CFS-045-118	12	SEE MAP	11%	141
EL-CFS-045-119	12	SEE MAP	11%	141
EL-CFS-045-120	12	SEE MAP	11%	141
EL-CFS-045-121	12	SEE MAP	11%	141

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-045-122	12	SEE MAP	11%	141
EL-CFS-045-123	12	SEE MAP	11%	141
EL-CFS-045-124	12	SEE MAP	11%	141
EL-CFS-045-125	12	SEE MAP	11%	141
EL-CFS-045-126	12	SEE MAP	6%	218
EL-CFS-045-127	12	SEE MAP	6%	218
EL-CFS-045-128	12	SEE MAP	6%	218
EL-CFS-045-129	12	SEE MAP	6%	218
EL-CFS-045-130	12	SEE MAP	6%	218
EL-CFS-045-131	12	SEE MAP	6%	218
EL-CFS-045-132	12	SEE MAP	6%	218
EL-CFS-045-133	12	SEE MAP	4%	155
EL-CFS-045-134	12	SEE MAP	4%	155
EL-CFS-045-135	12	SEE MAP	4%	155
EL-CFS-045-136	12	SEE MAP	4%	155
EL-CFS-045-137	12	SEE MAP	3%	36
EL-CFS-045-138	12	SEE MAP	3%	36
EL-CFS-045-139	12	SEE MAP	15%	73
EL-CFS-045-140	12	SEE MAP	15%	73
EL-CFS-045-141	12	SEE MAP	2%	154
EL-CFS-045-142	12	SEE MAP	2%	224
EL-CFS-045-143	12	SEE MAP	4%	307
EL-CFS-045-144	12	SEE MAP	4%	307
EL-CFS-045-145	12	SEE MAP	4%	206
EL-CFS-045-146	12	SEE MAP	3%	298
EL-CFS-045-147	12	SEE MAP	3%	298

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**

LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**


Monroe County, Pennsylvania

PREPARED BY: **JB**

DATE: **4/5/2021**

CHECKED BY: **KCC**

DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-045-148	12	SEE MAP	3%	146
EL-CFS-045-149	12	SEE MAP	3%	146
EL-CFS-045-150	12	SEE MAP	3%	146
EL-CFS-045-151	12	SEE MAP	10%	100
EL-CFS-045-152	12	SEE MAP	10%	100
EL-CFS-045-153	12	SEE MAP	10%	100
EL-CFS-045-154	12	SEE MAP	19%	48
EL-CFS-045-155	12	SEE MAP	19%	48
EL-CFS-045-156	12	SEE MAP	6%	213
EL-CFS-045-157	12	SEE MAP	6%	213
EL-CFS-045-158	12	SEE MAP	6%	213
EL-CFS-045-159	12	SEE MAP	6%	213
EL-CFS-045-160	18	SEE MAP	4%	403
EL-CFS-045-161	18	SEE MAP	4%	403
EL-CFS-045-162	18	SEE MAP	4%	403
EL-CFS-045-163	18	SEE MAP	4%	403
EL-CFS-045-164	18	SEE MAP	4%	403
EL-CFS-045-165	18	SEE MAP	4%	403
EL-CFS-045-166	18	SEE MAP	4%	403
EL-CFS-045-167	12	SEE MAP	Wetland	
EL-CFS-045-168	18	SEE MAP	4%	412
EL-CFS-045-169	18	SEE MAP	4%	412
EL-CFS-045-170	18	SEE MAP	4%	412
EL-CFS-045-171	18	SEE MAP	4%	412
EL-CFS-045-172	18	SEE MAP	4%	412
EL-CFS-045-173	12	SEE MAP	1%	106

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-046-001	12	SEE MAP	3%	284
EL-CFS-046-002	12	SEE MAP	3%	284
EL-CFS-046-003	12	SEE MAP	3%	284
EL-CFS-046-004	12	SEE MAP	3%	284
EL-CFS-046-005	12	SEE MAP	3%	284
EL-CFS-046-006	12	SEE MAP	3%	284
EL-CFS-046-007	12	SEE MAP	6%	18
EL-CFS-046-008	12	SEE MAP	9%	87
EL-CFS-046-009	12	SEE MAP	9%	87
EL-CFS-046-010	18	SEE MAP	13%	136
EL-CFS-046-011	18	SEE MAP	13%	136
EL-CFS-046-012	12	SEE MAP	Wetland	
EL-CFS-046-013	18	SEE MAP	15%	123
EL-CFS-046-014	18	SEE MAP	15%	123
EL-CFS-046-015	12	SEE MAP	3%	335
EL-CFS-046-016	12	SEE MAP	3%	335
EL-CFS-046-017	12	SEE MAP	3%	335
EL-CFS-046-018	12	SEE MAP	3%	92
EL-CFS-046-019	18	SEE MAP	7%	260
EL-CFS-046-020	18	SEE MAP	7%	260
EL-CFS-046-021	18	SEE MAP	7%	260
EL-CFS-046-022	18	SEE MAP	7%	260
EL-CFS-046-023	12	SEE MAP	4%	420
EL-CFS-046-024	12	SEE MAP	4%	420
EL-CFS-046-025	12	SEE MAP	4%	420
EL-CFS-046-026	12	SEE MAP	4%	420

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-046-027	12	SEE MAP	4%	420
EL-CFS-046-028	12	SEE MAP	3%	234
EL-CFS-046-029	12	SEE MAP	3%	234
EL-CFS-046-030	12	SEE MAP	3%	234
EL-CFS-046-031	12	SEE MAP	3%	234
EL-CFS-046-032	12	SEE MAP	5%	64
EL-CFS-046-033	12	SEE MAP	5%	64
EL-CFS-046-034	12	SEE MAP	5%	64
EL-CFS-046-035	12	SEE MAP	Wetland	
EL-CFS-046-036	12	SEE MAP	4%	136
EL-CFS-046-037	12	SEE MAP	4%	136
EL-CFS-046-038	12	SEE MAP	4%	136
EL-CFS-046-039	12	SEE MAP	4%	136
EL-CFS-046-040	12	SEE MAP	8%	13
EL-CFS-046-041	12	SEE MAP	5%	85
EL-CFS-046-042	12	SEE MAP	5%	85
EL-CFS-046-043	12	SEE MAP	5%	85
EL-CFS-046-044	12	SEE MAP	29%	17
EL-CFS-046-045	12	SEE MAP	29%	17
EL-CFS-046-046	12	SEE MAP	29%	17
EL-CFS-046-047	12	SEE MAP	5%	176
EL-CFS-046-048	12	SEE MAP	5%	176
EL-CFS-046-049	12	SEE MAP	5%	176
EL-CFS-046-050	24	SEE MAP	5%	386
EL-CFS-046-051	24	SEE MAP	5%	386
EL-CFS-046-052	24	SEE MAP	5%	386

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-046-053	24	SEE MAP	5%	386
EL-CFS-046-054	24	SEE MAP	5%	386
EL-CFS-046-055	12	SEE MAP	4%	112
EL-CFS-046-056	12	SEE MAP	4%	112
EL-CFS-046-057	12	SEE MAP	9%	167
EL-CFS-046-058	12	SEE MAP	7%	112
EL-CFS-046-059	18	SEE MAP	17%	137
EL-CFS-046-060	18	SEE MAP	17%	137
EL-CFS-046-061	18	SEE MAP	17%	137
EL-CFS-046-062	18	SEE MAP	17%	137
EL-CFS-046-063	18	SEE MAP	17%	137
EL-CFS-046-064	18	SEE MAP	17%	137
EL-CFS-046-065	18	SEE MAP	17%	137
EL-CFS-046-066	18	SEE MAP	17%	137
EL-CFS-046-067	18	SEE MAP	17%	137
EL-CFS-046-068	18	SEE MAP	17%	137
EL-CFS-046-069	18	SEE MAP	17%	137
EL-CFS-046-070	18	SEE MAP	17%	137
EL-CFS-046-071	12	SEE MAP	9%	150
EL-CFS-046-072	12	SEE MAP	9%	150
EL-CFS-046-073	12	SEE MAP	9%	150
EL-CFS-046-074	12	SEE MAP	9%	150
EL-CFS-046-075	12	SEE MAP	9%	150
EL-CFS-046-076	12	SEE MAP	9%	150
EL-CFS-046-077	12	SEE MAP	9%	150
EL-CFS-046-078	24	SEE MAP	4%	74

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-046-079	24	SEE MAP	4%	74
EL-CFS-046-080	24	SEE MAP	4%	74
EL-CFS-046-081	12	SEE MAP	11%	127
EL-CFS-046-082	12	SEE MAP	11%	127
EL-CFS-046-083	12	SEE MAP	11%	127
EL-CFS-046-084	12	SEE MAP	11%	127
EL-CFS-046-085	12	SEE MAP	11%	127
EL-CFS-046-086	12	SEE MAP	11%	127
EL-CFS-046-087	12	SEE MAP	11%	127
EL-CFS-046-088	18	SEE MAP	7%	251
EL-CFS-046-089	18	SEE MAP	7%	251
EL-CFS-046-090	18	SEE MAP	7%	251
EL-CFS-046-091	18	SEE MAP	7%	251
EL-CFS-046-092	12	SEE MAP	6%	239
EL-CFS-046-093	12	SEE MAP	6%	239
EL-CFS-046-094	12	SEE MAP	6%	239
EL-CFS-046-095	12	SEE MAP	6%	239
EL-CFS-046-096	12	SEE MAP	6%	239
EL-CFS-046-097	18	SEE MAP	15%	124
EL-CFS-046-098	18	SEE MAP	15%	124
EL-CFS-046-099	18	SEE MAP	15%	124
EL-CFS-046-100	18	SEE MAP	15%	124
EL-CFS-046-101	18	SEE MAP	15%	124
EL-CFS-046-102	18	SEE MAP	15%	124
EL-CFS-046-103	18	SEE MAP	15%	124
EL-CFS-046-104	18	SEE MAP	15%	124

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-046-105	18	SEE MAP	15%	124
EL-CFS-046-106	12	SEE MAP	33%	27
EL-CFS-046-107	18	SEE MAP	19%	135
EL-CFS-046-108	18	SEE MAP	19%	135
EL-CFS-046-109	18	SEE MAP	8%	239
EL-CFS-046-110	18	SEE MAP	8%	239
EL-CFS-046-111	18	SEE MAP	8%	239
EL-CFS-046-112	18	SEE MAP	8%	239
EL-CFS-046-113	12	SEE MAP	11%	136
EL-CFS-046-114	12	SEE MAP	11%	136
EL-CFS-046-115	12	SEE MAP		Wetland
EL-CFS-046-116	18	SEE MAP	21%	104
EL-CFS-046-117	18	SEE MAP	21%	104
EL-CFS-046-118	18	SEE MAP	21%	104
EL-CFS-046-119	18	SEE MAP	20%	87
EL-CFS-046-120	18	SEE MAP	20%	87
EL-CFS-046-121	18	SEE MAP	20%	87
EL-CFS-046-122	18	SEE MAP	20%	87
EL-CFS-046-123	18	SEE MAP	24%	89
EL-CFS-046-124	18	SEE MAP	24%	89
EL-CFS-046-125	18	SEE MAP	24%	89
EL-CFS-046-126	18	SEE MAP	24%	89
EL-CFS-046-127	18	SEE MAP	24%	89
EL-CFS-046-128	18	SEE MAP	24%	89
EL-CFS-046-129	18	SEE MAP	24%	89
EL-CFS-046-130	18	SEE MAP	24%	89

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-046-131	18	SEE MAP	24%	89
EL-CFS-046-132	18	SEE MAP	24%	89
EL-CFS-046-133	12	SEE MAP	8%	104
EL-CFS-046-134	12	SEE MAP	8%	104
EL-CFS-046-135	12	SEE MAP	8%	104
EL-CFS-046-136	12	SEE MAP	5%	81
EL-CFS-046-137	12	SEE MAP	5%	74
EL-CFS-046-138	12	SEE MAP	6%	52
EL-CFS-046-139	12	SEE MAP	6%	52
EL-CFS-046-140	12	SEE MAP	Wetland	
EL-CFS-046-141	12	SEE MAP	4%	157
EL-CFS-046-142	12	SEE MAP	4%	157
EL-CFS-046-143	12	SEE MAP	4%	157
EL-CFS-046-144	12	SEE MAP	4%	157
EL-CFS-046-145	12	SEE MAP	7%	96
EL-CFS-046-146	12	SEE MAP	7%	96
EL-CFS-046-147	12	SEE MAP	3%	262
EL-CFS-046-148	12	SEE MAP	3%	262
EL-CFS-046-149	12	SEE MAP	3%	262
EL-CFS-046-150	12	SEE MAP	3%	88
EL-CFS-046-151	12	SEE MAP	3%	88
EL-CFS-046-152	12	SEE MAP	3%	88
EL-CFS-046-153	12	SEE MAP	5%	288
EL-CFS-046-154	12	SEE MAP	5%	288
EL-CFS-046-155	12	SEE MAP	5%	253
EL-CFS-046-156	12	SEE MAP	5%	253

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-046-157	12	SEE MAP	5%	253
EL-CFS-046-158	24	SEE MAP	17%	18
EL-CFS-046-159	24	SEE MAP	17%	18
EL-CFS-046-160	24	SEE MAP	17%	18
EL-CFS-046-161	12	SEE MAP	7%	89
EL-CFS-046-162	12	SEE MAP	7%	89
EL-CFS-046-163	12	SEE MAP	7%	89
EL-CFS-046-164	12	SEE MAP	14%	43
EL-CFS-046-165	12	SEE MAP	14%	43
EL-CFS-046-166	12	SEE MAP	14%	43
EL-CFS-046-167	12	SEE MAP	14%	43
EL-CFS-046-168	12	SEE MAP	19%	52
EL-CFS-046-169	12	SEE MAP	19%	52
EL-CFS-046-170	18	SEE MAP	21%	96
EL-CFS-046-171	18	SEE MAP	21%	96
EL-CFS-046-172	18	SEE MAP	21%	96
EL-CFS-046-173	18	SEE MAP	21%	96
EL-CFS-046-174	18	SEE MAP	21%	96
EL-CFS-046-175	18	SEE MAP	21%	96
EL-CFS-046-176	12	SEE MAP	9%	99
EL-CFS-046-177	12	SEE MAP	9%	99
EL-CFS-046-178	12	SEE MAP	9%	99
EL-CFS-047-001	12	SEE MAP	9%	85
EL-CFS-047-002	12	SEE MAP	6%	94
EL-CFS-047-003	12	SEE MAP	6%	94
EL-CFS-047-004	12	SEE MAP	6%	94

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-005	12	SEE MAP	6%	94
EL-CFS-047-006	12	SEE MAP	6%	94
EL-CFS-047-007	18	SEE MAP	16%	104
EL-CFS-047-008	18	SEE MAP	16%	104
EL-CFS-047-009	18	SEE MAP	16%	104
EL-CFS-047-010	18	SEE MAP	16%	104
EL-CFS-047-011	18	SEE MAP	16%	104
EL-CFS-047-012	18	SEE MAP	16%	104
EL-CFS-047-013	18	SEE MAP	16%	104
EL-CFS-047-014	18	SEE MAP	16%	104
EL-CFS-047-015	18	SEE MAP	21%	92
EL-CFS-047-016	18	SEE MAP	21%	92
EL-CFS-047-017	18	SEE MAP	21%	92
EL-CFS-047-018	12	SEE MAP	25%	24
EL-CFS-047-019	12	SEE MAP	25%	24
EL-CFS-047-020	12	SEE MAP	25%	24
EL-CFS-047-021	18	SEE MAP	39%	49
EL-CFS-047-022	18	SEE MAP	39%	49
EL-CFS-047-023	18	SEE MAP	39%	49
EL-CFS-047-024	18	SEE MAP	39%	49
EL-CFS-047-025	18	SEE MAP	39%	49
EL-CFS-047-026	18	SEE MAP	39%	49
EL-CFS-047-027	18	SEE MAP	39%	49
EL-CFS-047-028	18	SEE MAP	39%	49
EL-CFS-047-029	18	SEE MAP	39%	49
EL-CFS-047-030	18	SEE MAP	27%	81

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-031	18	SEE MAP	27%	81
EL-CFS-047-032	18	SEE MAP	27%	81
EL-CFS-047-033	18	SEE MAP	27%	81
EL-CFS-047-034	18	SEE MAP	27%	81
EL-CFS-047-035	12	SEE MAP	23%	48
EL-CFS-047-036	12	SEE MAP	23%	48
EL-CFS-047-037	12	SEE MAP	23%	48
EL-CFS-047-038	12	SEE MAP	23%	48
EL-CFS-047-039	12	SEE MAP	23%	48
EL-CFS-047-040	18	SEE MAP	15%	170
EL-CFS-047-041	18	SEE MAP	15%	170
EL-CFS-047-042	18	SEE MAP	15%	170
EL-CFS-047-043	18	SEE MAP	15%	170
EL-CFS-047-044	18	SEE MAP	15%	170
EL-CFS-047-045	18	SEE MAP	15%	170
EL-CFS-047-046	18	SEE MAP	15%	170
EL-CFS-047-047	12	SEE MAP	14%	22
EL-CFS-047-048	12	SEE MAP	11%	71
EL-CFS-047-049	12	SEE MAP	11%	71
EL-CFS-047-050	12	SEE MAP	11%	71
EL-CFS-047-051	12	SEE MAP	11%	71
EL-CFS-047-052	12	SEE MAP	14%	28
EL-CFS-047-053	12	SEE MAP	8%	142
EL-CFS-047-054	12	SEE MAP	9%	155
EL-CFS-047-055	12	SEE MAP	9%	155
EL-CFS-047-056	12	SEE MAP	8%	78

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-057	12	SEE MAP	8%	78
EL-CFS-047-058	12	SEE MAP	8%	78
EL-CFS-047-059	12	SEE MAP	10%	60
EL-CFS-047-060	12	SEE MAP	10%	60
EL-CFS-047-061	12	SEE MAP	10%	60
EL-CFS-047-062	18	SEE MAP	6%	237
EL-CFS-047-063	18	SEE MAP	6%	237
EL-CFS-047-064	18	SEE MAP	6%	237
EL-CFS-047-065	18	SEE MAP	6%	237
EL-CFS-047-066	18	SEE MAP	6%	237
EL-CFS-047-067	18	SEE MAP	6%	237
EL-CFS-047-068	18	SEE MAP	6%	237
EL-CFS-047-069	12	SEE MAP	7%	172
EL-CFS-047-070	12	SEE MAP	12%	76
EL-CFS-047-071	12	SEE MAP	11%	44
EL-CFS-047-072	32	SEE MAP	12%	340
EL-CFS-047-073	32	SEE MAP	12%	340
EL-CFS-047-074	32	SEE MAP	12%	340
EL-CFS-047-075	32	SEE MAP	12%	340
EL-CFS-047-076	32	SEE MAP	12%	340
EL-CFS-047-077	18	SEE MAP	17%	150
EL-CFS-047-078	24	SEE MAP	58%	38
EL-CFS-047-079	24	SEE MAP	58%	38
EL-CFS-047-080	24	SEE MAP	58%	38
EL-CFS-047-081	24	SEE MAP	58%	38
EL-CFS-047-082	24	SEE MAP	58%	38

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-083	24	SEE MAP	58%	38
EL-CFS-047-084	32	SEE MAP	60%	47
EL-CFS-047-085	32	SEE MAP	60%	47
EL-CFS-047-086	32	SEE MAP	60%	47
EL-CFS-047-087	12	SEE MAP	10%	100
EL-CFS-047-088	12	SEE MAP	10%	100
EL-CFS-047-089	12	SEE MAP	10%	100
EL-CFS-047-090	12	SEE MAP	10%	100
EL-CFS-047-091	12	SEE MAP	10%	100
EL-CFS-047-092	18	SEE MAP	19%	81
EL-CFS-047-093	18	SEE MAP	19%	81
EL-CFS-047-094	18	SEE MAP	19%	81
EL-CFS-047-095	18	SEE MAP	19%	81
EL-CFS-047-096	18	SEE MAP	19%	81
EL-CFS-047-097	18	SEE MAP	19%	81
EL-CFS-047-098	18	SEE MAP	19%	81
EL-CFS-047-099	18	SEE MAP	28%	68
EL-CFS-047-100	18	SEE MAP	28%	68
EL-CFS-047-101	18	SEE MAP	28%	68
EL-CFS-047-102	18	SEE MAP	28%	68
EL-CFS-047-103	18	SEE MAP	28%	68
EL-CFS-047-104	18	SEE MAP	28%	68
EL-CFS-047-105	18	SEE MAP	28%	68
EL-CFS-047-106	18	SEE MAP	28%	68
EL-CFS-047-107	18	SEE MAP	28%	68
EL-CFS-047-108	18	SEE MAP	28%	68

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-109	12	SEE MAP	5%	140
EL-CFS-047-110	12	SEE MAP	5%	140
EL-CFS-047-111	12	SEE MAP	5%	140
EL-CFS-047-112	12	SEE MAP	16%	32
EL-CFS-047-113	12	SEE MAP	11%	45
EL-CFS-047-114	12	SEE MAP	11%	45
EL-CFS-047-115	12	SEE MAP	11%	45
EL-CFS-047-116	12	SEE MAP	11%	45
EL-CFS-047-117	12	SEE MAP	11%	45
EL-CFS-047-118	12	SEE MAP	11%	45
EL-CFS-047-119	32	SEE MAP	5%	576
EL-CFS-047-120	32	SEE MAP	5%	576
EL-CFS-047-121	32	SEE MAP	5%	576
EL-CFS-047-122	32	SEE MAP	5%	576
EL-CFS-047-123	32	SEE MAP	7%	513
EL-CFS-047-124	12	SEE MAP	9%	99
EL-CFS-047-125	12	SEE MAP	9%	99
EL-CFS-047-126	12	SEE MAP	11%	47
EL-CFS-047-127	12	SEE MAP	11%	47
EL-CFS-047-128	12	SEE MAP	11%	47
EL-CFS-047-129	12	SEE MAP	2%	146
EL-CFS-047-130	12	SEE MAP	2%	146
EL-CFS-047-131	12	SEE MAP	4%	227
EL-CFS-047-132	12	SEE MAP	4%	227
EL-CFS-047-133	12	SEE MAP	4%	227
EL-CFS-047-134	12	SEE MAP	4%	227

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-135	12	SEE MAP	6%	88
EL-CFS-047-136	12	SEE MAP	6%	88
EL-CFS-047-137	12	SEE MAP	6%	88
EL-CFS-047-138	12	SEE MAP	11%	44
EL-CFS-047-139	12	SEE MAP	11%	44
EL-CFS-047-140	12	SEE MAP	14%	107
EL-CFS-047-141	12	SEE MAP	14%	107
EL-CFS-047-142	12	SEE MAP	14%	107
EL-CFS-047-143	12	SEE MAP	14%	107
EL-CFS-047-144	12	SEE MAP	14%	107
EL-CFS-047-145	12	SEE MAP	14%	107
EL-CFS-047-146	12	SEE MAP	14%	107
EL-CFS-047-147	18	SEE MAP	14%	153
EL-CFS-047-148	18	SEE MAP	14%	153
EL-CFS-047-149	18	SEE MAP	14%	153
EL-CFS-047-150	18	SEE MAP	14%	153
EL-CFS-047-151	18	SEE MAP	14%	153
EL-CFS-047-152	18	SEE MAP	14%	153
EL-CFS-047-153	18	SEE MAP	14%	153
EL-CFS-047-154	18	SEE MAP	14%	153
EL-CFS-047-155	18	SEE MAP	14%	153
EL-CFS-047-156	12	SEE MAP	10%	39
EL-CFS-047-157	12	SEE MAP	10%	39
EL-CFS-047-158	12	SEE MAP	10%	39
EL-CFS-047-159	12	SEE MAP	11%	142
EL-CFS-047-160	12	SEE MAP	11%	142

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-161	18	SEE MAP	13%	142
EL-CFS-047-162	24	SEE MAP	14%	253
EL-CFS-047-163	24	SEE MAP	14%	253
EL-CFS-047-164	24	SEE MAP	14%	253
EL-CFS-047-165	24	SEE MAP	14%	253
EL-CFS-047-166	24	SEE MAP	14%	253
EL-CFS-047-167	24	SEE MAP	14%	253
EL-CFS-047-168	24	SEE MAP	14%	253
EL-CFS-047-169	24	SEE MAP	14%	253
EL-CFS-047-170	18	SEE MAP	15%	157
EL-CFS-047-171	18	SEE MAP	15%	157
EL-CFS-047-172	18	SEE MAP	15%	157
EL-CFS-047-173	18	SEE MAP	15%	157
EL-CFS-047-174	18	SEE MAP	15%	157
EL-CFS-047-175	18	SEE MAP	17%	149
EL-CFS-047-176	18	SEE MAP	17%	149
EL-CFS-047-177	18	SEE MAP	17%	149
EL-CFS-047-178	18	SEE MAP	13%	196
EL-CFS-047-179	18	SEE MAP	13%	196
EL-CFS-047-180	18	SEE MAP	13%	196
EL-CFS-047-181	18	SEE MAP	13%	196
EL-CFS-047-182	18	SEE MAP	13%	196
EL-CFS-047-183	12	SEE MAP	28%	39
EL-CFS-047-184	12	SEE MAP	28%	39
EL-CFS-047-185	12	SEE MAP	28%	39
EL-CFS-047-186	12	SEE MAP	28%	39

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**

LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**


Monroe County, Pennsylvania

PREPARED BY: **JB**

DATE: **4/5/2021**

CHECKED BY: **KCC**

DATE: **4/5/2021**




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-187	12	SEE MAP	28%	39
EL-CFS-047-188	12	SEE MAP	21%	39
EL-CFS-047-189	12	SEE MAP	21%	39
EL-CFS-047-190	12	SEE MAP	21%	39
EL-CFS-047-191	12	SEE MAP	21%	39
EL-CFS-047-192	18	SEE MAP	22%	120
EL-CFS-047-193	18	SEE MAP	22%	120
EL-CFS-047-194	18	SEE MAP	22%	120
EL-CFS-047-195	18	SEE MAP	22%	120
EL-CFS-047-196	18	SEE MAP	22%	120
EL-CFS-047-197	18	SEE MAP	22%	120
EL-CFS-047-198	18	SEE MAP	22%	120
EL-CFS-047-199	18	SEE MAP	22%	120
EL-CFS-047-200	18	SEE MAP	22%	120
EL-CFS-047-201	18	SEE MAP	22%	120
EL-CFS-047-202	18	SEE MAP	22%	120
EL-CFS-047-203	18	SEE MAP	38%	40
EL-CFS-047-204	18	SEE MAP	38%	40
EL-CFS-047-205	18	SEE MAP	38%	40
EL-CFS-047-206	18	SEE MAP	38%	40
EL-CFS-047-207	18	SEE MAP	38%	40
EL-CFS-047-208	18	SEE MAP	38%	40
EL-CFS-047-209	18	SEE MAP	38%	40
EL-CFS-047-210	12	SEE MAP	37%	30
EL-CFS-047-211	12	SEE MAP	37%	30
EL-CFS-047-212	12	SEE MAP	37%	30

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-213	12	SEE MAP	37%	30
EL-CFS-047-214	12	SEE MAP	37%	30
EL-CFS-047-215	24	SEE MAP	40%	53
EL-CFS-047-216	24	SEE MAP	40%	53
EL-CFS-047-217	24	SEE MAP	40%	53
EL-CFS-047-218	24	SEE MAP	40%	53
EL-CFS-047-219	24	SEE MAP	40%	53
EL-CFS-047-220	24	SEE MAP	40%	53
EL-CFS-047-221	24	SEE MAP	40%	53
EL-CFS-047-222	24	SEE MAP	40%	53
EL-CFS-047-223	24	SEE MAP	40%	53
EL-CFS-047-224	24	SEE MAP	40%	53
EL-CFS-047-225	32	SEE MAP	46%	57
EL-CFS-047-226	32	SEE MAP	46%	57
EL-CFS-047-227	32	SEE MAP	46%	57
EL-CFS-047-228	32	SEE MAP	46%	57
EL-CFS-047-229	32	SEE MAP	46%	57
EL-CFS-047-230	32	SEE MAP	46%	57
EL-CFS-047-231	32	SEE MAP	46%	57
EL-CFS-047-232	32	SEE MAP	46%	57
EL-CFS-047-233	32	SEE MAP	46%	57
EL-CFS-047-234	32	SEE MAP	46%	57
EL-CFS-047-235	32	SEE MAP	46%	57
EL-CFS-047-236	32	SEE MAP	46%	57
EL-CFS-047-237	12	SEE MAP	44%	25
EL-CFS-047-238	12	SEE MAP	44%	25

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-239	12	SEE MAP	44%	25
EL-CFS-047-240	12	SEE MAP	44%	25
EL-CFS-047-241	12	SEE MAP	44%	25
EL-CFS-047-242	24	SEE MAP	44%	52
EL-CFS-047-243	24	SEE MAP	44%	52
EL-CFS-047-244	24	SEE MAP	44%	52
EL-CFS-047-245	24	SEE MAP	44%	52
EL-CFS-047-246	24	SEE MAP	44%	52
EL-CFS-047-247	24	SEE MAP	44%	52
EL-CFS-047-248	24	SEE MAP	44%	52
EL-CFS-047-249	24	SEE MAP	44%	52
EL-CFS-047-250	24	SEE MAP	44%	52
EL-CFS-047-251	24	SEE MAP	44%	52
EL-CFS-047-252	24	SEE MAP	44%	52
EL-CFS-047-253	24	SEE MAP	50%	36
EL-CFS-047-254	24	SEE MAP	50%	36
EL-CFS-047-255	24	SEE MAP	50%	36
EL-CFS-047-256	24	SEE MAP	50%	36
EL-CFS-047-257	24	SEE MAP	50%	36
EL-CFS-047-258	24	SEE MAP	50%	36
EL-CFS-047-259	24	SEE MAP	50%	36
EL-CFS-047-260	24	SEE MAP	50%	36
EL-CFS-047-261	24	SEE MAP	50%	36
EL-CFS-047-262	18	SEE MAP	44%	32
EL-CFS-047-263	18	SEE MAP	44%	32
EL-CFS-047-264	18	SEE MAP	44%	32

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-047-265	18	SEE MAP	44%	32
EL-CFS-047-266	18	SEE MAP	44%	32
EL-CFS-047-267	18	SEE MAP	44%	32
EL-CFS-047-268	18	SEE MAP	44%	32
EL-CFS-047-269	18	SEE MAP	29%	55
EL-CFS-047-270	18	SEE MAP	29%	55
EL-CFS-047-271	18	SEE MAP	29%	55
EL-CFS-047-272	18	SEE MAP	29%	55
EL-CFS-047-273	18	SEE MAP	29%	55
EL-CFS-047-274	18	SEE MAP	29%	55
EL-CFS-047-275	18	SEE MAP	29%	55
EL-CFS-047-276	12	SEE MAP	3%	105
EL-CFS-047-277	12	SEE MAP	3%	105
EL-CFS-047-278	32	SEE MAP	6%	560
EL-CFS-047-279	32	SEE MAP	6%	560
EL-CFS-047-280	32	SEE MAP	6%	560
EL-CFS-047-281	32	SEE MAP	6%	560
EL-CFS-047-282	32	SEE MAP	7%	513
EL-CFS-047-283	32	SEE MAP	7%	513
EL-CFS-047-284	32	SEE MAP	7%	513
EL-CFS-047-285	12	SEE MAP	4%	90
EL-CFS-048-001	12	SEE MAP	5%	98
EL-CFS-048-002	12	SEE MAP	5%	98
EL-CFS-048-003	12	SEE MAP	5%	98
EL-CFS-048-004	12	SEE MAP	8%	40
EL-CFS-048-005	12	SEE MAP	8%	40

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-048-006	12	SEE MAP	4%	269
EL-CFS-048-007	12	SEE MAP	4%	269
EL-CFS-048-008	12	SEE MAP	1%	137
EL-CFS-048-009	12	SEE MAP	1%	137
EL-CFS-048-010	12	SEE MAP	2%	279
EL-CFS-048-011	12	SEE MAP	2%	279
EL-CFS-048-012	12	SEE MAP	3%	308
EL-CFS-048-013	18	SEE MAP	9%	248
EL-CFS-048-014	18	SEE MAP	9%	248
EL-CFS-048-015	12	SEE MAP	8%	146
EL-CFS-048-016	12	SEE MAP	8%	146
EL-CFS-048-017	12	SEE MAP	8%	146
EL-CFS-048-018	12	SEE MAP	9%	119
EL-CFS-048-019	12	SEE MAP	9%	119
EL-CFS-048-020	12	SEE MAP	9%	119
EL-CFS-048-021	12	SEE MAP	9%	119
EL-CFS-048-022	12	SEE MAP	9%	119
EL-CFS-048-023	12	SEE MAP	9%	119
EL-CFS-048-024	18	SEE MAP	14%	197
EL-CFS-048-025	18	SEE MAP	14%	197
EL-CFS-048-026	18	SEE MAP	14%	197
EL-CFS-048-027	18	SEE MAP	14%	197
EL-CFS-048-028	18	SEE MAP	14%	197
EL-CFS-048-029	18	SEE MAP	14%	197
EL-CFS-048-030	18	SEE MAP	14%	197
EL-CFS-048-031	18	SEE MAP	14%	197

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**

LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**


Monroe County, Pennsylvania

PREPARED BY: **JB**

DATE: **4/5/2021**

CHECKED BY: **KCC**

DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-048-032	18	SEE MAP	14%	197
EL-CFS-048-033	18	SEE MAP	14%	197
EL-CFS-048-034	12	SEE MAP	18%	67
EL-CFS-048-035	12	SEE MAP	18%	67
EL-CFS-048-036	12	SEE MAP	18%	67
EL-CFS-048-037	12	SEE MAP	18%	67
EL-CFS-048-038	12	SEE MAP	18%	67
EL-CFS-048-039	12	SEE MAP	18%	67
EL-CFS-048-040	12	SEE MAP	18%	67
EL-CFS-048-041	24	SEE MAP	8%	310
EL-CFS-048-042	24	SEE MAP	8%	310
EL-CFS-048-043	12	SEE MAP	6%	142
EL-CFS-048-044	12	SEE MAP	6%	142
EL-CFS-048-045	12	SEE MAP	6%	142
EL-CFS-048-046	12	SEE MAP	6%	142
EL-CFS-048-047	12	SEE MAP	6%	142
EL-CFS-048-048	12	SEE MAP	8%	122
EL-CFS-048-049	12	SEE MAP	8%	122
EL-CFS-048-050	12	SEE MAP	8%	122
EL-CFS-048-051	12	SEE MAP	8%	122
EL-CFS-048-052	12	SEE MAP	8%	83
EL-CFS-048-053	12	SEE MAP	8%	83
EL-CFS-048-054	12	SEE MAP	8%	83
EL-CFS-048-055	12	SEE MAP	4%	117
EL-CFS-048-056	12	SEE MAP	4%	117
EL-CFS-048-057	12	SEE MAP	4%	117

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-048-058	12	SEE MAP	7%	126
EL-CFS-048-059	12	SEE MAP	7%	126
EL-CFS-048-060	12	SEE MAP	7%	126
EL-CFS-048-061	12	SEE MAP	7%	126
EL-CFS-048-062	12	SEE MAP	7%	126
EL-CFS-048-063	12	SEE MAP	8%	154
EL-CFS-048-064	12	SEE MAP	8%	154
EL-CFS-048-065	12	SEE MAP	8%	154
EL-CFS-048-066	12	SEE MAP	8%	154
EL-CFS-048-067	12	SEE MAP	8%	154
EL-CFS-048-068	12	SEE MAP	8%	154
EL-CFS-048-069	12	SEE MAP	9%	144
EL-CFS-048-070	12	SEE MAP	9%	144
EL-CFS-048-071	12	SEE MAP	9%	144
EL-CFS-048-072	12	SEE MAP	9%	144
EL-CFS-048-073	12	SEE MAP	9%	144
EL-CFS-048-074	12	SEE MAP	9%	144
EL-CFS-048-075	12	SEE MAP	9%	144
EL-CFS-048-076	12	SEE MAP	8%	133
EL-CFS-048-077	12	SEE MAP	8%	133
EL-CFS-048-078	12	SEE MAP	8%	133
EL-CFS-048-079	12	SEE MAP	8%	133
EL-CFS-048-080	12	SEE MAP	8%	133
EL-CFS-048-081	18	SEE MAP	5%	403
EL-CFS-048-082	18	SEE MAP	5%	403
EL-CFS-048-083	18	SEE MAP	5%	403

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-048-084	18	SEE MAP	5%	403
EL-CFS-048-085	12	SEE MAP	5%	340
EL-CFS-048-086	12	SEE MAP	5%	340
EL-CFS-048-087	12	SEE MAP	5%	340
EL-CFS-048-088	12	SEE MAP	4%	271
EL-CFS-048-089	24	SEE MAP	5%	426
EL-CFS-048-090	24	SEE MAP	5%	426
EL-CFS-048-091	24	SEE MAP	5%	426
EL-CFS-048-092	12	SEE MAP	4%	90
EL-CFS-048-093	12	SEE MAP	4%	90
EL-CFS-048-094	12	SEE MAP	2%	115
EL-CFS-048-095	12	SEE MAP	2%	115
EL-CFS-048-096	12	SEE MAP	4%	271
EL-CFS-048-097	12	SEE MAP	3%	330
EL-CFS-048-098	12	SEE MAP	11%	49
EL-CFS-048-099	12	SEE MAP	11%	72
EL-CFS-048-100	12	SEE MAP	11%	72
EL-CFS-048-101	12	SEE MAP	11%	72
EL-CFS-048-102	12	SEE MAP	5%	100
EL-CFS-048-103	12	SEE MAP	5%	100
EL-CFS-048-104	12	SEE MAP	5%	100
EL-CFS-048-105	12	SEE MAP	4%	256
EL-CFS-048-106	12	SEE MAP	4%	256
EL-CFS-048-107	12	SEE MAP	4%	256
EL-CFS-048-108	12	SEE MAP	3%	308
EL-CFS-048-109	12	SEE MAP	12%	57

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-048-110	12	SEE MAP	12%	57
EL-CFS-048-111	12	SEE MAP	13%	62
EL-CFS-048-112	12	SEE MAP	13%	62
EL-CFS-048-113	12	SEE MAP	13%	62
EL-CFS-048-114	12	SEE MAP	13%	62
EL-CFS-048-115	12	SEE MAP	17%	53
EL-CFS-048-116	12	SEE MAP	17%	53
EL-CFS-048-117	12	SEE MAP	17%	53
EL-CFS-048-118	12	SEE MAP	17%	53
EL-CFS-048-119	12	SEE MAP	17%	53
EL-CFS-048-120	12	SEE MAP	41%	27
EL-CFS-048-121	12	SEE MAP	41%	27
EL-CFS-048-122	12	SEE MAP	41%	27
EL-CFS-048-123	12	SEE MAP	41%	27
EL-CFS-048-124	12	SEE MAP	41%	27
EL-CFS-048-125	12	SEE MAP	18%	67
EL-CFS-048-126	24	SEE MAP	8%	310
EL-CFS-048-127	18	SEE MAP	10%	260
EL-CFS-048-128	18	SEE MAP	10%	260
EL-CFS-048-129	18	SEE MAP	10%	260
EL-CFS-048-130	12	SEE MAP	6%	131
EL-CFS-048-131	12	SEE MAP	6%	131
EL-CFS-048-132	24	SEE MAP	10%	321
EL-CFS-048-133	24	SEE MAP	10%	321
EL-CFS-048-134	12	SEE MAP	5%	242
EL-CFS-048-135	12	SEE MAP	5%	242

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-048-136	12	SEE MAP	5%	242
EL-CFS-048-137	12	SEE MAP	5%	242
EL-CFS-048-138	12	SEE MAP	5%	242
EL-CFS-048-139	12	SEE MAP	5%	242
EL-CFS-048-140	12	SEE MAP	4%	24
EL-CFS-048-141	12	SEE MAP	4%	24
EL-CFS-049-001	24	SEE MAP	5%	426
EL-CFS-049-002	12	SEE MAP	8%	143
EL-CFS-049-003	12	SEE MAP	8%	143
EL-CFS-049-004	12	SEE MAP	8%	143
EL-CFS-049-005	12	SEE MAP	8%	143
EL-CFS-049-006	12	SEE MAP	8%	143
EL-CFS-049-007	12	SEE MAP	8%	195
EL-CFS-049-008	12	SEE MAP	8%	195
EL-CFS-049-009	12	SEE MAP	8%	195
EL-CFS-049-010	12	SEE MAP	8%	195
EL-CFS-049-011	12	SEE MAP	8%	195
EL-CFS-049-012	18	SEE MAP	13%	210
EL-CFS-049-013	18	SEE MAP	13%	210
EL-CFS-049-014	18	SEE MAP	13%	210
EL-CFS-049-015	18	SEE MAP	13%	210
EL-CFS-049-016	18	SEE MAP	13%	210
EL-CFS-049-017	18	SEE MAP	13%	210
EL-CFS-049-018	12	SEE MAP	10%	81
EL-CFS-049-019	12	SEE MAP	10%	81
EL-CFS-049-020	12	SEE MAP	10%	81

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-021	12	SEE MAP	10%	81
EL-CFS-049-022	12	SEE MAP	10%	81
EL-CFS-049-023	12	SEE MAP	10%	81
EL-CFS-049-024	12	SEE MAP	10%	81
EL-CFS-049-025	12	SEE MAP	10%	81
EL-CFS-049-026	12	SEE MAP	10%	81
EL-CFS-049-027	12	SEE MAP	10%	145
EL-CFS-049-028	12	SEE MAP	10%	145
EL-CFS-049-029	12	SEE MAP	10%	145
EL-CFS-049-030	12	SEE MAP	3%	73
EL-CFS-049-031	18	SEE MAP	29%	70
EL-CFS-049-032	18	SEE MAP	29%	70
EL-CFS-049-033	18	SEE MAP	29%	70
EL-CFS-049-034	18	SEE MAP	29%	70
EL-CFS-049-035	18	SEE MAP	29%	70
EL-CFS-049-036	18	SEE MAP	29%	70
EL-CFS-049-037	18	SEE MAP	29%	70
EL-CFS-049-038	18	SEE MAP	29%	70
EL-CFS-049-039	12	SEE MAP	9%	109
EL-CFS-049-040	12	SEE MAP	5%	148
EL-CFS-049-041	12	SEE MAP	5%	148
EL-CFS-049-042	12	SEE MAP	5%	148
EL-CFS-049-043	12	SEE MAP	5%	148
EL-CFS-049-044	12	SEE MAP	5%	148
EL-CFS-049-045	12	SEE MAP	Wetland	
EL-CFS-049-046	12	SEE MAP	Wetland	

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-047	12	SEE MAP	3%	76
EL-CFS-049-048	12	SEE MAP	3%	76
EL-CFS-049-049	12	SEE MAP	3%	76
EL-CFS-049-050	18	SEE MAP	15%	104
EL-CFS-049-051	18	SEE MAP	22%	115
EL-CFS-049-052	18	SEE MAP	19%	124
EL-CFS-049-053	18	SEE MAP	19%	124
EL-CFS-049-054	18	SEE MAP	19%	124
EL-CFS-049-055	18	SEE MAP	19%	124
EL-CFS-049-056	18	SEE MAP	19%	124
EL-CFS-049-057	18	SEE MAP	19%	124
EL-CFS-049-058	18	SEE MAP	19%	124
EL-CFS-049-059	18	SEE MAP	19%	124
EL-CFS-049-060	18	SEE MAP	19%	124
EL-CFS-049-061	18	SEE MAP	19%	124
EL-CFS-049-062	12	SEE MAP	11%	88
EL-CFS-049-063	12	SEE MAP	11%	88
EL-CFS-049-064	12	SEE MAP	11%	88
EL-CFS-049-065	12	SEE MAP	11%	88
EL-CFS-049-066	12	SEE MAP	11%	88
EL-CFS-049-067	12	SEE MAP	16%	37
EL-CFS-049-068	12	SEE MAP	16%	37
EL-CFS-049-069	12	SEE MAP	16%	37
EL-CFS-049-070	12	SEE MAP	17%	66
EL-CFS-049-071	12	SEE MAP	17%	66
EL-CFS-049-072	12	SEE MAP	17%	66

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-073	12	SEE MAP	17%	66
EL-CFS-049-074	12	SEE MAP	17%	66
EL-CFS-049-075	12	SEE MAP	17%	66
EL-CFS-049-076	18	SEE MAP	5%	340
EL-CFS-049-077	18	SEE MAP	18%	138
EL-CFS-049-078	18	SEE MAP	18%	138
EL-CFS-049-079	18	SEE MAP	18%	138
EL-CFS-049-080	18	SEE MAP	18%	138
EL-CFS-049-081	18	SEE MAP	18%	138
EL-CFS-049-082	18	SEE MAP	18%	138
EL-CFS-049-083	18	SEE MAP	18%	138
EL-CFS-049-084	18	SEE MAP	18%	138
EL-CFS-049-085	18	SEE MAP	18%	138
EL-CFS-049-086	18	SEE MAP	18%	138
EL-CFS-049-087	18	SEE MAP	18%	138
EL-CFS-049-088	18	SEE MAP	18%	138
EL-CFS-049-089	24	SEE MAP	17%	210
EL-CFS-049-090	24	SEE MAP	17%	210
EL-CFS-049-091	24	SEE MAP	17%	210
EL-CFS-049-092	24	SEE MAP	17%	210
EL-CFS-049-093	24	SEE MAP	17%	210
EL-CFS-049-094	24	SEE MAP	17%	210
EL-CFS-049-095	24	SEE MAP	17%	210
EL-CFS-049-096	24	SEE MAP	17%	210
EL-CFS-049-097	24	SEE MAP	17%	210
EL-CFS-049-098	24	SEE MAP	17%	210

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-099	24	SEE MAP	17%	210
EL-CFS-049-100	24	SEE MAP	17%	210
EL-CFS-049-101	12	SEE MAP	9%	74
EL-CFS-049-102	12	SEE MAP	9%	74
EL-CFS-049-103	12	SEE MAP	9%	74
EL-CFS-049-104	12	SEE MAP	9%	74
EL-CFS-049-105	18	SEE MAP	9%	254
EL-CFS-049-106	18	SEE MAP	9%	254
EL-CFS-049-107	18	SEE MAP	9%	254
EL-CFS-049-108	18	SEE MAP	9%	254
EL-CFS-049-109	18	SEE MAP	9%	254
EL-CFS-049-110	18	SEE MAP	9%	254
EL-CFS-049-111	18	SEE MAP	9%	254
EL-CFS-049-112	18	SEE MAP	9%	254
EL-CFS-049-113	18	SEE MAP	9%	254
EL-CFS-049-114	18	SEE MAP	9%	254
EL-CFS-049-115	18	SEE MAP	9%	254
EL-CFS-049-116	18	SEE MAP	9%	254
EL-CFS-049-117	18	SEE MAP	9%	254
EL-CFS-049-118	18	SEE MAP	8%	229
EL-CFS-049-119	18	SEE MAP	8%	229
EL-CFS-049-120	18	SEE MAP	8%	229
EL-CFS-049-121	18	SEE MAP	8%	229
EL-CFS-049-122	12	SEE MAP	10%	81
EL-CFS-049-123	12	SEE MAP	10%	81
EL-CFS-049-124	24	SEE MAP	26%	104

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-125	24	SEE MAP	26%	104
EL-CFS-049-126	24	SEE MAP	26%	104
EL-CFS-049-127	24	SEE MAP	26%	104
EL-CFS-049-128	24	SEE MAP	26%	104
EL-CFS-049-129	24	SEE MAP	26%	104
EL-CFS-049-130	24	SEE MAP	26%	104
EL-CFS-049-131	24	SEE MAP	26%	104
EL-CFS-049-132	24	SEE MAP	26%	104
EL-CFS-049-133	24	SEE MAP	26%	104
EL-CFS-049-134	24	SEE MAP	26%	104
EL-CFS-049-135	24	SEE MAP	26%	104
EL-CFS-049-136	24	SEE MAP	30%	99
EL-CFS-049-137	24	SEE MAP	30%	99
EL-CFS-049-138	24	SEE MAP	30%	99
EL-CFS-049-139	24	SEE MAP	30%	99
EL-CFS-049-140	24	SEE MAP	30%	99
EL-CFS-049-141	24	SEE MAP	30%	99
EL-CFS-049-142	24	SEE MAP	30%	99
EL-CFS-049-143	24	SEE MAP	30%	99
EL-CFS-049-144	24	SEE MAP	30%	99
EL-CFS-049-145	24	SEE MAP	30%	99
EL-CFS-049-146	24	SEE MAP	30%	99
EL-CFS-049-147	24	SEE MAP	30%	99
EL-CFS-049-148	24	SEE MAP	30%	99
EL-CFS-049-149	24	SEE MAP	30%	99
EL-CFS-049-150	24	SEE MAP	30%	99

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-151	24	SEE MAP	27%	96
EL-CFS-049-152	24	SEE MAP	27%	96
EL-CFS-049-153	24	SEE MAP	27%	96
EL-CFS-049-154	24	SEE MAP	27%	96
EL-CFS-049-155	24	SEE MAP	27%	96
EL-CFS-049-156	24	SEE MAP	27%	96
EL-CFS-049-157	24	SEE MAP	27%	96
EL-CFS-049-158	24	SEE MAP	27%	96
EL-CFS-049-159	24	SEE MAP	27%	96
EL-CFS-049-160	24	SEE MAP	27%	96
EL-CFS-049-161	24	SEE MAP	27%	96
EL-CFS-049-162	24	SEE MAP	27%	96
EL-CFS-049-163	24	SEE MAP	27%	96
EL-CFS-049-164	18	SEE MAP	35%	60
EL-CFS-049-165	18	SEE MAP	35%	60
EL-CFS-049-166	18	SEE MAP	35%	60
EL-CFS-049-167	18	SEE MAP	35%	60
EL-CFS-049-168	18	SEE MAP	35%	60
EL-CFS-049-169	18	SEE MAP	35%	60
EL-CFS-049-170	18	SEE MAP	35%	60
EL-CFS-049-171	18	SEE MAP	35%	60
EL-CFS-049-172	18	SEE MAP	35%	60
EL-CFS-049-173	18	SEE MAP	25%	92
EL-CFS-049-174	18	SEE MAP	25%	92
EL-CFS-049-175	18	SEE MAP	25%	92
EL-CFS-049-176	18	SEE MAP	25%	92

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-177	18	SEE MAP	25%	92
EL-CFS-049-178	18	SEE MAP	25%	92
EL-CFS-049-179	18	SEE MAP	10%	229
EL-CFS-049-180	18	SEE MAP	10%	229
EL-CFS-049-181	18	SEE MAP	10%	229
EL-CFS-049-182	18	SEE MAP	10%	229
EL-CFS-049-183	18	SEE MAP	10%	229
EL-CFS-049-184	18	SEE MAP	10%	229
EL-CFS-049-185	18	SEE MAP	10%	229
EL-CFS-049-186	18	SEE MAP	10%	229
EL-CFS-049-187	18	SEE MAP	10%	229
EL-CFS-049-188	18	SEE MAP	10%	229
EL-CFS-049-189	18	SEE MAP	10%	229
EL-CFS-049-190	12	SEE MAP	7%	174
EL-CFS-049-191	12	SEE MAP	6%	97
EL-CFS-049-192	12	SEE MAP	6%	97
EL-CFS-049-193	12	SEE MAP	Wetland	
EL-CFS-049-194	12	SEE MAP	Wetland	
EL-CFS-049-195	12	SEE MAP	2%	94
EL-CFS-049-196	12	SEE MAP	2%	94
EL-CFS-049-197	18	SEE MAP	13%	127
EL-CFS-049-198	18	SEE MAP	22%	115
EL-CFS-049-199	18	SEE MAP	22%	115
EL-CFS-049-200	18	SEE MAP	22%	115
EL-CFS-049-201	18	SEE MAP	22%	115
EL-CFS-049-202	18	SEE MAP	22%	115

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-203	18	SEE MAP	22%	115
EL-CFS-049-204	18	SEE MAP	22%	115
EL-CFS-049-205	18	SEE MAP	22%	115
EL-CFS-049-206	18	SEE MAP	22%	115
EL-CFS-049-207	18	SEE MAP	22%	115
EL-CFS-049-208	18	SEE MAP	29%	55
EL-CFS-049-209	18	SEE MAP	29%	55
EL-CFS-049-210	18	SEE MAP	29%	55
EL-CFS-049-211	18	SEE MAP	5%	340
EL-CFS-049-212	12	SEE MAP	10%	20
EL-CFS-049-213	12	SEE MAP	7%	145
EL-CFS-049-214	12	SEE MAP	7%	145
EL-CFS-049-215	12	SEE MAP	7%	145
EL-CFS-049-216	12	SEE MAP	7%	145
EL-CFS-049-217	12	SEE MAP	7%	145
EL-CFS-049-218	12	SEE MAP	15%	82
EL-CFS-049-219	12	SEE MAP	15%	82
EL-CFS-049-220	12	SEE MAP	15%	82
EL-CFS-049-221	12	SEE MAP	15%	82
EL-CFS-049-222	12	SEE MAP	15%	82
EL-CFS-049-223	12	SEE MAP	15%	82
EL-CFS-049-224	18	SEE MAP	13%	186
EL-CFS-049-225	18	SEE MAP	13%	186
EL-CFS-049-226	18	SEE MAP	13%	186
EL-CFS-049-227	18	SEE MAP	13%	186
EL-CFS-049-228	18	SEE MAP	13%	186

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-229	12	SEE MAP	9%	150
EL-CFS-049-230	12	SEE MAP	9%	150
EL-CFS-049-231	12	SEE MAP	9%	150
EL-CFS-049-232	18	SEE MAP	17%	132
EL-CFS-049-233	18	SEE MAP	17%	132
EL-CFS-049-234	18	SEE MAP	17%	132
EL-CFS-049-235	18	SEE MAP	17%	132
EL-CFS-049-236	18	SEE MAP	17%	132
EL-CFS-049-237	18	SEE MAP	17%	132
EL-CFS-049-238	18	SEE MAP	17%	115
EL-CFS-049-239	18	SEE MAP	15%	115
EL-CFS-049-240	18	SEE MAP	15%	115
EL-CFS-049-241	18	SEE MAP	15%	115
EL-CFS-049-242	18	SEE MAP	15%	115
EL-CFS-049-243	18	SEE MAP	15%	115
EL-CFS-049-244	18	SEE MAP	15%	115
EL-CFS-049-245	18	SEE MAP	15%	115
EL-CFS-049-246	18	SEE MAP	15%	115
EL-CFS-049-247	18	SEE MAP	15%	115
EL-CFS-049-248	18	SEE MAP	15%	115
EL-CFS-049-249	18	SEE MAP	15%	115
EL-CFS-049-250	18	SEE MAP	29%	62
EL-CFS-049-251	12	SEE MAP	5%	150
EL-CFS-049-252	12	SEE MAP	5%	150
EL-CFS-049-253	12	SEE MAP	14%	7
EL-CFS-049-254	18	SEE MAP	8%	216

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-049-255	18	SEE MAP	8%	216
EL-CFS-049-256	18	SEE MAP	8%	216
EL-CFS-049-257	18	SEE MAP	8%	216
EL-CFS-050-001	32	SEE MAP	5%	531
EL-CFS-050-002	32	SEE MAP	5%	531
EL-CFS-050-003	24	SEE MAP	4%	456
EL-CFS-050-004	24	SEE MAP	4%	456
EL-CFS-050-005	24	SEE MAP	4%	456
EL-CFS-050-006	12	SEE MAP	3%	173
EL-CFS-050-007	12	SEE MAP	3%	109
EL-CFS-050-008	12	SEE MAP	2%	373
EL-CFS-050-009	12	SEE MAP	2%	373
EL-CFS-050-010	12	SEE MAP	2%	373
EL-CFS-050-011	12	SEE MAP	3%	112
EL-CFS-050-012	12	SEE MAP	4%	193
EL-CFS-050-013	12	SEE MAP	4%	193
EL-CFS-050-014	12	SEE MAP	4%	193
EL-CFS-050-015	12	SEE MAP	4%	193
EL-CFS-050-016	12	SEE MAP	6%	97
EL-CFS-050-017	12	SEE MAP	6%	97
EL-CFS-050-018	12	SEE MAP	6%	97
EL-CFS-050-019	12	SEE MAP	6%	97
EL-CFS-050-020	12	SEE MAP	8%	72
EL-CFS-050-021	12	SEE MAP	8%	72
EL-CFS-050-022	12	SEE MAP	8%	72
EL-CFS-050-023	12	SEE MAP	16%	38

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-050-024	12	SEE MAP	16%	38
EL-CFS-050-025	18	SEE MAP	14%	174
EL-CFS-050-026	18	SEE MAP	14%	174
EL-CFS-050-027	18	SEE MAP	14%	174
EL-CFS-050-028	18	SEE MAP	14%	174
EL-CFS-050-029	18	SEE MAP	14%	174
EL-CFS-050-030	18	SEE MAP	14%	174
EL-CFS-050-031	18	SEE MAP	14%	174
EL-CFS-050-032	18	SEE MAP	14%	174
EL-CFS-050-033	18	SEE MAP	14%	174
EL-CFS-050-034	18	SEE MAP	14%	174
EL-CFS-050-035	18	SEE MAP	14%	174
EL-CFS-050-036	18	SEE MAP	14%	174
EL-CFS-050-037	18	SEE MAP	14%	174
EL-CFS-050-038	18	SEE MAP	24%	109
EL-CFS-050-039	18	SEE MAP	24%	109
EL-CFS-050-040	18	SEE MAP	28%	36
EL-CFS-050-041	18	SEE MAP	28%	36
EL-CFS-050-042	18	SEE MAP	28%	36
EL-CFS-050-043	18	SEE MAP	28%	36
EL-CFS-050-044	18	SEE MAP	22%	97
EL-CFS-050-045	18	SEE MAP	22%	97
EL-CFS-050-046	18	SEE MAP	22%	97
EL-CFS-050-047	18	SEE MAP	22%	97
EL-CFS-050-048	18	SEE MAP	22%	97
EL-CFS-050-049	18	SEE MAP	22%	97

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-050-050	12	SEE MAP	20%	20
EL-CFS-050-051	12	SEE MAP	20%	20
EL-CFS-050-052	12	SEE MAP	10%	102
EL-CFS-050-053	12	SEE MAP	10%	102
EL-CFS-050-054	12	SEE MAP	10%	102
EL-CFS-050-055	12	SEE MAP	10%	102
EL-CFS-050-056	12	SEE MAP	9%	146
EL-CFS-050-057	12	SEE MAP	9%	146
EL-CFS-050-058	12	SEE MAP	9%	146
EL-CFS-050-059	12	SEE MAP	9%	146
EL-CFS-050-060	12	SEE MAP	5%	232
EL-CFS-050-061	12	SEE MAP	5%	232
EL-CFS-050-062	12	SEE MAP	5%	232
EL-CFS-050-063	12	SEE MAP	5%	232
EL-CFS-050-064	12	SEE MAP	4%	204
EL-CFS-050-065	12	SEE MAP	4%	204
EL-CFS-050-066	12	SEE MAP	4%	204
EL-CFS-050-067	12	SEE MAP	4%	204
EL-CFS-050-068	24	SEE MAP	4%	523
EL-CFS-050-069	12	SEE MAP	3%	36
EL-CFS-050-070	12	SEE MAP	8%	25
EL-CFS-050-071	12	SEE MAP	13%	31
EL-CFS-050-072	12	SEE MAP	13%	31
EL-CFS-050-073	12	SEE MAP	3%	118
EL-CFS-050-074	12	SEE MAP	3%	118
EL-CFS-050-075	12	SEE MAP	2%	152

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-050-076	12	SEE MAP	2%	152
EL-CFS-050-077	24	SEE MAP	4%	506
EL-CFS-050-078	18	SEE MAP	4%	346
EL-CFS-050-079	18	SEE MAP	4%	346
EL-CFS-050-080	18	SEE MAP	4%	346
EL-CFS-050-081	18	SEE MAP	4%	346
EL-CFS-050-082	24	SEE MAP	4%	569
EL-CFS-050-083	24	SEE MAP	4%	569
EL-CFS-050-084	24	SEE MAP	4%	569
EL-CFS-050-085	24	SEE MAP	4%	569
EL-CFS-050-086	24	SEE MAP	4%	569
EL-CFS-050-087	24	SEE MAP	4%	569
EL-CFS-050-088	12	SEE MAP	3%	173
EL-CFS-050-089	12	SEE MAP	3%	173
EL-CFS-050-090	12	SEE MAP	3%	173
EL-CFS-050-091	12	SEE MAP	3%	173
EL-CFS-050-092	12	SEE MAP	3%	109
EL-CFS-050-093	18	SEE MAP	4%	406
EL-CFS-050-094	18	SEE MAP	4%	406
EL-CFS-050-095	18	SEE MAP	4%	406
EL-CFS-050-096	18	SEE MAP	4%	406
EL-CFS-050-097	18	SEE MAP	4%	406
EL-CFS-050-098	18	SEE MAP	4%	406
EL-CFS-050-099	18	SEE MAP	4%	406
EL-CFS-050-100	12	SEE MAP	5%	177
EL-CFS-050-101	12	SEE MAP	7%	90

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-050-128	18	SEE MAP	14%	123
EL-CFS-050-129	18	SEE MAP	14%	123
EL-CFS-050-130	12	SEE MAP	9%	129
EL-CFS-050-131	12	SEE MAP	9%	129
EL-CFS-050-132	12	SEE MAP	9%	129
EL-CFS-050-133	12	SEE MAP	5%	130
EL-CFS-050-134	12	SEE MAP	5%	130
EL-CFS-050-135	12	SEE MAP	3%	36
EL-CFS-050-136	12	SEE MAP	2%	116
EL-CFS-050-137	12	SEE MAP	4%	179
EL-CFS-050-138	12	SEE MAP	2%	340
EL-CFS-050-139	12	SEE MAP	2%	340
EL-CFS-050-140	12	SEE MAP	2%	340
EL-CFS-050-141	12	SEE MAP	2%	340
EL-CFS-050-142	12	SEE MAP	3%	216
EL-CFS-050-143	12	SEE MAP	3%	216
EL-CFS-050-144	12	SEE MAP	3%	216
EL-CFS-051-001	12	SEE MAP	4%	48
EL-CFS-051-002	12	SEE MAP	6%	100
EL-CFS-051-003	12	SEE MAP	15%	20
EL-CFS-051-004	12	SEE MAP	6%	149
EL-CFS-051-005	12	SEE MAP	6%	149
EL-CFS-051-006	12	SEE MAP	6%	149
EL-CFS-051-007	12	SEE MAP	6%	149
EL-CFS-051-008	12	SEE MAP	7%	128
EL-CFS-051-009	12	SEE MAP	7%	128

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-010	12	SEE MAP	7%	27
EL-CFS-051-011	12	SEE MAP	7%	82
EL-CFS-051-012	12	SEE MAP	7%	82
EL-CFS-051-013	12	SEE MAP	8%	26
EL-CFS-051-014	12	SEE MAP	8%	26
EL-CFS-051-015	12	SEE MAP	10%	142
EL-CFS-051-016	12	SEE MAP	10%	142
EL-CFS-051-017	12	SEE MAP	10%	142
EL-CFS-051-018	12	SEE MAP	10%	142
EL-CFS-051-019	12	SEE MAP	10%	142
EL-CFS-051-020	12	SEE MAP	5%	62
EL-CFS-051-021	12	SEE MAP	5%	62
EL-CFS-051-022	12	SEE MAP	5%	62
EL-CFS-051-023	12	SEE MAP	9%	108
EL-CFS-051-024	12	SEE MAP	9%	108
EL-CFS-051-025	12	SEE MAP	9%	108
EL-CFS-051-026	12	SEE MAP	9%	108
EL-CFS-051-027	12	SEE MAP	9%	108
EL-CFS-051-028	12	SEE MAP	9%	139
EL-CFS-051-029	12	SEE MAP	9%	139
EL-CFS-051-030	12	SEE MAP	9%	139
EL-CFS-051-031	12	SEE MAP	9%	139
EL-CFS-051-032	12	SEE MAP	9%	139
EL-CFS-051-033	12	SEE MAP	9%	139
EL-CFS-051-034	12	SEE MAP	9%	139
EL-CFS-051-035	12	SEE MAP	7%	15

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop


LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-036	12	SEE MAP	10%	130
EL-CFS-051-037	12	SEE MAP	10%	130
EL-CFS-051-038	12	SEE MAP	10%	130
EL-CFS-051-039	12	SEE MAP	10%	130
EL-CFS-051-040	12	SEE MAP	10%	130
EL-CFS-051-041	12	SEE MAP	10%	130
EL-CFS-051-042	18	SEE MAP	11%	207
EL-CFS-051-043	18	SEE MAP	11%	207
EL-CFS-051-044	18	SEE MAP	11%	207
EL-CFS-051-045	18	SEE MAP	11%	207
EL-CFS-051-046	18	SEE MAP	11%	207
EL-CFS-051-047	18	SEE MAP	11%	207
EL-CFS-051-048	18	SEE MAP	11%	207
EL-CFS-051-049	18	SEE MAP	11%	207
EL-CFS-051-050	18	SEE MAP	11%	207
EL-CFS-051-051	18	SEE MAP	11%	207
EL-CFS-051-052	18	SEE MAP	11%	207
EL-CFS-051-053	18	SEE MAP	12%	133
EL-CFS-051-054	18	SEE MAP	12%	133
EL-CFS-051-055	18	SEE MAP	12%	133
EL-CFS-051-056	18	SEE MAP	12%	133
EL-CFS-051-057	18	SEE MAP	12%	133
EL-CFS-051-058	18	SEE MAP	12%	147
EL-CFS-051-059	18	SEE MAP	12%	147
EL-CFS-051-060	18	SEE MAP	12%	147
EL-CFS-051-061	18	SEE MAP	12%	147

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-062	18	SEE MAP	12%	147
EL-CFS-051-063	18	SEE MAP	12%	147
EL-CFS-051-064	18	SEE MAP	12%	147
EL-CFS-051-065	18	SEE MAP	12%	147
EL-CFS-051-066	18	SEE MAP	13%	171
EL-CFS-051-067	18	SEE MAP	13%	171
EL-CFS-051-068	18	SEE MAP	13%	171
EL-CFS-051-069	18	SEE MAP	13%	171
EL-CFS-051-070	18	SEE MAP	13%	171
EL-CFS-051-071	18	SEE MAP	13%	171
EL-CFS-051-072	18	SEE MAP	13%	171
EL-CFS-051-073	18	SEE MAP	13%	171
EL-CFS-051-074	12	SEE MAP	14%	98
EL-CFS-051-075	12	SEE MAP	14%	98
EL-CFS-051-076	12	SEE MAP	14%	98
EL-CFS-051-077	12	SEE MAP	14%	98
EL-CFS-051-078	12	SEE MAP	14%	98
EL-CFS-051-079	12	SEE MAP	14%	98
EL-CFS-051-080	12	SEE MAP	14%	98
EL-CFS-051-081	18	SEE MAP	18%	88
EL-CFS-051-082	18	SEE MAP	18%	88
EL-CFS-051-083	18	SEE MAP	18%	88
EL-CFS-051-084	18	SEE MAP	18%	88
EL-CFS-051-085	18	SEE MAP	18%	88
EL-CFS-051-086	18	SEE MAP	18%	88
EL-CFS-051-087	18	SEE MAP	18%	88

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-088	18	SEE MAP	18%	88
EL-CFS-051-089	12	SEE MAP	19%	73
EL-CFS-051-090	12	SEE MAP	19%	73
EL-CFS-051-091	12	SEE MAP	19%	73
EL-CFS-051-092	12	SEE MAP	19%	73
EL-CFS-051-093	12	SEE MAP	19%	73
EL-CFS-051-094	12	SEE MAP	19%	73
EL-CFS-051-095	12	SEE MAP	19%	73
EL-CFS-051-096	24	SEE MAP	23%	117
EL-CFS-051-097	24	SEE MAP	23%	117
EL-CFS-051-098	24	SEE MAP	23%	117
EL-CFS-051-099	24	SEE MAP	23%	117
EL-CFS-051-100	24	SEE MAP	23%	117
EL-CFS-051-101	24	SEE MAP	23%	117
EL-CFS-051-102	24	SEE MAP	23%	117
EL-CFS-051-103	24	SEE MAP	23%	117
EL-CFS-051-104	24	SEE MAP	23%	117
EL-CFS-051-105	24	SEE MAP	23%	117
EL-CFS-051-106	24	SEE MAP	23%	117
EL-CFS-051-107	24	SEE MAP	23%	117
EL-CFS-051-108	24	SEE MAP	23%	117
EL-CFS-051-109	18	SEE MAP	37%	54
EL-CFS-051-110	18	SEE MAP	37%	54
EL-CFS-051-111	18	SEE MAP	37%	54
EL-CFS-051-112	18	SEE MAP	37%	54
EL-CFS-051-113	18	SEE MAP	37%	54

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-114	18	SEE MAP	37%	54
EL-CFS-051-115	18	SEE MAP	37%	54
EL-CFS-051-116	18	SEE MAP	37%	54
EL-CFS-051-117	18	SEE MAP	37%	54
EL-CFS-051-118	18	SEE MAP	37%	54
EL-CFS-051-119	24	SEE MAP	53%	34
EL-CFS-051-120	24	SEE MAP	53%	34
EL-CFS-051-121	24	SEE MAP	53%	34
EL-CFS-051-122	24	SEE MAP	53%	34
EL-CFS-051-123	24	SEE MAP	53%	34
EL-CFS-051-124	24	SEE MAP	53%	34
EL-CFS-051-125	24	SEE MAP	53%	34
EL-CFS-051-126	24	SEE MAP	53%	34
EL-CFS-051-127	32	SEE MAP	56%	43
EL-CFS-051-128	32	SEE MAP	56%	43
EL-CFS-051-129	32	SEE MAP	56%	43
EL-CFS-051-130	32	SEE MAP	56%	43
EL-CFS-051-131	32	SEE MAP	56%	43
EL-CFS-051-132	32	SEE MAP	56%	43
EL-CFS-051-133	32	SEE MAP	56%	43
EL-CFS-051-134	32	SEE MAP	56%	43
EL-CFS-051-135	32	SEE MAP	56%	43
EL-CFS-051-136	32	SEE MAP	56%	43
EL-CFS-051-137	32	SEE MAP	56%	43
EL-CFS-051-138	32	SEE MAP	56%	43
EL-CFS-051-139	32	SEE MAP	52%	52

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-140	32	SEE MAP	52%	52
EL-CFS-051-141	32	SEE MAP	52%	52
EL-CFS-051-142	32	SEE MAP	52%	52
EL-CFS-051-143	32	SEE MAP	52%	52
EL-CFS-051-144	32	SEE MAP	52%	52
EL-CFS-051-145	32	SEE MAP	52%	52
EL-CFS-051-146	32	SEE MAP	52%	52
EL-CFS-051-147	32	SEE MAP	52%	52
EL-CFS-051-148	32	SEE MAP	52%	52
EL-CFS-051-149	32	SEE MAP	52%	52
EL-CFS-051-150	32	SEE MAP	52%	52
EL-CFS-051-151	32	SEE MAP	52%	52
EL-CFS-051-152	32	SEE MAP	61%	44
EL-CFS-051-153	32	SEE MAP	61%	44
EL-CFS-051-154	32	SEE MAP	61%	44
EL-CFS-051-155	32	SEE MAP	61%	44
EL-CFS-051-156	32	SEE MAP	61%	44
EL-CFS-051-157	32	SEE MAP	61%	44
EL-CFS-051-158	32	SEE MAP	61%	44
EL-CFS-051-159	32	SEE MAP	61%	44
EL-CFS-051-160	32	SEE MAP	61%	44
EL-CFS-051-161	32	SEE MAP	61%	44
EL-CFS-051-162	32	SEE MAP	61%	44
EL-CFS-051-163	32	SEE MAP	61%	44
EL-CFS-051-164	32	SEE MAP	61%	44
EL-CFS-051-165	32	SEE MAP	61%	49

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-166	32	SEE MAP	61%	49
EL-CFS-051-167	32	SEE MAP	61%	49
EL-CFS-051-168	32	SEE MAP	61%	49
EL-CFS-051-169	32	SEE MAP	61%	49
EL-CFS-051-170	32	SEE MAP	61%	49
EL-CFS-051-171	32	SEE MAP	61%	49
EL-CFS-051-172	32	SEE MAP	61%	49
EL-CFS-051-173	32	SEE MAP	61%	49
EL-CFS-051-174	32	SEE MAP	61%	49
EL-CFS-051-175	32	SEE MAP	61%	49
EL-CFS-051-176	32	SEE MAP	61%	49
EL-CFS-051-177	32	SEE MAP	61%	49
EL-CFS-051-178	32	SEE MAP	61%	49
EL-CFS-051-179	32	SEE MAP	61%	49
EL-CFS-051-180	32	SEE MAP	64%	47
EL-CFS-051-181	32	SEE MAP	64%	47
EL-CFS-051-182	32	SEE MAP	64%	47
EL-CFS-051-183	32	SEE MAP	64%	47
EL-CFS-051-184	32	SEE MAP	64%	47
EL-CFS-051-185	32	SEE MAP	64%	47
EL-CFS-051-186	32	SEE MAP	64%	47
EL-CFS-051-187	32	SEE MAP	64%	47
EL-CFS-051-188	32	SEE MAP	64%	47
EL-CFS-051-189	32	SEE MAP	64%	47
EL-CFS-051-190	32	SEE MAP	64%	47
EL-CFS-051-191	32	SEE MAP	64%	47

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-192	32	SEE MAP	64%	47
EL-CFS-051-193	32	SEE MAP	64%	47
EL-CFS-051-194	32	SEE MAP	54%	54
EL-CFS-051-195	32	SEE MAP	54%	54
EL-CFS-051-196	32	SEE MAP	54%	54
EL-CFS-051-197	32	SEE MAP	54%	54
EL-CFS-051-198	32	SEE MAP	54%	54
EL-CFS-051-199	32	SEE MAP	54%	54
EL-CFS-051-200	32	SEE MAP	54%	54
EL-CFS-051-201	32	SEE MAP	54%	54
EL-CFS-051-202	32	SEE MAP	54%	54
EL-CFS-051-203	32	SEE MAP	54%	54
EL-CFS-051-204	32	SEE MAP	54%	54
EL-CFS-051-205	32	SEE MAP	54%	54
EL-CFS-051-206	32	SEE MAP	54%	54
EL-CFS-051-207	32	SEE MAP	54%	54
EL-CFS-051-208	32	SEE MAP	45%	65
EL-CFS-051-209	32	SEE MAP	45%	65
EL-CFS-051-210	32	SEE MAP	45%	65
EL-CFS-051-211	32	SEE MAP	45%	65
EL-CFS-051-212	32	SEE MAP	45%	65
EL-CFS-051-213	32	SEE MAP	45%	65
EL-CFS-051-214	32	SEE MAP	45%	65
EL-CFS-051-215	32	SEE MAP	45%	65
EL-CFS-051-216	32	SEE MAP	45%	65
EL-CFS-051-217	12	SEE MAP	3%	232

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop


LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-218	12	SEE MAP	3%	232
EL-CFS-051-219	12	SEE MAP	3%	232
EL-CFS-051-220	12	SEE MAP	2%	168
EL-CFS-051-221	12	SEE MAP	2%	168
EL-CFS-051-222	12	SEE MAP	3%	112
EL-CFS-051-223	18	SEE MAP	5%	318
EL-CFS-051-224	18	SEE MAP	5%	318
EL-CFS-051-225	18	SEE MAP	5%	318
EL-CFS-051-226	18	SEE MAP	5%	318
EL-CFS-051-227	18	SEE MAP	5%	318
EL-CFS-051-228	18	SEE MAP	5%	318
EL-CFS-051-229	18	SEE MAP	5%	318
EL-CFS-051-230	18	SEE MAP	5%	318
EL-CFS-051-231	12	SEE MAP	2%	122
EL-CFS-051-232	12	SEE MAP	6%	67
EL-CFS-051-233	12	SEE MAP	8%	97
EL-CFS-051-234	12	SEE MAP	8%	97
EL-CFS-051-235	12	SEE MAP	8%	97
EL-CFS-051-236	12	SEE MAP	13%	120
EL-CFS-051-237	12	SEE MAP	13%	120
EL-CFS-051-238	12	SEE MAP	13%	120
EL-CFS-051-239	12	SEE MAP	13%	120
EL-CFS-051-240	12	SEE MAP	13%	120
EL-CFS-051-241	12	SEE MAP	11%	88
EL-CFS-051-242	12	SEE MAP	11%	88
EL-CFS-051-243	12	SEE MAP	11%	88

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-051-244	12	SEE MAP	11%	88
EL-CFS-051-245	12	SEE MAP	11%	88
EL-CFS-052-001	12	SEE MAP	35%	40
EL-CFS-052-002	12	SEE MAP	35%	40
EL-CFS-052-003	12	SEE MAP	35%	40
EL-CFS-052-004	12	SEE MAP	35%	40
EL-CFS-052-005	12	SEE MAP	35%	40
EL-CFS-052-006	24	SEE MAP	43%	54
EL-CFS-052-007	24	SEE MAP	43%	54
EL-CFS-052-008	24	SEE MAP	43%	54
EL-CFS-052-009	24	SEE MAP	43%	54
EL-CFS-052-010	24	SEE MAP	43%	54
EL-CFS-052-011	24	SEE MAP	43%	54
EL-CFS-052-012	24	SEE MAP	43%	54
EL-CFS-052-013	24	SEE MAP	43%	54
EL-CFS-052-014	24	SEE MAP	43%	54
EL-CFS-052-015	24	SEE MAP	43%	54
EL-CFS-052-016	24	SEE MAP	43%	54
EL-CFS-052-017	24	SEE MAP	41%	51
EL-CFS-052-018	24	SEE MAP	41%	51
EL-CFS-052-019	24	SEE MAP	41%	51
EL-CFS-052-020	24	SEE MAP	41%	51
EL-CFS-052-021	24	SEE MAP	41%	51
EL-CFS-052-022	24	SEE MAP	41%	51
EL-CFS-052-023	24	SEE MAP	41%	51
EL-CFS-052-024	24	SEE MAP	41%	51

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-025	24	SEE MAP	41%	51
EL-CFS-052-026	24	SEE MAP	41%	51
EL-CFS-052-027	18	SEE MAP	42%	38
EL-CFS-052-028	18	SEE MAP	42%	38
EL-CFS-052-029	18	SEE MAP	42%	38
EL-CFS-052-030	18	SEE MAP	42%	38
EL-CFS-052-031	18	SEE MAP	42%	38
EL-CFS-052-032	18	SEE MAP	42%	38
EL-CFS-052-033	18	SEE MAP	42%	38
EL-CFS-052-034	18	SEE MAP	42%	38
EL-CFS-052-035	12	SEE MAP	35%	23
EL-CFS-052-036	12	SEE MAP	35%	23
EL-CFS-052-037	12	SEE MAP	35%	23
EL-CFS-052-038	12	SEE MAP	35%	23
EL-CFS-052-039	32	SEE MAP	15%	336
EL-CFS-052-040	32	SEE MAP	15%	336
EL-CFS-052-041	32	SEE MAP	15%	336
EL-CFS-052-042	32	SEE MAP	15%	336
EL-CFS-052-043	32	SEE MAP	15%	336
EL-CFS-052-044	32	SEE MAP	22%	224
EL-CFS-052-045	32	SEE MAP	22%	224
EL-CFS-052-046	32	SEE MAP	22%	224
EL-CFS-052-047	32	SEE MAP	22%	224
EL-CFS-052-048	32	SEE MAP	22%	224
EL-CFS-052-049	32	SEE MAP	22%	224
EL-CFS-052-050	32	SEE MAP	22%	224

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-051	32	SEE MAP	22%	224
EL-CFS-052-052	32	SEE MAP	22%	224
EL-CFS-052-053	32	SEE MAP	16%	283
EL-CFS-052-054	32	SEE MAP	16%	283
EL-CFS-052-055	32	SEE MAP	16%	283
EL-CFS-052-056	32	SEE MAP	16%	283
EL-CFS-052-057	32	SEE MAP	16%	283
EL-CFS-052-058	32	SEE MAP	16%	283
EL-CFS-052-059	32	SEE MAP	16%	283
EL-CFS-052-060	32	SEE MAP	16%	283
EL-CFS-052-061	32	SEE MAP	16%	283
EL-CFS-052-062	18	SEE MAP	10%	160
EL-CFS-052-063	18	SEE MAP	10%	160
EL-CFS-052-064	18	SEE MAP	10%	160
EL-CFS-052-065	18	SEE MAP	10%	160
EL-CFS-052-066	18	SEE MAP	9%	176
EL-CFS-052-067	18	SEE MAP	9%	176
EL-CFS-052-068	18	SEE MAP	9%	176
EL-CFS-052-069	12	SEE MAP	11%	142
EL-CFS-052-070	12	SEE MAP	11%	142
EL-CFS-052-071	12	SEE MAP	11%	142
EL-CFS-052-072	12	SEE MAP	11%	142
EL-CFS-052-073	12	SEE MAP	11%	142
EL-CFS-052-074	12	SEE MAP	11%	142
EL-CFS-052-075	18	SEE MAP	13%	122
EL-CFS-052-076	18	SEE MAP	13%	122

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-077	18	SEE MAP	13%	122
EL-CFS-052-078	12	SEE MAP	11%	133
EL-CFS-052-079	12	SEE MAP	11%	133
EL-CFS-052-080	12	SEE MAP	11%	133
EL-CFS-052-081	12	SEE MAP	11%	133
EL-CFS-052-082	12	SEE MAP	11%	133
EL-CFS-052-083	12	SEE MAP	11%	133
EL-CFS-052-084	12	SEE MAP	4%	192
EL-CFS-052-085	12	SEE MAP	4%	192
EL-CFS-052-086	12	SEE MAP	4%	192
EL-CFS-052-087	12	SEE MAP	6%	194
EL-CFS-052-088	12	SEE MAP	6%	194
EL-CFS-052-089	12	SEE MAP	6%	194
EL-CFS-052-090	18	SEE MAP	8%	274
EL-CFS-052-091	18	SEE MAP	8%	274
EL-CFS-052-092	18	SEE MAP	8%	274
EL-CFS-052-093	18	SEE MAP	8%	274
EL-CFS-052-094	24	SEE MAP	7%	287
EL-CFS-052-095	24	SEE MAP	7%	287
EL-CFS-052-096	24	SEE MAP	7%	287
EL-CFS-052-097	18	SEE MAP	9%	190
EL-CFS-052-098	18	SEE MAP	9%	190
EL-CFS-052-099	18	SEE MAP	9%	190
EL-CFS-052-100	18	SEE MAP	9%	190
EL-CFS-052-101	18	SEE MAP	9%	190
EL-CFS-052-102	18	SEE MAP	9%	190

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-103	12	SEE MAP	8%	164
EL-CFS-052-104	12	SEE MAP	8%	164
EL-CFS-052-105	12	SEE MAP	8%	164
EL-CFS-052-106	12	SEE MAP	8%	164
EL-CFS-052-107	18	SEE MAP	10%	187
EL-CFS-052-108	18	SEE MAP	10%	187
EL-CFS-052-109	18	SEE MAP	10%	187
EL-CFS-052-110	18	SEE MAP	10%	187
EL-CFS-052-111	18	SEE MAP	12%	156
EL-CFS-052-112	18	SEE MAP	12%	156
EL-CFS-052-113	18	SEE MAP	12%	156
EL-CFS-052-114	18	SEE MAP	12%	156
EL-CFS-052-115	18	SEE MAP	12%	156
EL-CFS-052-116	18	SEE MAP	12%	156
EL-CFS-052-117	18	SEE MAP	12%	156
EL-CFS-052-118	12	SEE MAP	6%	146
EL-CFS-052-119	12	SEE MAP	6%	146
EL-CFS-052-120	12	SEE MAP	6%	146
EL-CFS-052-121	12	SEE MAP	12%	93
EL-CFS-052-122	12	SEE MAP	12%	93
EL-CFS-052-123	12	SEE MAP	12%	93
EL-CFS-052-124	12	SEE MAP	12%	66
EL-CFS-052-125	12	SEE MAP	12%	66
EL-CFS-052-126	12	SEE MAP	12%	66
EL-CFS-052-127	18	SEE MAP	17%	95
EL-CFS-052-128	18	SEE MAP	17%	95

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-129	18	SEE MAP	17%	95
EL-CFS-052-130	18	SEE MAP	17%	95
EL-CFS-052-131	18	SEE MAP	17%	95
EL-CFS-052-132	18	SEE MAP	17%	95
EL-CFS-052-133	18	SEE MAP	17%	95
EL-CFS-052-134	12	SEE MAP	30%	33
EL-CFS-052-135	12	SEE MAP	30%	33
EL-CFS-052-136	12	SEE MAP	30%	33
EL-CFS-052-137	18	SEE MAP	28%	57
EL-CFS-052-138	18	SEE MAP	28%	57
EL-CFS-052-139	18	SEE MAP	28%	57
EL-CFS-052-140	18	SEE MAP	28%	57
EL-CFS-052-141	18	SEE MAP	28%	57
EL-CFS-052-142	18	SEE MAP	28%	57
EL-CFS-052-143	18	SEE MAP	28%	57
EL-CFS-052-144	18	SEE MAP	28%	57
EL-CFS-052-145	24	SEE MAP	38%	58
EL-CFS-052-146	24	SEE MAP	38%	58
EL-CFS-052-147	24	SEE MAP	38%	58
EL-CFS-052-148	24	SEE MAP	38%	58
EL-CFS-052-149	12	SEE MAP	50%	18
EL-CFS-052-150	32	SEE MAP	37%	75
EL-CFS-052-151	32	SEE MAP	48%	54
EL-CFS-052-152	32	SEE MAP	48%	54
EL-CFS-052-153	12	SEE MAP	57%	7
EL-CFS-052-154	32	SEE MAP	57%	56

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-155	32	SEE MAP	57%	56
EL-CFS-052-156	32	SEE MAP	57%	56
EL-CFS-052-157	32	SEE MAP	57%	56
EL-CFS-052-158	32	SEE MAP	57%	56
EL-CFS-052-159	32	SEE MAP	57%	56
EL-CFS-052-160	32	SEE MAP	57%	56
EL-CFS-052-161	32	SEE MAP	57%	56
EL-CFS-052-162	32	SEE MAP	57%	56
EL-CFS-052-163	32	SEE MAP	57%	56
EL-CFS-052-164	32	SEE MAP	50%	40
EL-CFS-052-165	32	SEE MAP	50%	40
EL-CFS-052-166	32	SEE MAP	50%	40
EL-CFS-052-167	32	SEE MAP	50%	40
EL-CFS-052-168	32	SEE MAP	50%	40
EL-CFS-052-169	32	SEE MAP	50%	40
EL-CFS-052-170	32	SEE MAP	50%	40
EL-CFS-052-171	32	SEE MAP	50%	40
EL-CFS-052-172	24	SEE MAP	39%	54
EL-CFS-052-173	18	SEE MAP	29%	48
EL-CFS-052-174	18	SEE MAP	29%	48
EL-CFS-052-175	18	SEE MAP	29%	48
EL-CFS-052-176	18	SEE MAP	29%	48
EL-CFS-052-177	18	SEE MAP	29%	48
EL-CFS-052-178	18	SEE MAP	29%	48
EL-CFS-052-179	18	SEE MAP	14%	122
EL-CFS-052-180	18	SEE MAP	14%	122

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-181	18	SEE MAP	14%	122
EL-CFS-052-182	18	SEE MAP	14%	122
EL-CFS-052-183	18	SEE MAP	14%	122
EL-CFS-052-184	18	SEE MAP	14%	122
EL-CFS-052-185	18	SEE MAP	14%	122
EL-CFS-052-186	12	SEE MAP	16%	56
EL-CFS-052-187	12	SEE MAP	16%	56
EL-CFS-052-188	12	SEE MAP	10%	99
EL-CFS-052-189	12	SEE MAP	10%	99
EL-CFS-052-190	12	SEE MAP	7%	153
EL-CFS-052-191	12	SEE MAP	7%	153
EL-CFS-052-192	12	SEE MAP	7%	153
EL-CFS-052-193	12	SEE MAP	7%	153
EL-CFS-052-194	12	SEE MAP	3%	121
EL-CFS-052-195	12	SEE MAP	3%	121
EL-CFS-052-196	12	SEE MAP	3%	175
EL-CFS-052-197	12	SEE MAP	3%	175
EL-CFS-052-198	12	SEE MAP	4%	135
EL-CFS-052-199	12	SEE MAP	4%	135
EL-CFS-052-200	12	SEE MAP	9%	22
EL-CFS-052-201	12	SEE MAP	4%	214
EL-CFS-052-202	12	SEE MAP	4%	214
EL-CFS-052-203	12	SEE MAP	4%	214
EL-CFS-052-204	32	SEE MAP	48%	54
EL-CFS-052-205	32	SEE MAP	48%	54
EL-CFS-052-206	32	SEE MAP	48%	54

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-207	32	SEE MAP	48%	54
EL-CFS-052-208	32	SEE MAP	44%	59
EL-CFS-052-209	32	SEE MAP	44%	59
EL-CFS-052-210	32	SEE MAP	44%	59
EL-CFS-052-211	32	SEE MAP	44%	59
EL-CFS-052-212	32	SEE MAP	44%	59
EL-CFS-052-213	32	SEE MAP	44%	59
EL-CFS-052-214	32	SEE MAP	44%	59
EL-CFS-052-215	32	SEE MAP	44%	59
EL-CFS-052-216	32	SEE MAP	44%	59
EL-CFS-052-217	32	SEE MAP	44%	59
EL-CFS-052-218	32	SEE MAP	44%	59
EL-CFS-052-219	32	SEE MAP	44%	59
EL-CFS-052-220	32	SEE MAP	44%	59
EL-CFS-052-221	32	SEE MAP	44%	59
EL-CFS-052-222	32	SEE MAP	48%	54
EL-CFS-052-223	32	SEE MAP	50%	60
EL-CFS-052-224	32	SEE MAP	50%	60
EL-CFS-052-225	32	SEE MAP	50%	60
EL-CFS-052-226	32	SEE MAP	50%	60
EL-CFS-052-227	32	SEE MAP	50%	60
EL-CFS-052-228	32	SEE MAP	50%	60
EL-CFS-052-229	32	SEE MAP	50%	60
EL-CFS-052-230	32	SEE MAP	50%	60
EL-CFS-052-231	32	SEE MAP	50%	60
EL-CFS-052-232	32	SEE MAP	50%	60

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-052-233	32	SEE MAP	50%	60
EL-CFS-052-234	12	SEE MAP	10%	103
EL-CFS-052-235	12	SEE MAP	10%	103
EL-CFS-052-236	12	SEE MAP	6%	98
EL-CFS-052-237	12	SEE MAP	13%	31
EL-CFS-052-238	12	SEE MAP	13%	31
EL-CFS-052-239	12	SEE MAP	12%	121
EL-CFS-052-240	12	SEE MAP	12%	121
EL-CFS-052-241	12	SEE MAP	12%	121
EL-CFS-052-242	12	SEE MAP	12%	121
EL-CFS-052-243	12	SEE MAP	12%	121
EL-CFS-052-244	12	SEE MAP	12%	121
EL-CFS-052-245	12	SEE MAP	12%	121
EL-CFS-052-246	12	SEE MAP	12%	121
EL-CFS-052-247	12	SEE MAP	4%	113
EL-CFS-052-248	12	SEE MAP	4%	113
EL-CFS-053-001	12	SEE MAP	4%	214
EL-CFS-053-002	12	SEE MAP	4%	214
EL-CFS-053-003	12	SEE MAP	6%	229
EL-CFS-053-004	12	SEE MAP	6%	229
EL-CFS-053-005	12	SEE MAP	6%	229
EL-CFS-053-006	12	SEE MAP	6%	229
EL-CFS-053-007	12	SEE MAP	6%	229
EL-CFS-053-008	12	SEE MAP	6%	229
EL-CFS-053-009	32	SEE MAP	7%	421
EL-CFS-053-010	32	SEE MAP	7%	421

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-053-011	32	SEE MAP	7%	421
EL-CFS-053-012	32	SEE MAP	7%	421
EL-CFS-053-013	32	SEE MAP	7%	421
EL-CFS-053-014	24	SEE MAP	6%	430
EL-CFS-053-015	24	SEE MAP	6%	430
EL-CFS-053-016	24	SEE MAP	6%	430
EL-CFS-053-017	24	SEE MAP	6%	430
EL-CFS-053-018	24	SEE MAP	6%	430
EL-CFS-053-019	24	SEE MAP	6%	430
EL-CFS-053-020	24	SEE MAP	3%	821
EL-CFS-053-021	24	SEE MAP	3%	821
EL-CFS-053-022	24	SEE MAP	3%	821
EL-CFS-053-023	24	SEE MAP	3%	821
EL-CFS-053-024	24	SEE MAP	3%	821
EL-CFS-053-025	12	SEE MAP	2%	235
EL-CFS-053-026	12	SEE MAP	4%	131
EL-CFS-053-027	12	SEE MAP	4%	131
EL-CFS-053-028	12	SEE MAP	4%	131
EL-CFS-053-029	12	SEE MAP	4%	131
EL-CFS-053-030	12	SEE MAP		wetland
EL-CFS-053-031	12	SEE MAP		wetland
EL-CFS-053-032	12	SEE MAP	2%	161
EL-CFS-053-033	12	SEE MAP		wetland
EL-CFS-053-034	12	SEE MAP		wetland
EL-CFS-053-035	12	SEE MAP		wetland
EL-CFS-053-036	12	SEE MAP		wetland

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-053-037	12	SEE MAP		wetland
EL-CFS-053-038	12	SEE MAP	3%	72
EL-CFS-053-039	12	SEE MAP	3%	72
EL-CFS-053-040	12	SEE MAP	3%	72
EL-CFS-053-041	12	SEE MAP	6%	163
EL-CFS-053-042	12	SEE MAP	6%	163
EL-CFS-053-043	12	SEE MAP	6%	163
EL-CFS-053-044	12	SEE MAP	6%	163
EL-CFS-053-045	12	SEE MAP	4%	245
EL-CFS-053-046	12	SEE MAP	4%	245
EL-CFS-053-047	18	SEE MAP	5%	269
EL-CFS-053-048	18	SEE MAP	5%	269
EL-CFS-053-049	18	SEE MAP	5%	269
EL-CFS-053-050	18	SEE MAP	5%	269
EL-CFS-053-051	12	SEE MAP	5%	86
EL-CFS-053-052	12	SEE MAP	5%	86
EL-CFS-053-053	12	SEE MAP	4%	174
EL-CFS-053-054	12	SEE MAP	4%	337
EL-CFS-053-055	12	SEE MAP	4%	337
EL-CFS-053-056	12	SEE MAP	4%	337
EL-CFS-053-057	12	SEE MAP	4%	337
EL-CFS-053-058	12	SEE MAP	4%	337
EL-CFS-053-059	12	SEE MAP	4%	337
EL-CFS-053-060	12	SEE MAP	6%	31
EL-CFS-053-061	12	SEE MAP	6%	31
EL-CFS-053-062	12	SEE MAP	4%	166

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**

LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**


Monroe County, Pennsylvania

PREPARED BY: **JB**

DATE: **4/5/2021**

CHECKED BY: **KCC**

DATE: **4/5/2021**




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-053-063	12	SEE MAP	4%	166
EL-CFS-053-064	18	SEE MAP	11%	176
EL-CFS-053-065	18	SEE MAP	11%	176
EL-CFS-053-066	18	SEE MAP	11%	176
EL-CFS-053-067	18	SEE MAP	11%	176
EL-CFS-053-068	18	SEE MAP	11%	176
EL-CFS-053-069	18	SEE MAP	11%	176
EL-CFS-053-070	18	SEE MAP	11%	176
EL-CFS-053-071	18	SEE MAP	11%	176
EL-CFS-053-072	12	SEE MAP	4%	120
EL-CFS-053-073	12	SEE MAP	4%	120
EL-CFS-053-074	12	SEE MAP	5%	124
EL-CFS-053-075	12	SEE MAP	5%	124
EL-CFS-053-076	12	SEE MAP	5%	124
EL-CFS-053-077	12	SEE MAP	5%	124
EL-CFS-053-078	12	SEE MAP	5%	124
EL-CFS-053-079	18	SEE MAP	4%	395
EL-CFS-053-080	18	SEE MAP	4%	395
EL-CFS-053-081	18	SEE MAP	4%	395
EL-CFS-053-082	18	SEE MAP	4%	395
EL-CFS-053-083	18	SEE MAP	4%	395
EL-CFS-053-084	18	SEE MAP	4%	395
EL-CFS-053-085	18	SEE MAP	4%	395
EL-CFS-053-086	18	SEE MAP	4%	395
EL-CFS-053-087	18	SEE MAP	4%	395
EL-CFS-053-088	12	SEE MAP	3%	201

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-053-089	12	SEE MAP	3%	201
EL-CFS-053-090	12	SEE MAP	4%	145
EL-CFS-053-091	12	SEE MAP	4%	145
EL-CFS-053-092	12	SEE MAP	wetland	
EL-CFS-053-093	12	SEE MAP	wetland	
EL-CFS-053-094	12	SEE MAP	3%	270
EL-CFS-053-095	12	SEE MAP	5%	187
EL-CFS-053-096	12	SEE MAP	5%	187
EL-CFS-053-097	12	SEE MAP	5%	65
EL-CFS-053-098	12	SEE MAP	5%	65
EL-CFS-053-099	12	SEE MAP	5%	235
EL-CFS-053-100	12	SEE MAP	5%	235
EL-CFS-053-101	12	SEE MAP	5%	235
EL-CFS-053-102	12	SEE MAP	14%	7
EL-CFS-053-103	12	SEE MAP	4%	263
EL-CFS-053-104	12	SEE MAP	4%	263
EL-CFS-053-105	12	SEE MAP	3%	202
EL-CFS-053-106	12	SEE MAP	3%	202
EL-CFS-053-107	12	SEE MAP	8%	78
EL-CFS-053-108	12	SEE MAP	8%	78
EL-CFS-054-001	12	SEE MAP	2%	187
EL-CFS-054-002	12	SEE MAP	2%	187
EL-CFS-054-003	12	SEE MAP	1%	288
EL-CFS-054-004	12	SEE MAP	1%	288
EL-CFS-054-005	12	SEE MAP	2%	637
EL-CFS-054-006	12	SEE MAP	2%	637

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-054-007	12	SEE MAP	2%	637
EL-CFS-054-008	12	SEE MAP	2%	637
EL-CFS-054-009	12	SEE MAP	2%	637
EL-CFS-054-010	12	SEE MAP	5%	322
EL-CFS-054-011	12	SEE MAP	5%	322
EL-CFS-054-012	12	SEE MAP	5%	322
EL-CFS-054-013	12	SEE MAP	5%	322
EL-CFS-054-014	12	SEE MAP	1%	236
EL-CFS-054-015	12	SEE MAP	2%	712
EL-CFS-054-016	12	SEE MAP	2%	712
EL-CFS-054-017	12	SEE MAP	2%	712
EL-CFS-054-018	12	SEE MAP	2%	712
EL-CFS-054-019	12	SEE MAP	2%	712
EL-CFS-054-020	12	SEE MAP	2%	261
EL-CFS-054-021	12	SEE MAP	2%	261
EL-CFS-054-022	12	SEE MAP	2%	261
EL-CFS-054-023	12	SEE MAP	2%	454
EL-CFS-054-024	12	SEE MAP	2%	454
EL-CFS-054-025	12	SEE MAP	2%	454
EL-CFS-054-026	12	SEE MAP	2%	454
EL-CFS-054-027	12	SEE MAP	3%	244
EL-CFS-054-028	12	SEE MAP	3%	244
EL-CFS-054-029	12	SEE MAP	3%	244
EL-CFS-054-030	12	SEE MAP	4%	332
EL-CFS-054-031	12	SEE MAP	4%	332
EL-CFS-054-032	12	SEE MAP	4%	332

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop
 LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
 Monroe County, Pennsylvania

PREPARED BY: JB
 CHECKED BY: KCC

DATE: 4/5/2021
 DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-054-033	24	SEE MAP	3%	938
EL-CFS-054-034	24	SEE MAP	3%	938
EL-CFS-054-035	24	SEE MAP	3%	938
EL-CFS-054-036	24	SEE MAP	3%	938
EL-CFS-054-037	24	SEE MAP	3%	938
EL-CFS-054-038	18	SEE MAP	5%	376
EL-CFS-054-039	12	SEE MAP	5%	322
EL-CFS-054-040	12	SEE MAP	5%	322
EL-CFS-054-041	18	SEE MAP	5%	352
EL-CFS-054-042	18	SEE MAP	5%	352
EL-CFS-054-043	18	SEE MAP	5%	352
EL-CFS-054-044	12	SEE MAP	5%	174
EL-CFS-054-045	18	SEE MAP	5%	174
EL-CFS-054-046	18	SEE MAP	5%	174
EL-CFS-054-047	18	SEE MAP	5%	174
EL-CFS-055-001	12	SEE MAP	5%	111
EL-CFS-055-002	12	SEE MAP	5%	148
EL-CFS-055-003	12	SEE MAP	5%	148
EL-CFS-055-004	12	SEE MAP	5%	121
EL-CFS-055-005	12	SEE MAP	5%	121
EL-CFS-055-006	12	SEE MAP	5%	121
EL-CFS-055-007	12	SEE MAP	5%	133
EL-CFS-055-008	12	SEE MAP	5%	133
EL-CFS-055-009	12	SEE MAP	5%	120
EL-CFS-055-010	12	SEE MAP	5%	120
EL-CFS-055-011	12	SEE MAP	5%	78

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-055-012	12	SEE MAP	5%	78
EL-CFS-055-013	12	SEE MAP	5%	77
EL-CFS-055-014	12	SEE MAP	3%	108
EL-CFS-055-015	12	SEE MAP	3%	108
EL-CFS-055-016	12	SEE MAP	3%	108
EL-CFS-055-017	12	SEE MAP	3%	108
EL-CFS-055-018	12	SEE MAP	3%	108
EL-CFS-055-019	12	SEE MAP	4%	216
EL-CFS-055-020	12	SEE MAP	4%	216
EL-CFS-055-021	12	SEE MAP	4%	216
EL-CFS-055-022	12	SEE MAP	3%	104
EL-CFS-055-023	12	SEE MAP	4%	51
EL-CFS-055-024	12	SEE MAP	4%	51
EL-CFS-055-025	32	SEE MAP	6%	561
EL-CFS-055-026	32	SEE MAP	6%	561
EL-CFS-055-027	32	SEE MAP	6%	561
EL-CFS-055-028	18	SEE MAP	9%	180
EL-CFS-055-029	18	SEE MAP	9%	180
EL-CFS-055-030	18	SEE MAP	9%	180
EL-CFS-055-031	18	SEE MAP	9%	180
EL-CFS-055-032	18	SEE MAP	9%	180
EL-CFS-055-033	18	SEE MAP	9%	180
EL-CFS-055-034	12	SEE MAP	6%	68
EL-CFS-055-035	12	SEE MAP	6%	68
EL-CFS-055-036	12	SEE MAP	6%	68
EL-CFS-055-037	24	SEE MAP	6%	333

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-055-038	24	SEE MAP	6%	333
EL-CFS-055-039	24	SEE MAP	6%	333
EL-CFS-055-040	24	SEE MAP	6%	333
EL-CFS-055-041	24	SEE MAP	6%	333
EL-CFS-055-042	24	SEE MAP	6%	333
EL-CFS-055-043	24	SEE MAP	6%	333
EL-CFS-055-044	18	SEE MAP	5%	392
EL-CFS-055-045	18	SEE MAP	5%	392
EL-CFS-055-046	18	SEE MAP	5%	392
EL-CFS-055-047	18	SEE MAP	5%	392
EL-CFS-055-048	12	SEE MAP	4%	163
EL-CFS-055-049	12	SEE MAP	4%	163
EL-CFS-055-050	12	SEE MAP	4%	163
EL-CFS-055-051	12	SEE MAP	4%	163
EL-CFS-055-052	12	SEE MAP	5%	128
EL-CFS-055-053	12	SEE MAP	5%	128
EL-CFS-055-054	12	SEE MAP	4%	108
EL-CFS-055-055	12	SEE MAP	4%	108
EL-CFS-055-056	12	SEE MAP	3%	183
EL-CFS-055-057	12	SEE MAP	3%	183
EL-CFS-055-058	12	SEE MAP	3%	183
EL-CFS-055-059	12	SEE MAP	3%	183
EL-CFS-055-060	12	SEE MAP	5%	276
EL-CFS-055-061	12	SEE MAP	5%	276
EL-CFS-055-062	12	SEE MAP	5%	276
EL-CFS-055-063	12	SEE MAP	5%	276

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-055-064	12	SEE MAP	5%	276
EL-CFS-055-065	12	SEE MAP	3%	239
EL-CFS-055-066	12	SEE MAP	3%	239
EL-CFS-055-067	12	SEE MAP	3%	179
EL-CFS-055-068	12	SEE MAP	3%	179
EL-CFS-055-069	12	SEE MAP	3%	179
EL-CFS-055-070	12	SEE MAP	4%	244
EL-CFS-055-071	12	SEE MAP	4%	244
EL-CFS-055-072	12	SEE MAP	4%	244
EL-CFS-055-073	12	SEE MAP	4%	141
EL-CFS-055-074	12	SEE MAP	4%	141
EL-CFS-055-075	12	SEE MAP	4%	141
EL-CFS-055-076	24	SEE MAP	4%	651
EL-CFS-055-077	24	SEE MAP	4%	651
EL-CFS-055-078	24	SEE MAP	4%	648
EL-CFS-055-079	24	SEE MAP	4%	648
EL-CFS-055-080	24	SEE MAP	4%	648
EL-CFS-055-081	24	SEE MAP	4%	648
EL-CFS-056-001	24	SEE MAP	3%	590
EL-CFS-056-002	24	SEE MAP	3%	590
EL-CFS-056-003	24	SEE MAP	3%	590
EL-CFS-056-004	24	SEE MAP	3%	590
EL-CFS-056-005	24	SEE MAP	3%	590
EL-CFS-056-006	24	SEE MAP	3%	590
EL-CFS-056-007	24	SEE MAP	3%	590
EL-CFS-056-008	24	SEE MAP	3%	590

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-056-009	24	SEE MAP	3%	590
EL-CFS-056-010	24	SEE MAP	3%	590
EL-CFS-056-011	18	SEE MAP	3%	519
EL-CFS-056-012	18	SEE MAP	3%	519
EL-CFS-056-013	24	SEE MAP	5%	536
EL-CFS-056-014	12	SEE MAP		wetland
EL-CFS-056-015	12	SEE MAP		wetland
EL-CFS-056-016	12	SEE MAP		wetland
EL-CFS-056-017	12	SEE MAP		wetland
EL-CFS-056-018	12	SEE MAP		wetland
EL-CFS-056-019	12	SEE MAP		wetland
EL-CFS-056-020	12	SEE MAP		wetland
EL-CFS-056-021	12	SEE MAP		wetland
EL-CFS-056-022	12	SEE MAP		wetland
EL-CFS-056-023	12	SEE MAP		wetland
EL-CFS-056-024	12	SEE MAP		wetland
EL-CFS-056-025	12	SEE MAP		wetland
EL-CFS-056-026	12	SEE MAP		wetland
EL-CFS-056-027	12	SEE MAP		wetland
EL-CFS-056-028	12	SEE MAP		wetland
EL-CFS-056-029	12	SEE MAP		wetland
EL-CFS-056-030	12	SEE MAP		wetland
EL-CFS-056-031	12	SEE MAP		wetland
EL-CFS-056-032	12	SEE MAP		wetland
EL-CFS-056-033	12	SEE MAP		wetland
EL-CFS-056-034	24	SEE MAP	4%	704

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-056-035	24	SEE MAP	4%	704
EL-CFS-056-036	24	SEE MAP	4%	704
EL-CFS-056-037	24	SEE MAP	4%	704
EL-CFS-056-038	24	SEE MAP	4%	704
EL-CFS-056-039	24	SEE MAP	4%	653
EL-CFS-056-040	24	SEE MAP	4%	653
EL-CFS-056-041	24	SEE MAP	4%	653
EL-CFS-056-042	24	SEE MAP	4%	653
EL-CFS-056-043	24	SEE MAP	4%	653
EL-CFS-056-044	24	SEE MAP	4%	653
EL-CFS-056-045	24	SEE MAP	4%	653
EL-CFS-056-046	24	SEE MAP	4%	653
EL-CFS-056-047	24	SEE MAP	4%	653
EL-CFS-056-048	24	SEE MAP	4%	653
EL-CFS-056-049	24	SEE MAP	4%	653
EL-CFS-056-050	24	SEE MAP	4%	653
EL-CFS-056-051	24	SEE MAP	3%	876
EL-CFS-056-052	24	SEE MAP	3%	876
EL-CFS-056-053	24	SEE MAP	3%	876
EL-CFS-056-054	24	SEE MAP	3%	876
EL-CFS-056-055	24	SEE MAP	3%	876
EL-CFS-056-056	24	SEE MAP	3%	567
EL-CFS-056-057	24	SEE MAP	3%	567
EL-CFS-056-058	24	SEE MAP	3%	567
EL-CFS-056-059	24	SEE MAP	4%	638
EL-CFS-056-060	24	SEE MAP	4%	638

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-056-061	24	SEE MAP	4%	638
EL-CFS-056-062	24	SEE MAP	4%	638
EL-CFS-056-063	24	SEE MAP	4%	638
EL-CFS-056-064	24	SEE MAP	4%	638
EL-CFS-056-065	24	SEE MAP	4%	574
EL-CFS-056-066	24	SEE MAP	4%	574
EL-CFS-056-067	12	SEE MAP	4%	253
EL-CFS-056-068	12	SEE MAP	4%	253
EL-CFS-056-069	12	SEE MAP	4%	253
EL-CFS-056-070	12	SEE MAP	4%	253
EL-CFS-056-071	12	SEE MAP	6%	180
EL-CFS-056-072	12	SEE MAP	6%	180
EL-CFS-056-073	12	SEE MAP	6%	180
EL-CFS-056-074	12	SEE MAP	6%	180
EL-CFS-056-075	12	SEE MAP	4%	226
EL-CFS-056-076	12	SEE MAP	4%	226
EL-CFS-056-077	12	SEE MAP	4%	226
EL-CFS-056-078	12	SEE MAP	4%	226
EL-CFS-056-079	12	SEE MAP	4%	226
EL-CFS-056-080	12	SEE MAP	4%	226
EL-CFS-056-081	12	SEE MAP	4%	226
EL-CFS-056-082	12	SEE MAP	4%	275
EL-CFS-056-083	12	SEE MAP	4%	275
EL-CFS-056-084	12	SEE MAP	5%	281
EL-CFS-056-085	12	SEE MAP	5%	281
EL-CFS-056-086	24	SEE MAP	5%	358

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-056-087	24	SEE MAP	5%	358
EL-CFS-056-088	24	SEE MAP	5%	358
EL-CFS-056-089	24	SEE MAP	5%	358
EL-CFS-057-001	24	SEE MAP	5%	380
EL-CFS-057-002	24	SEE MAP	5%	380
EL-CFS-057-003	24	SEE MAP	5%	380
EL-CFS-057-004	24	SEE MAP	5%	380
EL-CFS-057-005	24	SEE MAP	5%	380
EL-CFS-057-006	24	SEE MAP	4%	650
EL-CFS-057-007	24	SEE MAP	4%	650
EL-CFS-057-008	12	SEE MAP	2%	513
EL-CFS-057-009	12	SEE MAP	2%	513
EL-CFS-057-010	12	SEE MAP	2%	513
EL-CFS-057-011	12	SEE MAP	2%	513
EL-CFS-057-012	12	SEE MAP	2%	513
EL-CFS-057-013	12	SEE MAP	2%	513
EL-CFS-057-014	12	SEE MAP	4%	388
EL-CFS-057-015	12	SEE MAP	4%	388
EL-CFS-057-016	12	SEE MAP	4%	388
EL-CFS-057-017	12	SEE MAP	4%	388
EL-CFS-057-018	12	SEE MAP	4%	388
EL-CFS-057-019	12	SEE MAP	2%	447
EL-CFS-057-020	12	SEE MAP	2%	447
EL-CFS-057-021	12	SEE MAP	2%	447
EL-CFS-057-022	12	SEE MAP	2%	447
EL-CFS-057-023	12	SEE MAP	2%	447

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021




SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-057-050	12	SEE MAP	2%	313
EL-CFS-057-051	12	SEE MAP	2%	313
EL-CFS-057-052	12	SEE MAP	2%	313
EL-CFS-057-053	12	SEE MAP	2%	313
EL-CFS-057-054	12	SEE MAP	2%	313
EL-CFS-057-055	12	SEE MAP	2%	431
EL-CFS-057-056	12	SEE MAP	2%	431
EL-CFS-057-057	12	SEE MAP	2%	431
EL-CFS-057-058	12	SEE MAP	2%	431
EL-CFS-057-059	12	SEE MAP	2%	513
EL-CFS-057-060	12	SEE MAP	2%	513
EL-CFS-057-061	12	SEE MAP	2%	513
EL-CFS-057-062	12	SEE MAP	2%	513
EL-CFS-057-063	12	SEE MAP	4%	388
EL-CFS-057-064	12	SEE MAP	4%	388
EL-CFS-057-065	12	SEE MAP	4%	388
EL-CFS-057-066	12	SEE MAP	4%	388
EL-CFS-057-067	12	SEE MAP	4%	388
EL-CFS-057-068	12	SEE MAP	4%	388
EL-CFS-057-069	12	SEE MAP	4%	388
EL-CFS-057-070	12	SEE MAP	4%	388
EL-CFS-057-071	12	SEE MAP	3%	211
EL-CFS-057-072	12	SEE MAP	3%	211
EL-CFS-057-073	12	SEE MAP	3%	211
EL-CFS-057-074	12	SEE MAP	3%	211
EL-CFS-057-075	12	SEE MAP	3%	211

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: **Williams REAE - Effort Loop**
 LOCATION: **Ross, Chestnuthill, and Tunkhannock Townships**
Monroe County, Pennsylvania

PREPARED BY: **JB**
 CHECKED BY: **KCC**

DATE: **4/5/2021**
 DATE: **4/5/2021**



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-CFS-057-076	12	SEE MAP	3%	211
EL-CFS-057-077	12	SEE MAP	2%	447
EL-CFS-057-078	12	SEE MAP	2%	447
EL-CFS-057-079	12	SEE MAP	2%	447
EL-CFS-057-080	12	SEE MAP	2%	447
EL-CFS-057-081	12	SEE MAP	2%	264
EL-CFS-057-082	12	SEE MAP	1%	501
EL-CFS-057-083	12	SEE MAP	1%	501
EL-CFS-057-084	12	SEE MAP	1%	501
EL-CFS-057-085	12	SEE MAP	1%	501
EL-CFS-057-086	12	SEE MAP	1%	501
EL-CFS-057-087	12	SEE MAP	1%	501
EL-CFS-057-088	12	SEE MAP	1%	501
EL-CFS-057-089	12	SEE MAP	8%	12
EL-CFS-057-090	12	SEE MAP	4%	135
EL-CFS-057-091	12	SEE MAP	4%	135
EL-CFS-057-092	12	SEE MAP	4%	135
EL-MLV-CFS-001	24	See Map, MLV-505LD86	14%	221
EL-MLV-CFS-002	24	See Map, MLV-505LD86	14%	240
EL-MLV-CFS-003	24	See Map, MLV-505LD86	24%	153
EL-MLV-CFS-004	24	See Map, MLV-505LD86	24%	153
EL-MLV-CFS-005	24	See Map, MLV-505LD86	24%	153
EL-MLV-CFS-006	24	See Map, MLV-505LD86	24%	153
EL-MLV-CFS-007	24	See Map, MLV-505LD86	24%	153
EL-MLV-CFS-008	12	See Map, MLV-505LD86	19%	75
EL-MLV-CFS-009	12	See Map, MLV-505LD86	19%	75

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop

LOCATION: Ross, Chestnuthill, and Tunkhannock Townships


Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-MLV-CFS-010	12	See Map, MLV-505LD86	19%	75
EL-MLV-CFS-011	12	See Map, MLV-505LD86	19%	75
EL-MLV-CFS-012	32	See Map, MLV-505LD86	11%	393
EL-MLV-CFS-013	32	See Map, MLV-505LD86	11%	393
EL-MLV-CFS-014	32	See Map, MLV-505LD86	11%	393
EL-MLV-CFS-015	32	See Map, MLV-505LD86	11%	393
EL-MLV-CFS-016	32	See Map, MLV-505LD86	8%	391
EL-MLV-CFS-017	32	See Map, MLV-505LD86	8%	391
EL-MLV-CFS-018	24	See Map, MLV-505LD86	8%	290
EL-MLV-CFS-019	24	See Map, MLV-505LD86	8%	290
EL-MLV-CFS-020	24	See Map, MLV-505LD86	8%	290
EL-MLV-CFS-021	24	See Map, MLV-505LD86	8%	290
EL-MLV-CFS-022	24	See Map, MLV-505LD86	8%	290
EL-MLV-CFS-023	12	See Map, MLV-505LD86	5%	223
EL-MLV-CFS-024	12	See Map, MLV-505LD86	5%	223
EL-MLV-CFS-025	12	See Map, MLV-505LD86	5%	223
EL-MLV-CFS-026	12	See Map, MLV-505LD86	5%	223
EL-MLV-CFS-027	12	See Map, MLV-505LD86	5%	223
EL-MLV-CFS-028	18	See Map, MLV-505LD86	8%	236
EL-MLV-CFS-029	18	See Map, MLV-505LD86	8%	236
EL-MLV-CFS-030	18	See Map, MLV-505LD86	8%	236
EL-MLV-CFS-031	18	See Map, MLV-505LD86	8%	236
EL-MLV-CFS-032	18	See Map, MLV-505LD86	8%	236
EL-MLV-CFS-033	12	See Map, MLV-505LD86	5%	223
EL-MLV-CFS-034	12	See Map, MLV-505LD86	5%	223
EL-MLV-CFS-035	12	See Map, MLV-505LD86	9%	79

SEDIMENT SOCK WORKSHEET #1

PROJECT NAME: Williams REAE - Effort Loop


LOCATION: Ross, Chestnuthill, and Tunkhannock Townships
Monroe County, Pennsylvania

PREPARED BY: JB

DATE: 4/5/2021

CHECKED BY: KCC

DATE: 4/5/2021



SOCK No.	DIA (IN.)	LOCATION	SLOPE (%)	SLOPE LENGTH ABOVE BARRIER (FT)
EL-MLV-CFS-036	12	See Map, MLV-505LD86	9%	79
EL-MLV-CFS-037	12	See Map, MLV-505LD86	9%	79
EL-MLV-CFS-038	12	See Map, MLV-505LD86	8%	145
EL-MLV-CFS-039	12	See Map, MLV-505LD86	8%	145

ATTACHMENT 3.2
CN TABLE – EFFORT LOOP

Table 2-2a Runoff curve numbers for urban areas ^{1/}

Cover description	Average percent impervious area ^{2/}	Curve numbers for hydrologic soil group			
		A	B	C	D
<i>Fully developed urban areas (vegetation established)</i>					
Open space (lawns, parks, golf courses, cemeteries, etc.) ^{3/} :					
Poor condition (grass cover < 50%)		68	79	86	89
Fair condition (grass cover 50% to 75%)		49	69	79	84
Good condition (grass cover > 75%)		39	61	74	80
Impervious areas:					
Paved parking lots, roofs, driveways, etc. (excluding right-of-way)		98	98	98	98
Streets and roads:					
Paved; curbs and storm sewers (excluding right-of-way)		98	98	98	98
Paved; open ditches (including right-of-way)		83	89	92	93
Gravel (including right-of-way)		76	85	89	91
Dirt (including right-of-way)		72	82	87	89
Western desert urban areas:					
Natural desert landscaping (pervious areas only) ^{4/}		63	77	85	88
Artificial desert landscaping (impervious weedbarrier, desert shrub with 1- to 2-inch sand or gravel mulch and basin borders)		96	96	96	96
Urban districts:					
Commercial and business	85	89	92	94	95
Industrial	72	81	88	91	93
Residential districts by average lot size:					
1/8 acre or less (town houses)	65	77	85	90	92
1/4 acre	38	61	75	83	87
1/3 acre	30	57	72	81	86
1/2 acre	25	54	70	80	85
1 acre	20	51	68	79	84
2 acres	12	46	65	77	82
<i>Developing urban areas</i>					
Newly graded areas (pervious areas only, no vegetation) ^{5/}		77	86	91	94
Idle lands (CN's are determined using cover types similar to those in table 2-2c).					

¹ Average runoff condition, and $I_a = 0.2S$.² The average percent impervious area shown was used to develop the composite CN's. Other assumptions are as follows: impervious areas are directly connected to the drainage system, impervious areas have a CN of 98, and pervious areas are considered equivalent to open space in good hydrologic condition. CN's for other combinations of conditions may be computed using figure 2-3 or 2-4.³ CN's shown are equivalent to those of pasture. Composite CN's may be computed for other combinations of open space cover type.⁴ Composite CN's for natural desert landscaping should be computed using figures 2-3 or 2-4 based on the impervious area percentage (CN = 98) and the pervious area CN. The pervious area CN's are assumed equivalent to desert shrub in poor hydrologic condition.⁵ Composite CN's to use for the design of temporary measures during grading and construction should be computed using figure 2-3 or 2-4 based on the degree of development (impervious area percentage) and the CN's for the newly graded pervious areas.

Table 2-2b Runoff curve numbers for cultivated agricultural lands ^{1/}

Cover description			Curve numbers for hydrologic soil group			
Cover type	Treatment ^{2/}	Hydrologic condition ^{3/}	A	B	C	D
Fallow	Bare soil	—	77	86	91	94
	Crop residue cover (CR)	Poor	76	85	90	93
		Good	74	83	88	90
Row crops	Straight row (SR)	Poor	72	81	88	91
		Good	67	78	85	89
	SR + CR	Poor	71	80	87	90
		Good	64	75	82	85
	Contoured (C)	Poor	70	79	84	88
		Good	65	75	82	86
	C + CR	Poor	69	78	83	87
		Good	64	74	81	85
	Contoured & terraced (C&T)	Poor	66	74	80	82
		Good	62	71	78	81
C&T+ CR		Poor	65	73	79	81
	Good	61	70	77	80	
Small grain	SR	Poor	65	76	84	88
		Good	63	75	83	87
	SR + CR	Poor	64	75	83	86
		Good	60	72	80	84
	C	Poor	63	74	82	85
		Good	61	73	81	84
	C + CR	Poor	62	73	81	84
		Good	60	72	80	83
	C&T	Poor	61	72	79	82
		Good	59	70	78	81
C&T+ CR	Poor	60	71	78	81	
	Good	58	69	77	80	
Close-seeded or broadcast legumes or rotation meadow	SR	Poor	66	77	85	89
		Good	58	72	81	85
	C	Poor	64	75	83	85
		Good	55	69	78	83
	C&T	Poor	63	73	80	83
		Good	51	67	76	80

^{1/} Average runoff condition, and $I_a=0.2S$

^{2/} Crop residue cover applies only if residue is on at least 5% of the surface throughout the year.

^{3/} Hydraulic condition is based on combination factors that affect infiltration and runoff, including (a) density and canopy of vegetative areas, (b) amount of year-round cover, (c) amount of grass or close-seeded legumes, (d) percent of residue cover on the land surface (good $\geq 20\%$), and (e) degree of surface roughness.

Poor: Factors impair infiltration and tend to increase runoff.

Good: Factors encourage average and better than average infiltration and tend to decrease runoff.

Table 2-2c Runoff curve numbers for other agricultural lands ^{1/}

Cover description	Hydrologic condition	Curve numbers for hydrologic soil group			
		A	B	C	D
Pasture, grassland, or range—continuous forage for grazing. ^{2/}	Poor	68	79	86	89
	Fair	49	69	79	84
	Good	39	61	74	80
Meadow—continuous grass, protected from grazing and generally mowed for hay.	—	30	58	71	78
Brush—brush-weed-grass mixture with brush the major element. ^{3/}	Poor	48	67	77	83
	Fair	35	56	70	77
	Good	30 ^{4/}	48	65	73
Woods—grass combination (orchard or tree farm). ^{5/}	Poor	57	73	82	86
	Fair	43	65	76	82
	Good	32	58	72	79
Woods. ^{6/}	Poor	45	66	77	83
	Fair	36	60	73	79
	Good	30 ^{4/}	55	70	77
Farmsteads—buildings, lanes, driveways, and surrounding lots.	—	59	74	82	86

^{1/} Average runoff condition, and $I_a = 0.2S$.

^{2/} *Poor*: <50% ground cover or heavily grazed with no mulch.

Fair: 50 to 75% ground cover and not heavily grazed.

Good: > 75% ground cover and lightly or only occasionally grazed.

^{3/} *Poor*: <50% ground cover.

Fair: 50 to 75% ground cover.

Good: >75% ground cover.

^{4/} Actual curve number is less than 30; use CN = 30 for runoff computations.

^{5/} CN's shown were computed for areas with 50% woods and 50% grass (pasture) cover. Other combinations of conditions may be computed from the CN's for woods and pasture.

^{6/} *Poor*: Forest litter, small trees, and brush are destroyed by heavy grazing or regular burning.

Fair: Woods are grazed but not burned, and some forest litter covers the soil.

Good: Woods are protected from grazing, and litter and brush adequately cover the soil.

Table 2-2d Runoff curve numbers for arid and semiarid rangelands ^{1/}

Cover description	Hydrologic condition ^{2/}	Curve numbers for hydrologic soil group			
		A ^{3/}	B	C	D
Herbaceous—mixture of grass, weeds, and low-growing brush, with brush the minor element.	Poor		80	87	93
	Fair		71	81	89
	Good		62	74	85
Oak-aspen—mountain brush mixture of oak brush, aspen, mountain mahogany, bitter brush, maple, and other brush.	Poor		66	74	79
	Fair		48	57	63
	Good		30	41	48
Pinyon-juniper—pinyon, juniper, or both; grass understory.	Poor		75	85	89
	Fair		58	73	80
	Good		41	61	71
Sagebrush with grass understory.	Poor		67	80	85
	Fair		51	63	70
	Good		35	47	55
Desert shrub—major plants include saltbush, greasewood, creosotebush, blackbrush, bursage, palo verde, mesquite, and cactus.	Poor	63	77	85	88
	Fair	55	72	81	86
	Good	49	68	79	84

¹ Average runoff condition, and I_a , = 0.2S. For range in humid regions, use table 2-2c.

² Poor: <30% ground cover (litter, grass, and brush overstory).

Fair: 30 to 70% ground cover.

Good: > 70% ground cover.

³ Curve numbers for group A have been developed only for desert shrub.

ATTACHMENT 3.3
CHANNEL DESIGN WORKSHEETS –
EFFORT LOOP

STANDARD E&S WORKSHEET # 11

Channel Design Data

PROJECT NAME: Williams REAE – Effort Loop

LOCATION: Monroe County, PA

PREPARED BY: CD

DATE: 03/22/2021

CHECKED BY: KCC

DATE: 03/22/2021

CHANNEL OR CHANNEL SECTION	DC-EL-001	DC-EL-001	DC-EL-002	DC-EL-002	DC-EL-003
TEMPORARY OR PERMANENT? (T OR P)	T	T	T	T	T
DESIGN STORM (2, 5, OR 10 YR)	2 YR	2 YR	2 YR	2 YR	2 YR
ACRES (AC)	31.2	31.2	11.44	11.44	1.42
MULTIPLIER (1.6, 2.25, or 2.75) ¹	N/A	N/A	N/A	N/A	N/A
Q _r (REQUIRED CAPACITY) (CFS)	14.06	14.06	2.64	2.64	3.51
Q (CALCULATED AT FLOW DEPTH d) (CFS)	14.06	14.09	2.65	2.65	3.54
PROTECTIVE LINING ²	SC150BN	Vegetated	SC150BN	Vegetated	SC150BN
n (MANNING'S COEFFICIENT) ²	0.038	0.066	0.047	0.080	0.050
V _a (ALLOWABLE VELOCITY) (FPS)	8.0	15.0	8.0	15.0	8.0
V (CALCULATED AT FLOW DEPTH d) (FPS)	3.0	2.0	1.6	1.1	1.8
T _a (MAX ALLOWABLE SHEAR STRESS) (LB/FT ²)	2.1	8.0	2.1	8.0	2.1
T _d (CALC'D SHEAR STRESS AT FLOW DEPTH d) (LB/FT ²)	0.7	0.9	0.3	0.4	0.5
CHANNEL BOTTOM WIDTH (FT)	2	2	2	2	2
CHANNEL SIDE SLOPES (H:V)	2	2	2	2	2
D (TOTAL DEPTH) (FT)	1.75	2.00	1.25	1.25	1.00
CHANNEL TOP WIDTH @ D (FT)	9.00	10.00	7.00	7.00	6.00
d (CALCULATED FLOW DEPTH) (FT)	1.11	1.44	0.56	0.70	0.43
CHANNEL TOP WIDTH @ FLOW DEPTH d (FT)	6.44	7.76	4.12	4.80	3.72
BOTTOM WIDTH: FLOW DEPTH RATIO (12:1 MAX)	1.80	1.39	3.77	2.86	4.65
d ₅₀ STONE SIZE (IN)	-	-	-	-	-
A (CROSS-SECTIONAL AREA) (SQ. FT.)	4.684	7.027	1.622	2.380	1.230
R (HYDRAULIC RADIUS) (FT)	0.673	0.833	0.371	0.464	0.313
S (BED SLOPE) ³ (FT/FT)	0.010	0.010	0.010	0.010	0.044
S _c (CRITICAL SLOPE) (FT/FT)	0.026	0.072	0.047	0.129	0.056
.7S _c (FT/FT)	0.018	0.051	0.033	0.090	0.040
1.3S _c (FT/FT)	0.034	0.094	0.062	0.167	0.073
STABLE FLOW? (Y/N)	Y	Y	Y	Y	N
FREEBOARD BASED ON UNSTABLE FLOW (FT)	-	-	-	-	0.09
FREEBOARD BASED ON STABLE FLOW (FT)	0.3	0.4	0.1	0.2	-
MINIMUM REQUIRED FREEBOARD ⁴ (FT)	0.5	0.5	0.5	0.5	0.5
DESIGN METHOD FOR PROTECTIVE LINING ⁵ PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)	V	V	V	V	V

1. Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For Rational Method, enter "N/A" and attach E&S Worksheets 9 and 10. For TR-55 enter "N/A" and attach appropriate Worksheets.
2. Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns.
3. Slopes may not be averaged.
4. Minimum Freeboard is 0.5 ft. or ¼ Total Channel Depth, whichever is greater
5. Permissible velocity lining design method is not acceptable for channels with a bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.

CHANNEL OR CHANNEL SECTION	DC-EL-003	DC-EL-004	DC-EL-004	DC-EL-005	DC-EL-005
TEMPORARY OR PERMANENT? (T OR P)	T	T	T	T	T
DESIGN STORM (2, 5, OR 10 YR)	2 YR	2 YR	2 YR	2 YR	2 YR
ACRES (AC)	1.42	4.75	4.75	10.97	10.97
MULTIPLIER (1.6, 2.25, or 2.75) ¹	N/A	N/A	N/A	N/A	N/A
Q _r (REQUIRED CAPACITY) (CFS)	3.51	6.04	6.04	3.41	3.41
Q (CALCULATED AT FLOW DEPTH d) (CFS)	3.54	6.06	6.06	3.54	3.54
PROTECTIVE LINING ²	Vegetated	SC150BN	Vegetated	SC150BN	Vegetated
n (MANNING'S COEFFICIENT) ²	0.050	0.045	0.045	0.050	0.050
V _a (ALLOWABLE VELOCITY) (FPS)	8.0	8.0	15.0	8.0	15.0
V (CALCULATED AT FLOW DEPTH d) (FPS)	1.8	3.7	3.7	2.9	2.9
T _a (MAX ALLOWABLE SHEAR STRESS) (LB/FT ²)	2.1	2.1	8.0	2.1	8.0
T _d (CALC'D SHEAR STRESS AT FLOW DEPTH d) (LB/FT ²)	0.5	1.6	1.6	1.2	1.2
CHANNEL BOTTOM WIDTH (FT)	2	2	2	2	2
CHANNEL SIDE SLOPES (H:V)	2	2	2	2	2
D (TOTAL DEPTH) (FT)	1.00	1.25	1.25	1.00	1.00
CHANNEL TOP WIDTH @ D (FT)	6.00	7.00	7.00	6.00	6.00
d (CALCULATED FLOW DEPTH) (FT)	0.43	0.53	0.53	0.43	0.43
CHANNEL TOP WIDTH @ FLOW DEPTH d (FT)	3.72	4.12	4.12	3.72	3.72
BOTTOM WIDTH: FLOW DEPTH RATIO (12:1 MAX)	4.65	3.77	3.77	4.65	4.65
d ₅₀ STONE SIZE (IN)	-	-	-	-	-
A (CROSS-SECTIONAL AREA) (SQ. FT.)	1.230	1.622	1.622	1.230	1.230
R (HYDRAULIC RADIUS) (FT)	0.313	0.371	0.371	0.313	0.313
S (BED SLOPE) ³ (FT/FT)	0.044	0.048	0.048	0.044	0.044
S _c (CRITICAL SLOPE) (FT/FT)	0.056	0.044	0.044	0.056	0.056
.7S _c (FT/FT)	0.040	0.030	0.030	0.040	0.040
1.3S _c (FT/FT)	0.073	0.057	0.057	0.073	0.073
STABLE FLOW? (Y/N)	N	N	N	N	N
FREEBOARD BASED ON UNSTABLE FLOW (FT)	0.09	0.15	0.15	0.09	0.09
FREEBOARD BASED ON STABLE FLOW (FT)	-	-	-	-	-
MINIMUM REQUIRED FREEBOARD ⁴ (FT)	0.5	0.5	0.5	0.5	0.5
DESIGN METHOD FOR PROTECTIVE LINING ⁵ PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)	V	V	V	V	V

1. Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For Rational Method, enter "N/A" and attach E&S Worksheets 9 and 10. For TR-55 enter "N/A" and attach appropriate Worksheets.
2. Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns.
3. Slopes may not be averaged.
4. Minimum Freeboard is 0.5 ft. or ¼ Total Channel Depth, whichever is greater
5. Permissible velocity lining design method is not acceptable for channels with a bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.

CHANNEL OR CHANNEL SECTION	DC-EL-006	DC-EL-006	DC-EL-007	DC-EL-007	DC-EL-008
TEMPORARY OR PERMANENT? (T OR P)	T	T	T	T	T
DESIGN STORM (2, 5, OR 10 YR)	2 YR	2 YR	2 YR	2 YR	2 YR
ACRES (AC)	7.49	7.49	0.35	0.35	15.85
MULTIPLIER (1.6, 2.25, or 2.75) ¹	N/A	N/A	N/A	N/A	N/A
Q _r (REQUIRED CAPACITY) (CFS)	6.42	6.42	0.83	0.83	5.31
Q (CALCULATED AT FLOW DEPTH d) (CFS)	6.55	6.42	0.90	0.87	5.35
PROTECTIVE LINING ²	SC150BN	Vegetated	SC150BN	Vegetated	SC150BN
n (MANNING'S COEFFICIENT) ²	0.039	0.070	0.050	0.057	0.050
V _a (ALLOWABLE VELOCITY) (FPS)	8.0	15.0	8.0	15.0	8.0
V (CALCULATED AT FLOW DEPTH d) (FPS)	2.4	1.6	2.1	1.9	3.8
T _a (MAX ALLOWABLE SHEAR STRESS) (LB/FT ²)	2.1	8.0	2.1	8.0	2.1
T _d (CALC'D SHEAR STRESS AT FLOW DEPTH d) (LB/FT ²)	0.5	0.6	0.7	0.7	2.0
CHANNEL BOTTOM WIDTH (FT)	2	2	2	2	2
CHANNEL SIDE SLOPES (H:V)	2	2	2	2	2
D (TOTAL DEPTH) (FT)	1.50	1.75	0.75	0.75	1.00
CHANNEL TOP WIDTH @ D (FT)	8.00	9.00	5.00	5.00	6.00
d (CALCULATED FLOW DEPTH) (FT)	0.77	1.02	0.18	0.19	0.48
CHANNEL TOP WIDTH @ FLOW DEPTH d (FT)	5.08	6.08	2.72	2.76	3.92
BOTTOM WIDTH: FLOW DEPTH RATIO (12:1 MAX)	2.60	1.96	11.11	10.53	4.17
d ₅₀ STONE SIZE (IN)	-	-	-	-	-
A (CROSS-SECTIONAL AREA) (SQ. FT.)	2.726	4.121	0.425	0.452	1.421
R (HYDRAULIC RADIUS) (FT)	0.501	0.628	0.151	0.159	0.343
S (BED SLOPE) ³ (FT/FT)	0.010	0.010	0.063	0.063	0.067
S _c (CRITICAL SLOPE) (FT/FT)	0.030	0.090	0.070	0.090	0.055
.7S _c (FT/FT)	0.021	0.063	0.049	0.063	0.039
1.3S _c (FT/FT)	0.039	0.117	0.091	0.117	0.072
STABLE FLOW? (Y/N)	Y	Y	N	Y	N
FREEBOARD BASED ON UNSTABLE FLOW (FT)	-	-	0.03	-	0.14
FREEBOARD BASED ON STABLE FLOW (FT)	0.2	0.3	-	0.05	-
MINIMUM REQUIRED FREEBOARD ⁴ (FT)	0.5	0.5	0.5	0.5	0.5
DESIGN METHOD FOR PROTECTIVE LINING ⁵ PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)	V	V	V	V	V

1. Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For Rational Method, enter "N/A" and attach E&S Worksheets 9 and 10. For TR-55 enter "N/A" and attach appropriate Worksheets.
2. Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns.
3. Slopes may not be averaged.
4. Minimum Freeboard is 0.5 ft. or ¼ Total Channel Depth, whichever is greater
5. Permissible velocity lining design method is not acceptable for channels with a bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.

CHANNEL OR CHANNEL SECTION		DC-EL-008	DC-EL-009	DC-EL-009		
TEMPORARY OR PERMANENT? (T OR P)		T	T	T		
DESIGN STORM (2, 5, OR 10 YR)		2 YR	2 YR	2 YR		
ACRES (AC)		15.85	17.15	17.15		
MULTIPLIER (1.6, 2.25, or 2.75) ¹		N/A	N/A	N/A		
Q _r (REQUIRED CAPACITY) (CFS)		5.31	1.13	1.13		
Q (CALCULATED AT FLOW DEPTH d) (CFS)		5.32	1.18	1.19		
PROTECTIVE LINING ²		Vegetated	SC150BN	Vegetated		
n (MANNING'S COEFFICIENT) ²		0.041	0.050	0.058		
V _a (ALLOWABLE VELOCITY) (FPS)		15.0	8.0	15.0		
V (CALCULATED AT FLOW DEPTH d) (FPS)		4.3	2.3	2.1		
T _a (MAX ALLOWABLE SHEAR STRESS) (LB/FT ²)		8.0	2.1	8.0		
T _d (CALC'D SHEAR STRESS AT FLOW DEPTH d) (LB/FT ²)		1.8	0.8	0.9		
CHANNEL BOTTOM WIDTH (FT)		2	2	2		
CHANNEL SIDE SLOPES (H:V)		2	2	2		
D (TOTAL DEPTH) (FT)		1.00	0.75	0.75		
CHANNEL TOP WIDTH @ D (FT)		6.00	5.00	5.00		
d (CALCULATED FLOW DEPTH) (FT)		0.43	0.21	0.23		
CHANNEL TOP WIDTH @ FLOW DEPTH d (FT)		3.72	2.84	2.92		
BOTTOM WIDTH: FLOW DEPTH RATIO (12:1 MAX)		4.65	9.52	8.70		
d ₅₀ STONE SIZE (IN)		-	-	-		
A (CROSS-SECTIONAL AREA) (SQ. FT.)		1.230	0.508	0.566		
R (HYDRAULIC RADIUS) (FT)		0.313	0.173	0.187		
S (BED SLOPE) ³ (FT/FT)		0.067	0.063	0.063		
S _c (CRITICAL SLOPE) (FT/FT)		0.038	0.068	0.089		
.7S _c (FT/FT)		0.027	0.047	0.062		
1.3S _c (FT/FT)		0.049	0.088	0.115		
STABLE FLOW? (Y/N)		Y	N	N		
FREEBOARD BASED ON UNSTABLE FLOW (FT)		-	0.04	0.04		
FREEBOARD BASED ON STABLE FLOW (FT)		0.1	-	-		
MINIMUM REQUIRED FREEBOARD ⁴ (FT)		0.5	0.5	0.5		
DESIGN METHOD FOR PROTECTIVE LINING ⁵ PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)		V	V	V		

1. Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For Rational Method, enter "N/A" and attach E&S Worksheets 9 and 10. For TR-55 enter "N/A" and attach appropriate Worksheets.
2. Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns.
3. Slopes may not be averaged.
4. Minimum Freeboard is 0.5 ft. or ¼ Total Channel Depth, whichever is greater
5. Permissible velocity lining design method is not acceptable for channels with a bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.

STANDARD E&S WORKSHEET # 9

Time of Concentration

PROJECT NAME: Williams REAE- Effort Loop Pipeline

LOCATION: Monroe County, PA

PREPARED BY: JB

DATE: 03/19/2021

CHECKED BY: KCC

DATE: 03/19/2021

OVERLAND FLOW:

Path Number	Length (ft)	"n" Value	Average Slope (ft/ft)	Time (min)
DC-EL-1	100	0.15	0.04	7.4
DC-EL-2	100	0.4	0.02	21.3
DC-EL-3	100	0.05	0.04	3.1
DC-EL-4	100	0.15	0.02	9.7
DC-EL-5	100	0.4	0.04	16.2
DC-EL-6	100	0.05	0.05	2.8
DC-EL-7	100	0.4	0.05	14.7
DC-EL-8	100	0.4	0.06	13.7
DC-EL-9	100	0.4	0.03	18.1

$$T_{c (sheet\ flow)} = \left[\frac{2.48 (n)}{3.6^{0.5}} \right]^{0.4673}$$

n _____ **Type of Cover**
0.02 smooth pavement
0.1 bare parched soil
0.3 poor grass cover
0.4 average grass cover
0.8 dense grass cover
(L = 150' maximum)

SHALLOW CONCENTRATED FLOW:

Path Number	Length (ft)	Type of Cover	Average Slope (ft/ft)	Velocity (ft/sec)	Time (min)
DC-EL-1	571	Pasture	0.0315	7	7.7
	1,272	Woodland	0.0306	5	24.2
DC-EL-2	1,806	Woodland	0.026	5	37.3
DC-EL-3	157	Nearly Bare & Untilled	0.096	10	0.8
DC-EL-4	199	Pasture	0.04	7	2.4
	202	Pasture	0.089	7	1.6
	70	Pasture	0.243	7	0.3
	371	Woodland	0.102	5	3.9
DC-EL-5	390	Woodland	0.069	5	4.9
	193	Woodland	0.166	5	1.6
	407	Woodland	0.079	5	4.8
	165	Woodland	0.152	5	1.4
	371	Woodland	0.102	5	3.9
DC-EL-6	423	Nearly Bare & Untilled	0.05	10	3.2
DC-EL-7	564	Woodland	0.03	5	10.9
	117	Woodland	0.094	5	1.3
DC-EL-8	458	Woodland	0.057	5	6.4
	782	Woodland	0.063	5	10.4
DC-EL-9	353	Woodland	0.04	5	5.9
	861	Woodland	0.084	5	9.9
	241	Woodland	0.166	5	2.0
	246	Woodland	0.077	5	3.0

CHANNEL FLOW:

Path Number	Length (ft)	Flow Area (sq. ft.)	Average Slope (ft/ft)	Wetted Perimeter (ft)	Hydraulic Radius (ft)	Manning's "n"	Velocity (ft/sec)	Channel Time (min)	Tc (min)
DC-EL-1	37	4.7	0.01	7.0	0.673	0.038	3	0.2	39.5
DC-EL-2	19	1.6	0.01	4.4	0.371	0.047	1.6	0.2	58.8
DC-EL-3	362	1.2	0.044	3.9	0.313	0.05	2.9	2.1	6
DC-EL-4	42	1.6	0.048	4.4	0.371	0.045	3.7	0.2	18.1
DC-EL-5	45	1.21	0.044	3.9	0.313	0.05	2.9	0.3	33.1
DC-EL-6	782	2.7	0.01	5.4	0.501	0.039	2.4	5.4	11.4
DC-EL-7	111	0.4	0.063	2.8	0.151	0.05	2.1	0.9	27.8
DC-EL-8	30	1.4	0.067	4.1	0.343	0.05	3.8	0.1	30.6
DC-EL-9	32	0.5	0.063	2.9	0.173	0.05	2.3	0.2	39.1

CHANNEL DIMENSIONS:

Path Number	Bottom Width (ft)	Left Side Slope (H:V)	Right Side Slope (H:V)	Total Depth (ft)	Top Width (ft)
DC-EL-1	2	2	2	1.75	9
DC-EL-2	2	2	2	1.25	7
DC-EL-3	2	2	2	1.00	6
DC-EL-4	2	2	2	1.25	7
DC-EL-5	2	2	2	1.00	6
DC-EL-6	2	2	2	1.50	8
DC-EL-7	2	2	2	0.75	5
DC-EL-8	2	2	2	1.00	6
DC-EL-9	2	2	2	0.75	5

ATTACHMENT 3.4
LEVEL SPREADER DESIGN WORKSHEET

Williams REAE - Effort Loop
 LEVEL SPREADER DESIGN FOR CLEAN WATER CROSSINGS

Clean Water Crossing I.D.	NUMBER OF SLOPE PIPES	SLOPE PIPE DIAMETER (IN)	FLOW, Q (CFS)	STATIC HEAD (FT)	MAJOR LOSSES (DUE TO FRICTION) AND MINOR LOSSES	EFFECTIVE HEAD (FT)	LEVEL SPREADER PIPE DIAMETER (IN)	PERFORATION DIAMETER (IN)	NUMBER OF PERFORATIONS PER LINEAR FOOT OF PIPE	ORIFICE AREA (FT ²)	ORIFICE COEFFICIENT (C _d)	Q ₀ (PERFORATION FLOW RATE, CFS)	Q _L , DISCHARGE PER LINEAR FOOT (CFS/FT)	REQUIRED LENGTH (FT)	ACTUAL LENGTH (FT)	OVERALL LEVEL SPREADER CAPACITY (CFS)
CWC-EL-2	1	12	3.22	18	0.366	17.634	12	0.375	24	7.7E-04	0.60	0.0155	0.372	8.7	10	3.7

The Hazen-Williams formula was used to determine friction loss in the piping system under various flow conditions.

Hazen-Williams Formula:

$$f = 0.2083 \left(\frac{100 \cdot G}{C} \right)^{1.852} (1/d)^{4.8655}$$

C = Constant for inside roughness of pipe (Use C = 60)

f = Friction head in feet of water per 100 feet.

L₁ = ft

d = Inside diameter of pipe in inches.

L₂ = ft

G = Flow in gallons per minute


Flow GPM	C Roughness Coefficient	d Inside Pipe Diameter	Constant	(100G)/C ^{1.852}	(1/d) ^{4.8655}	f Friction Loss per 100 ft	Pipe Length Ft	Length 100 ft	Minor Losses Equivalent Length 100 ft	Total Length 100 ft	Friction Loss ft	
CWC-EL-2	1445.2	140	12	0.2083	381574.82	5.6136E-06	0.4462	15.0000	0.15	0.6700	0.8200	0.366

ATTACHMENT 3.5
SEDIMENT TRAP WORKSHEET

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #1
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1096	0	0	0	0
1096.5	531.02	531.02	132.76	132.76
1097	642.48	1173.50	454.00	586.75
1097.5	667.87	1841.37	794.28	1381.03
1098	706.72	2548.09	1167.06	2548.09
1098.5	647.68	3195.77	1446.62	3994.71
1099	727.78	3923.55	1890.61	5885.33




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
59944.44	1.38	2752.65

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #2
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1094	0	0	0	0
1094.5	867.50	867.50	216.88	216.88
1095	942.02	1809.52	687.89	904.76
1095.5	915.10	2724.62	1138.71	2043.47
1096	837.39	3562.01	1518.55	3562.01
1096.5	1191.61	4753.62	2380.02	5942.03
1097	1179.18	5932.80	2957.18	8899.20




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
127145.53	2.92	5838.52

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #3
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1090	0	0	0	0
1090.5	658.29	658.29	164.57	164.57
1091	713.18	1371.47	521.16	685.74
1091.5	557.90	1929.37	761.29	1447.03
1092	521.16	2450.53	1003.50	2450.53
1092.5	890.19	3340.72	1725.37	4175.90
1093	777.25	4117.97	2001.06	6176.96
1093.5	739.18	4857.15	2323.06	8500.01
1094	624.64	5481.79	2463.57	10963.58




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
152390.39	3.50	6997.77

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME REAE- Effort Loop
 LOCATION: CY- Sediment Trap #4
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1084	0	0	0	0
1084.5	583.02	583.02	145.76	145.76
1085	733.64	1316.66	512.58	658.33
1085.5	696.64	2013.30	851.65	1509.98
1086	746.13	2759.43	1249.46	2759.43
1086.5	482.60	3242.03	1293.11	4052.54
1087	528.72	3770.75	1603.59	5656.13
1087.5	571.74	4342.49	1943.23	7599.36
1088	517.07	4859.56	2119.76	9719.12




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
149853.42	3.44	6881.27

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #5
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1084	0	0	0	0
1084.5	203.16	203.16	50.79	50.79
1085	288.31	491.47	194.95	245.74
1085.5	325.94	817.41	367.32	613.06
1086	421.33	1238.74	625.68	1238.74
1086.5	297.10	1535.84	681.06	1919.80
1087	329.90	1865.74	878.81	2798.61
1087.5	342.46	2208.20	1065.74	3864.35
1088	329.78	2537.98	1211.61	5075.96
1088.5	390.80	2928.78	1513.80	6589.76
1089	301.29	3230.07	1485.42	8075.18




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
141263.55	3.24	6486.82

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #6
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1084	0	0	0	0
1084.5	403.35	403.35	100.84	100.84
1085	429.14	832.49	315.41	416.25
1085.5	544.85	1377.34	616.76	1033.01
1086	527.80	1905.14	872.14	1905.14
1086.5	532.04	2437.18	1141.34	3046.48
1087	545.93	2983.11	1428.19	4474.67
1087.5	593.72	3576.83	1784.79	6259.45
1088	581.95	4158.78	2058.11	8317.56
1088.5	506.77	4262.20	1272.39	9589.95
1089	564.18	4397.24	1403.15	10993.10




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
191014.33	4.39	8771.38

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #7
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1088	0	0	0	0
1088.5	506.94	506.94	126.74	126.74
1089	519.59	1026.53	386.53	513.27
1089.5	473.60	1500.13	611.83	1125.10
1090	430.92	1931.05	805.95	1931.05
1090.5	618.21	2549.26	1255.53	3186.58
1091	622.29	3171.55	1570.75	4757.33
1091.5	610.83	3782.38	1861.84	6619.17
1092	613.73	4396.11	2173.06	8792.22




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
128337.23	2.95	5893.25

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #8
 PREPARED BY: JB DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1092	0	0	0	0
1092.5	661.85	661.85	165.46	165.46
1093	611.48	1273.33	471.20	636.67
1093.5	701.15	1974.48	844.20	1480.86
1094	693.13	2667.61	1186.75	2667.61
1094.5	619.66	3287.27	1441.48	4109.09
1095	647.04	3934.31	1792.38	5901.47
1095.5	734.35	4668.66	2268.69	8170.16




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
108541.62	2.49	4984.23

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #9
 PREPARED BY: CJE DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1113	0	0	0	0
1113.25	2963.50	2963.50	370.44	370.44
1113.5	2963.50	5927.00	1111.31	1481.75
1113.75	2963.50	8890.50	1852.19	3333.94
1114	2963.50	11854	2593.06	5927.00
1114.25	2275.50	14129.5	2903.94	8830.94
1114.5	2275.50	13441.5	1250.19	10081.13
1114.75	2275.50	12753.5	1078.19	11159.31
1115	2275.50	12065.5	906.19	12065.50
1115.25	2844.38	11946.375	1374.17	13439.67




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
158122.80	3.63	7260.00

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #10
 PREPARED BY: CJE DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1114	0	0	0	0
1114.25	397.40	397.40	49.68	49.68
1114.5	397.40	794.80	149.03	198.70
1114.75	397.40	1192.20	248.38	447.08
1115	397.40	1589.6	347.73	794.80
1115.25	442.13	2031.73	475.03	1269.83
1115.5	442.13	2473.86	585.56	1855.40
1115.75	442.13	2518.59	348.37	2203.77
1116	442.13	2563.32	359.55	2563.32
1116.25	552.66	2718.5825	495.09	3058.41
1116.5	596.10	2917.2825	588.20	3646.60




Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
59241.60	1.36	2720.00

STANDARD E&S WORKSHEET # 14
Sediment Basin/Sediment Trap Storage Data

PROJECT NAME: REAE- Effort Loop
 LOCATION: CY- Sediment Trap #11
 PREPARED BY: CJE DATE: 3/2021
 CHECKED BY: KCC DATE: 3/2021

Water Surface Elevation ft	Area per Interval sq ft	Total Area sq ft	Incremental Storage Volume cubic ft	Total Storage Volume cubic ft
1116	0	0	0	0
1116.25	98.38	393.50	49.19	49.19
1116.5	393.50	787.00	147.56	196.75
1116.75	393.50	1180.50	245.94	442.69
1117	393.50	1574	344.31	787.00
1117.25	393.50	1967.5	442.69	1229.69
1117.5	393.50	2361	541.06	1770.75
1117.75	393.50	2754.5	639.44	2410.19
1118	759.50	3514	1103.81	3514.00
1118.25	878.50	4392.5	1427.56	4941.56
1118.5	878.50	5271.00	1647.19	6588.75



Area (sq ft)	Area (ac)	Required Volume Capacity (2,000 CF/AC)
54450.00	1.25	2500.00

ATTACHMENT 3.6
CHANNEL DESIGN WORKSHEET –
MLV-505LD86

STANDARD WORKSHEET
Channel Design Data

PROJECT NAME: Williams REAE - MLV-505LD86

LOCATION: Monroe County, PA

PREPARED BY: CWH

Date: 4/6/2021

CHECKED BY: KCC

Date: 4/6/2021

CHANNEL OR CHANNEL SECTION		SH-CC-001		SH-CC-002	
		Vegetated	Unvegetated	Vegetated	Unvegetated
TEMPORARY OR PERMANENT	(T OR P)	P	T	P	T
DESIGN STORM	(YR)	10	10	10	10
DRAINAGE AREA	(Acres)	3.91	3.91	0.22	0.22
1 MULTIPLIER (Qr)					
Qr (REQUIRED CAPACITY)	(CFS)	0.21	0.21	1.18	1.18
Q (CALCULATED AT FLOW DEPTH d)	(CFS)	0.21	0.22	1.18	1.18
2 PROTECTIVE LINING		Grass	SC150BN	Grass	SC150BN
VEGETATIVE LINING RETARDANCE		C	C	C	C
RIPRAP GRADATION		N/A	N/A	N/A	N/A
2 n (MANNING'S COEFFICIENT)		0.108	0.050	0.074	0.050
Va (ALLOWABLE VELOCITY)	(FPS)	5.0	8.0	5.0	8.0
V (CALCULATED AT FLOW DEPTH d)	(FPS)	0.47	0.82	1.17	1.54
ta (MAX ALLOWABLE SHEER STRESS)	(LB/FT ²)	1.00	2.10	1.00	2.10
7 td (CALCULATED AT FLOW DEPTH d)	(LB/FT ²)	X	X	X	X
CHANNEL TYPE		Trapez.	Trapez.	Trapez.	Trapez.
CHANNEL BOTTOM WIDTH	(FT)	1	1	2	2
CHANNEL LEFT SIDE SLOPE	(H:1V)	2	2	2	2
CHANNEL RIGHT SIDE SLOPE	(H:1V)	2	2	2	2
D (TOTAL DEPTH)	(FT)	1.00	1.00	2.00	2.00
CHANNEL TOP WIDTH @ D	(FT)	5.00	5.00	10.00	10.00
d (CALCULATED FLOW DEPTH)	(FT)	0.29	0.20	0.37	0.30
7 da (FLOW DEPTH ABOVE STONE)	(FT)	N/A	N/A	N/A	N/A
CHANNEL TOP WIDTH @ FLOW DEPTH d	(FT)	2.15	1.78	3.47	3.18
BOTTOM WIDTH: FLOW DEPTH RATIO	(12:1 MAX)	3.5	5.1	5.4	6.8
d50 STONE SIZE	(IN)	N/A	N/A	N/A	N/A
RIPRAP THICKNESS	(IN)	N/A	N/A	N/A	N/A
6 RIPRAP VOID SPACE	(SQ. FT.)	N/A	N/A	N/A	N/A
A (CROSS-SECTIONAL AREA)	(SQ. FT.)	0.45	0.27	1.01	0.77
7 Aa (FLOW AREA ABOVE STONE)	(SQ. FT.)	N/A	N/A	N/A	N/A
P (WETTED PERIMETER)	(FT)	2.29	1.87	3.65	3.32
R (HYDRAULIC RADIUS)		0.20	0.14	0.28	0.23
3 S (BED SLOPE)	(FT/FT)	0.010	0.010	0.019	0.019
Sc (CRITICAL SLOPE)	(FT/FT)	0.310	0.073	0.129	0.062
0.7 Sc	(FT/FT)	0.217	0.051	0.090	0.043
1.3 Sc	(FT/FT)	0.402	0.095	0.167	0.081
STABLE FLOW?	(Y/N)	YES	YES	YES	YES
FREEBOARD BASED ON UNSTABLE FLOW	(FT)	X	X	X	X
FREEBOARD BASED ON STABLE FLOW	(FT)	0.07	0.05	0.09	0.07
4 MINIMUM REQUIRED FREEBOARD	(FT)	0.50	0.50	0.50	0.50
MINIMUM DEPTH REQUIRED	(FT)	0.79	0.70	0.87	0.80
5 DESIGN METHOD FOR PROTECTIVE LINING		V	V	V	V
PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)		V	V	V	V

1 Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For other methods enter N/A and attach appropriate worksheets.

2 Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns

3 Slopes may not be averaged

4 Minimum freeboard is 0.5 ft. or 1/4 total channel depth, whichever is greater

5 Permissible velocity lining design method is not acceptable for channels with bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.

6 Assume 40% void space for flow in channel bottom, ignore side slopes

7 if flow depth above stone is less than 0, use maximum velocity to size riprap

STANDARD WORKSHEET
Channel Design Data

PROJECT NAME: Williams REAE - MLV-505LD86
 LOCATION: Monroe County, PA
 PREPARED BY: CWH Date: 4/6/2021
 CHECKED BY: KCC Date: 4/6/2021

CHANNEL OR CHANNEL SECTION		SH-CC-003		SH-CC-004	
		Vegetated	Unvegetated	Vegetated	Unvegetated
TEMPORARY OR PERMANENT	(T OR P)	P	T	P	T
DESIGN STORM	(YR)	10	10	10	10
DRAINAGE AREA	(Acres)	0.36	0.36	0.05	0.05
1 MULTIPLIER (Qr)					
Qr (REQUIRED CAPACITY)	(CFS)	1.62	1.62	3.03	3.03
Q (CALCULATED AT FLOW DEPTH d)	(CFS)	1.69	1.68	3.05	3.09
2 PROTECTIVE LINING		Grass	SC150BN	Grass	SC150BN
VEGETATIVE LINING RETARDANCE		C	C	C	C
RIPRAP GRADATION		N/A	N/A	N/A	N/A
2 n (MANNING'S COEFFICIENT)		0.056	0.050	0.043	0.050
Va (ALLOWABLE VELOCITY)	(FPS)	5.0	8.0	5.0	8.0
V (CALCULATED AT FLOW DEPTH d)	(FPS)	2.13	2.30	3.83	3.46
ta (MAX ALLOWABLE SHEER STRESS)	(LB/FT ²)	1.00	2.10	1.00	2.10
7 td (CALCULATED AT FLOW DEPTH d)	(LB/FT ²)	X	X	X	X
CHANNEL TYPE		Trapez.	Trapez.	Trapez.	Trapez.
CHANNEL BOTTOM WIDTH	(FT)	2	2	2	2
CHANNEL LEFT SIDE SLOPE	(H:1V)	2	2	2	2
CHANNEL RIGHT SIDE SLOPE	(H:1V)	2	2	2	2
D (TOTAL DEPTH)	(FT)	1.50	1.50	1.50	1.50
CHANNEL TOP WIDTH @ D	(FT)	8.00	8.00	8.00	8.00
d (CALCULATED FLOW DEPTH)	(FT)	0.30	0.29	0.31	0.33
7 da (FLOW DEPTH ABOVE STONE)	(FT)	N/A	N/A	N/A	N/A
CHANNEL TOP WIDTH @ FLOW DEPTH d	(FT)	3.22	3.14	3.22	3.34
BOTTOM WIDTH: FLOW DEPTH RATIO	(12:1 MAX)	6.6	7.0	6.6	6.0
d50 STONE SIZE	(IN)	N/A	N/A	N/A	N/A
RIPRAP THICKNESS	(IN)	N/A	N/A	N/A	N/A
6 RIPRAP VOID SPACE	(SQ. FT.)	N/A	N/A	N/A	N/A
A (CROSS-SECTIONAL AREA)	(SQ. FT.)	0.79	0.73	0.80	0.89
7 Aa (FLOW AREA ABOVE STONE)	(SQ. FT.)	N/A	N/A	N/A	N/A
P (WETTED PERIMETER)	(FT)	3.36	3.27	3.36	3.49
R (HYDRAULIC RADIUS)		0.24	0.22	0.24	0.26
3 S (BED SLOPE)	(FT/FT)	0.044	0.044	0.084	0.084
Sc (CRITICAL SLOPE)	(FT/FT)	0.077	0.063	0.045	0.060
0.7 Sc	(FT/FT)	0.054	0.044	0.032	0.042
1.3 Sc	(FT/FT)	0.100	0.081	0.059	0.078
STABLE FLOW?	(Y/N)	YES	NO	YES	YES
FREEBOARD BASED ON UNSTABLE FLOW	(FT)	X	0.05	X	X
FREEBOARD BASED ON STABLE FLOW	(FT)	0.08	X	0.08	0.08
4 MINIMUM REQUIRED FREEBOARD	(FT)	0.50	0.50	0.50	0.50
MINIMUM DEPTH REQUIRED	(FT)	0.80	0.79	0.81	0.83
5 DESIGN METHOD FOR PROTECTIVE LINING		V	V	V	V
PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)		V	V	V	V

- Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For other methods enter N/A and attach appropriate worksheets.
- Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns
- Slopes may not be averaged
- Minimum freeboard is 0.5 ft. or 1/4 total channel depth, whichever is greater
- Permissible velocity lining design method is not acceptable for channels with bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.
- Assume 40% void space for flow in channel bottom, ignore side slopes
- if flow depth above stone is less than 0, use maximum velocity to size riprap

STANDARD WORKSHEET
Channel Design Data

PROJECT NAME: Williams REAE - MLV-505LD86

LOCATION: Monroe County, PA

PREPARED BY: CWH

CHECKED BY: KCC

Date: 4/6/2021

Date: 4/6/2021

CHANNEL OR CHANNEL SECTION		SH-CC-005		SH-CC-006	SH-CC-007
		Vegetated	Unvegetated	Unvegetated	Unvegetated
TEMPORARY OR PERMANENT	(T OR P)	P	T	P	P
DESIGN STORM	(YR)	10	10	10	10
DRAINAGE AREA	(Acres)	1.20	1.20	0.66	0.13
1 MULTIPLIER (Qr)					
Qr (REQUIRED CAPACITY)	(CFS)	2.84	2.84	4.23	0.62
Q (CALCULATED AT FLOW DEPTH d)	(CFS)	2.89	2.89	4.25	0.68
2 PROTECTIVE LINING		Grass	SC150BN	Riprap	Riprap
VEGETATIVE LINING RETARDANCE		C	C	N/A	N/A
RIPRAP GRADATION		N/A	N/A	R-4	R-3
2 n (MANNING'S COEFFICIENT)		0.039	0.050	0.033	0.028
Va (ALLOWABLE VELOCITY)	(FPS)	5.0	8.0	9.0	6.5
V (CALCULATED AT FLOW DEPTH d)	(FPS)	4.22	3.55	6.97	4.12
ta (MAX ALLOWABLE SHEER STRESS)	(LB/FT ²)	1.00	2.10	2.00	1.00
7 td (CALCULATED AT FLOW DEPTH d)	(LB/FT ²)	X	X	0.09	0.00
CHANNEL TYPE		Trapez.	Trapez.	Trapez.	Trapez.
CHANNEL BOTTOM WIDTH	(FT)	2	2	1	1
CHANNEL LEFT SIDE SLOPE	(H:1V)	2	2	2	2
CHANNEL RIGHT SIDE SLOPE	(H:1V)	2	2	2	2
D (TOTAL DEPTH)	(FT)	1.50	1.50	1.00	1.00
CHANNEL TOP WIDTH @ D	(FT)	8.00	8.00	5.00	5.00
d (CALCULATED FLOW DEPTH)	(FT)	0.27	0.31	0.36	0.13
7 da (FLOW DEPTH ABOVE STONE)	(FT)	N/A	N/A	0.01	0.00
CHANNEL TOP WIDTH @ FLOW DEPTH d	(FT)	3.08	3.24	2.42	1.52
BOTTOM WIDTH: FLOW DEPTH RATIO	(12:1 MAX)	7.4	6.5	2.8	7.7
d50 STONE SIZE	(IN)	N/A	N/A	6	3
RIPRAP THICKNESS	(IN)	N/A	N/A	18	9
6 RIPRAP VOID SPACE	(SQ. FT.)	N/A	N/A	0.60	0.30
A (CROSS-SECTIONAL AREA)	(SQ. FT.)	0.69	0.81	0.61	0.16
7 Aa (FLOW AREA ABOVE STONE)	(SQ. FT.)	N/A	N/A	0.01	0.00
P (WETTED PERIMETER)	(FT)	3.21	3.39	2.59	1.58
R (HYDRAULIC RADIUS)		0.21	0.24	0.24	0.10
3 S (BED SLOPE)	(FT/FT)	0.096	0.096	0.168	0.124
Sc (CRITICAL SLOPE)	(FT/FT)	0.039	0.061	0.028	0.025
0.7 Sc	(FT/FT)	0.027	0.043	0.020	0.018
1.3 Sc	(FT/FT)	0.050	0.080	0.036	0.033
STABLE FLOW?	(Y/N)	YES	YES	YES	YES
FREEBOARD BASED ON UNSTABLE FLOW	(FT)	X	X	X	X
FREEBOARD BASED ON STABLE FLOW	(FT)	0.07	0.08	0.09	0.03
4 MINIMUM REQUIRED FREEBOARD	(FT)	0.50	0.50	0.50	0.50
MINIMUM DEPTH REQUIRED	(FT)	0.77	0.81	0.51	0.50
5 DESIGN METHOD FOR PROTECTIVE LINING		V	V	S	S
PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)		V	V	S	S

1 Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For other methods enter N/A and attach appropriate worksheets.

2 Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns

3 Slopes may not be averaged

4 Minimum freeboard is 0.5 ft. or 1/4 total channel depth, whichever is greater

5 Permissible velocity lining design method is not acceptable for channels with bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.

6 Assume 40% void space for flow in channel bottom, ignore side slopes

7 if flow depth above stone is less than 0, use maximum velocity to size riprap

STANDARD WORKSHEET
Channel Design Data

PROJECT NAME: Williams REAE - MLV-505LD86
 LOCATION: Monroe County, PA
 PREPARED BY: CWH Date: 4/6/2021
 CHECKED BY: KCC Date: 4/6/2021

CHANNEL OR CHANNEL SECTION		SH-CC-008		SH-CC-009	
		Vegetated	Unvegetated	Vegetated	Unvegetated
TEMPORARY OR PERMANENT	(T OR P)	P	T	P	T
DESIGN STORM	(YR)	10	10	10	10
DRAINAGE AREA	(Acres)	0.06	0.06	0.05	0.05
1 MULTIPLIER (Qr)					
Qr (REQUIRED CAPACITY)	(CFS)	4.23	4.23	0.19	0.19
Q (CALCULATED AT FLOW DEPTH d)	(CFS)	4.24	4.26	0.20	0.21
2 PROTECTIVE LINING		Grass	SC150BN	Grass	SC150BN
VEGETATIVE LINING RETARDANCE		C	C	C	C
RIPRAP GRADATION		N/A	N/A	N/A	N/A
2 n (MANNING'S COEFFICIENT)		0.054	0.050	0.055	0.050
Va (ALLOWABLE VELOCITY)	(FPS)	5.0	8.0	5.0	8.0
V (CALCULATED AT FLOW DEPTH d)	(FPS)	2.47	2.60	1.83	1.98
ta (MAX ALLOWABLE SHEER STRESS)	(LB/FT ²)	1.00	2.10	1.00	2.10
7 td (CALCULATED AT FLOW DEPTH d)	(LB/FT ²)	X	X	0.80	0.78
CHANNEL TYPE		Trapez.	Trapez.	Trapez.	Trapez.
CHANNEL BOTTOM WIDTH	(FT)	2	2	1	1
CHANNEL LEFT SIDE SLOPE	(H:1V)	2	2	2	2
CHANNEL RIGHT SIDE SLOPE	(H:1V)	2	2	2	2
D (TOTAL DEPTH)	(FT)	1.50	1.50	1.00	1.00
CHANNEL TOP WIDTH @ D	(FT)	8.00	8.00	5.00	5.00
d (CALCULATED FLOW DEPTH)	(FT)	0.55	0.53	0.09	0.09
7 da (FLOW DEPTH ABOVE STONE)	(FT)	N/A	N/A	N/A	N/A
CHANNEL TOP WIDTH @ FLOW DEPTH d	(FT)	4.21	4.14	1.37	1.36
BOTTOM WIDTH: FLOW DEPTH RATIO	(12:1 MAX)	3.6	3.7	10.8	11.1
d50 STONE SIZE	(IN)	N/A	N/A	N/A	N/A
RIPRAP THICKNESS	(IN)	N/A	N/A	N/A	N/A
6 RIPRAP VOID SPACE	(SQ. FT.)	N/A	N/A	N/A	N/A
A (CROSS-SECTIONAL AREA)	(SQ. FT.)	1.71	1.64	0.11	0.11
7 Aa (FLOW AREA ABOVE STONE)	(SQ. FT.)	N/A	N/A	N/A	N/A
P (WETTED PERIMETER)	(FT)	4.47	4.39	1.42	1.40
R (HYDRAULIC RADIUS)		0.38	0.37	0.08	0.08
3 S (BED SLOPE)	(FT/FT)	0.029	0.029	0.138	0.138
Sc (CRITICAL SLOPE)	(FT/FT)	0.061	0.054	0.106	0.089
0.7 Sc	(FT/FT)	0.043	0.038	0.074	0.062
1.3 Sc	(FT/FT)	0.079	0.070	0.138	0.115
STABLE FLOW?	(Y/N)	YES	YES	NO	YES
FREEBOARD BASED ON UNSTABLE FLOW	(FT)	X	X	0.01	X
FREEBOARD BASED ON STABLE FLOW	(FT)	0.14	0.13	X	0.02
4 MINIMUM REQUIRED FREEBOARD	(FT)	0.50	0.50	0.50	0.50
MINIMUM DEPTH REQUIRED	(FT)	1.05	1.03	0.59	0.59
5 DESIGN METHOD FOR PROTECTIVE LINING		V	V	S	S
PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)		V	V	S	S

- Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For other methods enter N/A and attach appropriate worksheets.
- Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns
- Slopes may not be averaged
- Minimum freeboard is 0.5 ft. or 1/4 total channel depth, whichever is greater
- Permissible velocity lining design method is not acceptable for channels with bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.
- Assume 40% void space for flow in channel bottom, ignore side slopes
- if flow depth above stone is less than 0, use maximum velocity to size riprap

STANDARD WORKSHEET
Channel Design Data

PROJECT NAME: Williams REAE - MLV-505LD86

LOCATION: Monroe County, PA

PREPARED BY: CWH

CHECKED BY: KCC

Date: 4/6/2021

Date: 4/6/2021

CHANNEL OR CHANNEL SECTION		SH-CC-010			
		Vegetated	Unvegetated		
TEMPORARY OR PERMANENT	(T OR P)	P	T		
DESIGN STORM	(YR)	10	10		
DRAINAGE AREA	(Acres)	0.06	0.06		
1 MULTIPLIER (Qr)					
Qr (REQUIRED CAPACITY)	(CFS)	0.25	0.25		
Q (CALCULATED AT FLOW DEPTH d)	(CFS)	0.26	0.25		
2 PROTECTIVE LINING		Grass	SC150BN		
VEGETATIVE LINING RETARDANCE		C	C		
RIPRAP GRADATION		N/A	N/A		
2 n (MANNING'S COEFFICIENT)		0.052	0.050		
Va (ALLOWABLE VELOCITY)	(FPS)	5.0	8.0		
V (CALCULATED AT FLOW DEPTH d)	(FPS)	2.08	2.10		
ta (MAX ALLOWABLE SHEER STRESS)	(LB/FT ²)	1.00	2.10		
7 td (CALCULATED AT FLOW DEPTH d)	(LB/FT ²)	0.90	0.86		
CHANNEL TYPE		Trapez.	Trapez.		
CHANNEL BOTTOM WIDTH	(FT)	1	1		
CHANNEL LEFT SIDE SLOPE	(H:1V)	2	2		
CHANNEL RIGHT SIDE SLOPE	(H:1V)	2	2		
D (TOTAL DEPTH)	(FT)	1.50	1.50		
CHANNEL TOP WIDTH @ D	(FT)	7.00	7.00		
d (CALCULATED FLOW DEPTH)	(FT)	0.11	0.10		
7 da (FLOW DEPTH ABOVE STONE)	(FT)	N/A	N/A		
CHANNEL TOP WIDTH @ FLOW DEPTH d	(FT)	1.42	1.40		
BOTTOM WIDTH: FLOW DEPTH RATIO	(12:1 MAX)	9.5	10.0		
d50 STONE SIZE	(IN)	N/A	N/A		
RIPRAP THICKNESS	(IN)	N/A	N/A		
6 RIPRAP VOID SPACE	(SQ. FT.)	N/A	N/A		
A (CROSS-SECTIONAL AREA)	(SQ. FT.)	0.13	0.12		
7 Aa (FLOW AREA ABOVE STONE)	(SQ. FT.)	N/A	N/A		
P (WETTED PERIMETER)	(FT)	1.47	1.45		
R (HYDRAULIC RADIUS)		0.09	0.08		
3 S (BED SLOPE)	(FT/FT)	0.138	0.138		
Sc (CRITICAL SLOPE)	(FT/FT)	0.092	0.086		
0.7 Sc	(FT/FT)	0.065	0.060		
1.3 Sc	(FT/FT)	0.120	0.112		
STABLE FLOW?	(Y/N)	YES	YES		
FREEBOARD BASED ON UNSTABLE FLOW	(FT)	X	X		
FREEBOARD BASED ON STABLE FLOW	(FT)	0.03	0.03		
4 MINIMUM REQUIRED FREEBOARD	(FT)	0.50	0.50		
MINIMUM DEPTH REQUIRED	(FT)	0.61	0.60		
5 DESIGN METHOD FOR PROTECTIVE LINING		S	S		
PERMISSIBLE VELOCITY (V) OR SHEAR STRESS (S)					

1 Use 1.6 for Temporary Channels; 2.25 for Temporary Channels in Special Protection (HQ or EV) Watersheds; 2.75 for Permanent Channels. For other methods enter N/A and attach appropriate worksheets.

2 Adjust "n" value for changes in channel liner and flow depth. For vegetated channels, provide data for manufactured linings without vegetation and with vegetation in separate columns

3 Slopes may not be averaged

4 Minimum freeboard is 0.5 ft. or 1/4 total channel depth, whichever is greater

5 Permissible velocity lining design method is not acceptable for channels with bed slope of 10% or greater. Shear stress lining design method is required for channels with a bed slope of 10% or greater. Shear stress lining design method may be used for any channel bed slope.

6 Assume 40% void space for flow in channel bottom, ignore side slopes

7 if flow depth above stone is less than 0, use maximum velocity to size riprap


ATTACHMENT 3.7
RIPRAP APRON DESIGN WORKSHEET

STANDARD E & S WORKSHEET # 20

Riprap Apron Outlet Protection


PROJECT NAME:	Williams REAE - MLV-505LD86		
LOCATION:	Monroe County, PA		
PREPARED BY:	CWH	DATE:	4/6/2021 16:09
CHECKED BY:	KCC	DATE:	4/6/2021 16:09

Riprap Apron at Pipe Outlet Without Flared Endwall




PLAN VIEW


Riprap Apron at Pipe Outlet to an Existing Channel



PLAN VIEW



SECTION A - A



ELEVATION

No.	Pipe/C H Dia. Do (in)	Tailwater Cond. (Max or Min)	Mannings "n"	Slope (ft/ft)	Q (cfs)	V* (fps)	RipRap Size	Rt (in)	Al (ft)	Aiw (ft)	Atw (ft)
1	24	Min	0.050	0.084	3.03	4.21	R-3	9	10	6.00	16.00
2	24	Min	0.050	0.330	4.87	7.93	R-4	18	10	6.00	16.00
3	24	Min	0.012	0.020	0.43	4.44	R-3	9	10	6.00	16.00

Note: The anticipated velocity (V) should not exceed the maximum permissible shown in Table 6.6 the proposed riprap protection.

ATTACHMENT 4
OFFSITE DISCHARGE REPORTS



Transcontinental Gas Pipe Line Company, LLC

Offsite Discharge Report

Regional Energy Access Expansion Project

Effort Loop

MLV-505LD86

April 2021

1.0 Project Description

Transcontinental Gas Pipe Line Company, LLC (Transco), a subsidiary of The Williams Companies, Inc., is proposing the Regional Energy Access Expansion Project (Project). MLV-505LD86 is proposed as part of the overall Project. The MLV-505LD86 site will utilize several PCSM BMP's to control stormwater runoff, attenuate peak flow rate and volume, and provide infiltration. Excess stormwater runoff will be directed to the basin and berms, via a series of collection channels, for infiltration and controlled discharge. The new MLV facility will require Erosion and Sediment (E&S) Control and Post Construction Stormwater Management (PCSM) Best Management Practices (BMP's) to manage stormwater runoff during and after construction.

Transco has developed an Offsite Discharge Report for the discharges associated with the proposed BMP's. An Offsite Discharge Report is performed to ensure that no offsite erosion will occur downstream of the proposed activities. The analysis conducted for this project followed the sequence outlined in PaDEP's factsheet for offsite discharges (Document #3930-FS-DEP4124).

2.0 Conveyance Best Management Practices

Erosion and Sediment Control and Post Construction Stormwater Management BMP's are proposed to manage stormwater runoff during and after construction. A series of diversion channels along the access road will direct water to discharge locations on both the north and south sides of the access road. On the south side of the access road, water from diversion channels enters and discharges from infiltration berm 1 near the southeastern part of the site's Limits of Disturbance and from another infiltration berm near the site entrance. Additional collection channels on both the south and north side of the access road direct water into an infiltration basin on the north side on the site entrance and is discharged from a basin outlet, where it then enters a Sugar Hollow Roadside ditch and leaves the site via a Sugar Hollow Road PennDOT culvert. Diversion channels on either side of the site entrance will also divert water to infiltration berm 2, just south of the site entrance. This water will then enter the flow path of the infiltration basin outlet discharge previously described. A diversion channel north of the access road also directs water to a level spreader near the northern part of the Limits of Disturbance. These BMP's will be installed to convey the net increase in volume between the pre- and post-development 2-year storm events and mitigate the increase (pre-post development) in peak runoff for the 2-, 10-, 50-, and 100-year storm events. Two infiltration berms and an infiltration basin

outlet, which allow water to flow to an offsite area, are proposed as discharge structures at this location.

2.1 Infiltration Berm 1

The infiltration berm discharges water, and it flows into the adjacent forested area located east of the Limits of Disturbance. The stormwater is discharged as sheet flow and travels along a vegetative flow path until it reaches a Sugar Hollow Roadside ditch and then crosses Sugar Hollow Road via a PennDOT culvert, eventually entering Sugar Hollow Creek. The flow path is depicted on Exhibit 1.0. Soil types and the erodibility factors within the flow path are shown on Table 1.

Soil Mapping Unit	Soil Erodibility Factor, K_f
KvB	$K_f = 0.15$
WKE	$K_f = 0.05$
Pp	$K_f = 0.43$

The soil erodibility factors are shown in Table 1. A low K value indicates the soil will not easily erode whereas a high K value means the soil will easily erode. KvB and WKE soils have a low susceptibility to erosion (0.15, 0.05) and Pp soils have a moderate susceptibility to erosion (0.43). Photos were taken along the flow path of the downstream area to show the vegetative cover.

*Regional Energy Access Expansion Project
MLV-505LD86
Transcontinental Gas Pipe Line Company, LLC
Offsite Discharge Report*



Photo 1: Existing Area at Proposed Infiltration Berm 1



Photo 2: Area Downgradient of the Proposed Infiltration Berm 1

Photo 1 shows the existing condition where the infiltration berm 1 is proposed. The area will be graded to facilitate the installation of the infiltration berm 1 and revegetated. Photo 2 shows the areas downgradient of the proposed infiltration berm 1, which is over 90% vegetated. In the E&S and PCSM Narrative, site calculations are provided that show the Pre- and Post-Construction runoff flow rates and volume. These calculations show a reduction in the post-construction discharge rates and volumes. Calculations indicated that the discharge velocity at the proposed Infiltration berm are 0.7 and 0.8 fps for the 25 year, 24-hour storm event.

2.2 Infiltration Basin & Infiltration Berm 2

The infiltration basin discharges water through a basin outlet, and it flows into the adjacent forested area near the site entrance. The stormwater is discharged from the basin riser and travels to a culvert crossing the site entrance and then continues along a Sugar Hollow Roadside ditch near the site entrance and then the leaves the LOD via a Sugar Hollow road culvert. Additionally, Infiltration berm 2 will discharge stormwater and will enter the same Sugar Hollow Roadside ditch and continue the same path as described above. The flow paths are depicted Exhibit 1.0. Soil types and the erodibility factors within the flow path are shown on Table 2.

Table 2 – Soils Mapped within Flow Path	
Soil Mapping Unit	Soil Erodibility Factor, K_f
WKE	$K_f = 0.28$
Pp	$K_f = 0.43$

The soil erodibility factor is shown in Table 2. A low K value indicates the soil will not easily erode whereas a high K value means the soil will easily erode. The soil in the flow path is considered moderately erodible (0.28, 0.43). Photos were taken along the flow path of the downstream area to show the vegetative cover.



Photo 3: Existing Area at Proposed Basin Outlet



Photo 4: Area Downgradient of the Proposed Basin Outlet





Photo 5: Existing Area and Area Downgradient Proposed Infiltration Berm 2

Photo 3 shows the existing condition where the basin outlet is proposed. The area will be graded to facilitate the installation of the infiltration basin/basin outlet and revegetated. Photo 4 shows the areas downgradient of the proposed basin outlet, which is over 90% vegetated. Photo 5 shows the area existing conditions where the infiltration berm 2 is proposed as well as the area downgradient of the proposed infiltration berm 2. In the E&S and PCSM Narrative, site calculations are provided that show the Pre- and Post-Construction runoff flow rates and volume. These calculations show a reduction in the post-construction discharge rates and volumes. Calculations indicated that the discharge velocity at the proposed infiltration basin outlet is 0.0 feet per second for the for the 25 year, 24-hour storm event. Additional calculations showed that the discharge velocity at the proposed infiltration berm 2 is 0.0 feet per second for the 25 year, 24-hour storm event.

3.0 Conclusion

*Regional Energy Access Expansion Project
MLV-505LD86
Transcontinental Gas Pipe Line Company, LLC
Offsite Discharge Report*

The Offsite Discharge Report completed for the proposed infiltration berm and basin outlet indicates that the flow paths downgradient of each discharge point are not anticipated to erode during storm events due to the existing vegetative conditions, low discharge velocities, and soil erodibility values.



LEGEND

OFFSITE DISCHARGE FLOW PATH



2525 GREEN TECH DRIVE, SUITE B
STATE COLLEGE, PA 16803

TELEPHONE: (814)-689-1650 FAX: (814)-689-1557

TRANSCONTINENTAL GAS PIPE LINE COMPANY, LLC
REGIONAL ENERGY ACCESS EXPANSION PROJECT
MLV-505LD86
EROSION AND SEDIMENTATION CONTROL PLAN

FLOW PATH

CHESTNUTHILL TWP MONROE COUNTY PENNSYLVANIA

DATE:	03/09/21
DRAWN BY:	RWS
CHECKED:	KCC
WHM DRAWING NO:	FLOW PATH

EXHIBIT 1.0

SECTION 2.2.2
DRAWINGS