





HDD PA-BR-0138.0001-RD (PuB-B3)

Given the design, the threat of inadvertent return has been reduced to the maximum extent practicable and in this case that threat is considered to be low. Implementing this design, along with adherence to the Pennsylvania Pipeline Project Inadvertent Return Contingency Plan will ensure inadvertent impacts, if they were to occur, are also minimized to the maximum extent.

The drill will enter/exit 510 feet from the western edge of Pond B3 (PuB-B3) and enter/exit 1,050 feet from the eastern edge. The drill will pass 30 feet below PuB-B3. The geotechnical results, as well as other data points, were used to determine the entry/exit angles, and depths to pass through the best substrates while maintaining the pipe integrity (e.g., no large bends). According to the geotechnical report the primary substrates being drilled through are siltstone, silty clays, and fine sands. Based on the geotechnical report and the drill profile minimal inadvertent returns are expected.



BERKS COUNTY, PENNSYLVANIA - BRECKNOCK TOWNSHIP S3-0230 PLAN VIEW PROFILE VIEW



- DESIGN AND CONSTRUCTION:**
- CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
 - THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
 - DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
 - CROSSING PIPE SPECIFICATION:
HDD HORZ. LENGTH (L): 1620'
HDD PIPE LENGTH (S): 1654'
20' x 0.456" W.T., X-65, API5L, PSL2, ERW, BFW
COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
 - INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGN FACTOR 0.50).
 - INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
 - PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
 - CARRIER PIPE NOT ENCASED.
 - PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER.
 - CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
 - SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
 - SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
 - SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.

NOTES

- ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
- STATIONING IS BASED ON HORIZONTAL DISTANCES
- ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP. FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
- CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
- SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

REF. DRAWING	NO.	DESCRIPTION	NO.	DESCRIPTION
ES-5.45	TO	EROSION & SEDIMENT PLAN	EP2	REVISED PER PADEP COMMENTS RECEIVED 09-06-16
SHEET 26	TO	AERIAL SITE PLAN	EP1	REVISED PER PADEP COMMENTS
			EP	
			C	ADDED GEOTECH INFO
			B	ISSUED FOR BID
			A	ISSUED FOR REVIEW

REVISIONS


BY	DATE	CHK	DATE	APP	DATE
DLM	09/30/16	RMB	09/30/16	AAW	09/30/16
JTW	05/09/16	RMB	05/09/16	AAW	05/09/16
MRS	11/23/15	RMB	11/23/15	AAW	11/23/15
MRS	09/28/15	RMB	09/28/15	AAW	09/28/15
MRS	07/31/15	RMB	07/31/15	AAW	07/31/15
KB	04/15/15	RMB	04/15/15	AAW	04/15/15



SUNOCO PIPELINE, L.P.




20-INCH HORIZONTAL DIRECTIONAL DRILL
GERHART SCHOOL ROAD
PENNSYLVANIA PIPELINE PROJECT

SCALE: 1"=200' DWG. NO. PA-BR-0138.0001-RD



PLAN VIEW

BERKS COUNTY, PENNSYLVANIA - BRECKNOCK TOWNSHIP
S3-0230-16



- DESIGN AND CONSTRUCTION:
- CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
 - THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
 - DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
 - CROSSING PIPE SPECIFICATION:
HDD HORZ. LENGTH (L-): 1657'
HDD PIPE LENGTH (S-): 1688'
16" x 0.438" W.T., X-70, API5L, PSL2, ERW, BFW
COATING: 14-16 MILS FBE WITH 30-35 MIL ARO (POWERCRETE R95)
 - INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGN FACTOR 0.50).
 - INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
 - PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
 - CARRIER PIPE NOT ENCASED.
 - PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER.
 - CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
 - SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.
 - SUNOCO PIPELINE, L.P.'S HORIZONTAL DIRECTIONAL DRILL INADVERTENT RETURN CONTINGENCY PLAN WILL BE IMPLEMENTED AT ALL TIMES.
 - SUNOCO PIPELINE, L.P.'S EROSION AND SEDIMENTATION CONTROL PLAN WILL BE IMPLEMENTED AT ALL TIMES.

NOTES

- ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83
- STATIONING IS BASED ON HORIZONTAL DISTANCES.
- ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP. FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN.
- CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING.
- SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440.

REF. DRAWING	NO.	DESCRIPTION	NO.	DESCRIPTION
ES-5.45	TO	ES-5.47	EROSION & SEDIMENT PLAN	
SHEET 26	TO	SHEET 27	AERIAL SITE PLAN	EP2 REVISED PER PADEP COMMENTS RECEIVED 09-06-16
				EP1 REVISED PER PADEP COMMENTS
				EP
			B	ADDED GEOTECH INFO
			A	ISSUED FOR BID


Sunoco Logistics Partners L.P.

TETRA TECH ROONEY
(303) 792-5911


SUNOCO PIPELINE, L.P.

16-INCH HORIZONTAL DIRECTIONAL DRILL
GERHART SCHOOL ROAD
PENNSYLVANIA PIPELINE PROJECT

SCALE: 1"=200' DWG. NO. PA-BR-0138.0001-RD-16



LEGEND:

 Geotechnical Soil Boring (SB) Locations



GEOTECHNICAL BORING LOCATIONS
HDD S3-2300
BERKS COUNTY, BRECKNOCK TOWNSHIP, PA
SUNOCO PENNSYLVANIA PIPELINE PROJECT



TETRA TECH

240 Continental Drive, Suite 200
 Newark, Delaware 19713
 302.738.7551
 fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: GEBHART SCHOOL ROAD			Page 1 of 1		
HDD No.: S3-0230		Dates(s) Drilled: 02-08-15		Inspector: E. WATT	
Boring No.: SB-01		Drilling Method: SPT - ASTM D1586		Driller: S. HOFFER	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): NOT ENCOUNTERED		Total Depth (ft): 30.0	
Boring Location Coordinates:			40° 13' 36.153" N		75° 57' 11.979" W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (ft)	Strata (USCS)	Description of Materials	6" Increment Blows *				N	
	From	To	From	To									
			0.0	0.5			TOPSOIL (6")						
1	3.0	5.0	0.5		13	CL	REDDISH BROWN SILTY CLAY WITH SOME FINE SAND, TRACE	1	2	3	5	5	
				8.7			COARSE GRAVEL. (USCS: CL).						
2	8.0	10.0	8.7		24	SC	REDDISH BROWN FINE SAND WITH SOME SILTY CLAY, TRACE	5	10	10	18	20	
							MICA.						
3	13.0	15.0			24		REDDISH BROWN FINE SAND AND SILTY CLAY, WITH A LITTLE	2	18	16	17	34	
							UNWEATHERED SILTSTONE/SHALE ROCK FRAGMENTS.						
4	18.0	20.0			18		REDDISH BROWN FINE SAND, WITH INTERLAYERED SILTY CLAY	3	7	10	24	17	
							LENSES. (USCS: SC).						
5	23.0	25.0			18	REDDISH BROWN MICACEOUS FINE TO MEDIUM SAND WITH A	5	12	16	16	28		
				28.5			LITTLE SILTY CLAY.						
6	28.0	29.3	28.5		15	CL	REDDISH BROWN SILTY CLAY, TRACE WEATHERED	2	25	50/3"		>50	
				30.0			SILTSTONE/SHALE. (USCS: CL)						
							AUGERED TO 30'.						
							CAVED AND DRY AT 29'.						

Notes/Comments:
Pocket Pentrometer Testing
 S1: 1.0 TSF

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
 N: Number of blows to drive spoon from 6" to 18" interval.



TETRA TECH

240 Continental Drive, Suite 200
 Newark, Delaware 19713
 302.738.7551
 fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: GEBHART SCHOOL ROAD			Page 1 of 2		
HDD No.: S3-0230		Dates(s) Drilled: 02-25-15		Inspector: E. WATT	
Boring No.: SB-02		Drilling Method: SPT - ASTM D1586		Driller: S. HOFFER	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): NOT ENCOUNTERED		Total Depth (ft): 68.0	
Boring Location Coordinates:			40° 13' 27.913" N		75° 56' 59.361" W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (ft)	Strata (USCS)	Description of Materials	6" Increment Blows *				N	
	From	To	From	To									
			0.0	0.3			TOPSOIL (3")						
1	3.0	5.0	0.3		23	SM	REDDISH BROWN FINE TO MEDIUM SAND WITH A LITTLE SILT, A LITTLE FINE GRAVEL.	3	9	9	8	18	
2	8.0	10.0	9.0		10	CL	REDDISH BROWN SILTY CLAY, TRACE FINE SAND. (USCS: CL).	4	3	4	4	7	
3	13.0	13.7	11.5		7	SM	REDDISH BROWN FINE TO MEDIUM SAND WITH SOME SILT, TRACE FINE UNWEATHERED GRAVEL.	25	50/2"			>50	
4	18.0	18.6			9		REDDISH BROWN FINE TO MEDIUM SAND WITH A LITTLE SILT, WITH A LITTLE FINE TO COARSE GRAVEL.	20	50/3"			>50	
5	23.0	23.3			4		LIGHT REDDISH BROWN FINE TO MEDIUM SAND, TRACE SILT, SOME FINE TO COARSE GRAVEL AND CONGLOMERATE.	50/4"				>50	
6	28.0	28.7			8		REDDISH BROWN FINE TO MEDIUM SAND WITH A LITTLE SILT, SOME FINE TO COARSE GRAVEL AND CONGLOMERATE.	30	50/2"			>50	
7	38.0	40.0			19		REDDISH BROWN MEDIUM TO COARSE SAND WITH SOME SILT, TRACE FINE GRAVEL.	36	42	16	20	58	
8	43.0	43.3			3		REDDISH BROWN FINE SAND AND WEATHERED ROCK FRAGMENTS.	50/3"				>50	
9	48.0	48.4			4		REDDISH BROWN FINE SAND AND WEATHERED ROCK FRAGMENTS, SOME SILT. (USCS: SM).	50/5"				>50	
10	53.0	53.5			6		REDDISH BROWN FINE SAND AND WEATHERED ROCK FRAGMENTS, SOME SILT.	50/6"				>50	
				55.0									
								AUGER REFUSAL AT 55". BEGIN ROCK CORING:					
RUN 1	55.0	57.5	55.0	57.5	17		REDDISH BROWN SILTSTONE	TCR: 57%, SCR: 57%, RQD: 30%					
							CORE HOLE FILLED WITH MATERIAL, PULLED BARREL AND SWITCHED BACK TO AUGER (SEE NEXT PAGE).						

Notes/Comments:
Pocket Pentrometer Testing
 S2 (9.5'): 3.25 TSF
 S11: > 4 TSF

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
 N: Number of blows to drive spoon from 6" to 18" interval.



TETRA TECH

240 Continental Drive, Suite 200
 Newark, Delaware 19713
 302.738.7551
 fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: GEBHART SCHOOL ROAD			Page 2 of 2		
HDD No.: S3-0230		Dates(s) Drilled: 02-26-15		Inspector: E. WATT	
Boring No.: SB-02		Drilling Method: SPT - ASTM D1586		Driller: S. HOFFER	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): NOT ENCOUNTERED		Total Depth (ft): 68.0	
Boring Location Coordinates:			40° 13' 27.913" N		75° 56' 59.361" W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (in)	Strata (USCS)	Description of Materials	6" Increment Blows *				N
	From	To	From	To								
11	57.5	58.8	57.5		15	CL	REDDISH BROWN SILTY CLAY AND FINE SAND, TRACE SILTSTONE	28	29	50/4"		>50
				61.0			FRAGMENTS. (DECOMPOSED SILTSTONE). (USCS: CL).					
12	64.0	64.3	61.0	65.0	3	SILTSTONE	REDDISH BROWN WEATHERED SILTSTONE.	50/3"				>50
RUN 2	65.0	68.0	65.0		30		HEAVILY WEATHERED REDDISH BROWN SILTSTONE.	TCR: 83%, SCR: 42%, RQD: 19%				
				68.0			SLIGHT TO MODERATELY WEATHERED SILTSTONE.					
							HEAVILY WEATHERED REDDISH BROWN SILTSTONE.					
							AUGER REFUSAL AT 65', BEGAN ROCK CORING AT 65'.					
							COULD NOT RESET CORE BARREL TO CONTINUE ROCK CORING DUE TO MATERIAL CAVE WITHIN BOREHOLE.					
							WATER LEVEL NOT ENCOUNTERED WITHIN OVERBURDEN.					
							CAVED AND DRY AT 26'.					
							<u>CORE TESTING RESULTS (RUN 2, DEPTH 66.7')</u> :					
							COMPRESSIVE STRENGTH: 3,390 PSI					
							UNIT WEIGHT: 157.1 PCF					

Notes/Comments:
Pocket Pentrometer Testing
 S2 (9.5'): 3.25 TSF
 S11: > 4 TSF

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
 N: Number of blows to drive spoon from 6" to 18" interval.



TETRA TECH

240 Continental Drive, Suite 200
 Newark, Delaware 19713
 302.738.7551
 fax: 302.454.5988

TEST BORING LOG

Project Name: SUNOCO PENNSYLVANIA PIPELINE PROJECT			Project No.: 103IP3406		
Project Location: GEBHART SCHOOL ROAD			Page 1 of 1		
HDD No.: S3-0230		Dates(s) Drilled: 02-11-15		Inspector: E. WATT	
Boring No.: SB-03		Drilling Method: SPT - ASTM D1586		Driller: S. HOFFER	
Drilling Contractor: HAD DRILLING		Groundwater Depth (ft): NOT ENCOUNTERED		Total Depth (ft): 25.0	
Boring Location Coordinates:			40° 13' 22.412" N		75° 56' 49.955" W

Sample No.	Sample Depth (ft)		Strata Depth (ft)		Recov. (ft)	Strata (USCS)	Description of Materials	6" Increment Blows *				N	
	From	To	From	To									
			0.0	0.1			TOPSOIL (1")						
1	3.0	5.0	0.1		14	CL	REDDISH BROWN SILTY CLAY AND FINE SAND, TRACE FINE GRAVEL.	1	5	8	13	13	
2	8.0	10.0			24		REDDISH BROWN SILTY CLAY AND FINE SAND, MICACEOUS, TRACE FINE GRAVEL.	8	13	23	35	36	
3	13.0	15.0			24		REDDISH BROWN SILTY CLAY. (USCS: CL)	4	11	18	17	29	
				16.5									
4	18.0	19.5	16.5		18	CL/ GC	REDDISH BROWN SILTY CLAY WITH SOME FINE MICACEOUS SAND, WITH SOME FINE GRAVEL.	3	31	50/6"		>50	
5	23.0	24.5			18		REDDISH BROWN SILTY CLAY WITH SOME FINE MICACEOUS SAND, WITH SOME FINE GRAVEL. (USCS: CL)	10	41	50/6"		>50	
				25.0									
							AUGER REFUSAL AT 25'.						
							CAVED AND DRY AT 24'.						

Notes/Comments:
Pocket Pentrometer Testing

Strata (USCS) Designations are approximated based on visual review, except where indicated in Description of Materials.

* Number of blows of 140 lb. Hammer dropped 30 in. required to drive 2 in. split-spoon sampler in 6 in. increments.
 N: Number of blows to drive spoon from 6" to 18" interval.

GEOTECHNICAL LABORATORY TESTING SUMMARY
SUNOCO PENNSYLVANIA PIPELINE PROJECT
HDD S3-0230

HDD No.	Test Boring No.	Sample No.	Depth of Sample (ft.)		Water Content, % (ASTM D2216)	Percent Silts/Clays, % (ASTM D1140)	Atterburg Limits (ASTM D4318)			USCS Classif. (ASTM D2487)
			From	To			Liquid Limit, %	Plastic Limit, %	Plasticity Index, %	
S3-0230	SB-01	1	3.0	5.0	19.6	73.5	34	19	15	CL
		2	8.0	10.0	6.6	28.6	-	-	-	-
		3	13.0	15.0	10.3	47.8	-	-	-	-
		4	18.0	20.0	12.8	41.0	30	20	10	SC
		5	23.0	25.0	9.2	17.6	-	-	-	-
		6	28.0	29.3	13.9	95.7	36	21	15	CL
	SB-02	2	8.0	10.0	21.0	97.7	42	24	18	CL
		3	13.0	13.7	7.6	35.5	-	-	-	-
		6	28.0	28.7	5.7	18.8	-	-	-	-
		7	38.0	40.0	12.3	27.9	-	-	-	-
		9	48.0	48.4	10.6	35.0	29	24	5	SM
		11	57.5	58.8	14.0	63.2	42	19	23	CL
	SB-03	1	3.0	5.0	12.9	52.8	-	-	-	-
		2	8.0	10.0	15.6	61.1	-	-	-	-
		3	13.0	15.0	14.9	99.0	35	20	15	CL
4		18.0	19.5	8.8	72.4	-	-	-	-	
5		23.0	24.5	10.0	74.0	34	19	15	CL	

Rock Core Testing Results				
Boring No.	Core Run	Approximate Depth (ft)	Compressive Strength (psi)	Unit Weight (pcf)
SB-02	2	66.7	3,390	157.1

Notes:

- 1) Sample depths based on feet below grade at time of exploration.

**REGIONAL GEOLOGY SUMMARY
SUNOCO PENNSYLVANIA PIPELINE PROJECT
HDD S3-0230**

HDD No.	NAME	BORING NO.	REGIONAL GEOLOGY DESCRIPTION	GENERAL TOPOGRAPHIC SETTING	BEDROCK FORMATION	GENERAL ROCK TYPE	APPROX MAX FM THICKNESS (FT)	DEPTH TO ROCK (Ft bgs) based on nearby well drilling logs	NOTES / COMMENTS
S3-0230	Gebhart School Rd.	SB-01	Hammer Creek Fm - reddish-brown, coarse grained sandstone with interbeds of red shale and quartz pebble conglomerate	Rolling hills	Hammer Creek Fm.	sandstone with quartz pebble conglomerate	9,360	13-70	
		SB-02	Hammer Creek Conglomerate - very coarse quartz conglomerate having abundant pebbles and cobbles of gray quartzite.		Hammer Creek Conglomerate	quartz conglomerate; reddish brown cross-bedded sandstone	2,580	14-70	
		SB-03							

Note : Source of well log data - <http://www.dcnr.state.pa.us/topogeo/groundwater/pagwis/records/index.htm>. All other sources as referenced in comments section.

**ROCK CORE DESCRIPTION SUMMARY
SUNOCO PENNSYLVANIA PIPELINE PROJECT
HDD S3-0230**

Location	Boring No.	Core Run	Core Depth (ft)		TCR (%)	SCR (%)	RQD (%)	Depth (ft)		Weathering	Classification	Bedding Thickness (ft)	Color	Discontinuity Data
			From	To				From	To					
S3-0230	SB-2	1	55	57.5	57	57	30	55	57.5	Slight	Siltstone	Massive	Red	Fractures ranging from 0° to 35°, Avg. 15°
		2	65	38	83	42	19	65	66	Heavily	Siltstone	Approx. 1'	Red	Heavily fractured and appears as though fines washed out during drilling
								66	67	Slight to moderate	Siltstone	Approx. 1'	Red	Fractures (very few) ranging from 0° to 5°, Avg. 2.5°; infilling of fractures with minerals, probably quartz
								67	68	Heavily	Siltstone	Approx. 1'	Red	Heavily fractured and weathered, very broken up and soft

FIELD DESCRIPTION AND LOGGING SYSTEM FOR SOIL EXPLORATION

GRANULAR SOILS

(Sand, Gravel & Combinations)

<u>Density</u>	<u>N (blows)*</u>
Very Loose	5 or less
Loose	6 to 10
Medium Dense	11 to 30
Dense	31 to 50
Very Dense	51 or more

Particle Size Identification

Boulders	8 in. diameter or more
Cobbles	3 to 8 in. diameter
Gravel	Coarse (C) 3 in. to ¾ in. sieve Fine (F) ¾ in. to No. 4 sieve
Sand	Coarse (C) No. 4 to No. 10 sieve (4.75mm-2.00mm) Medium (M) No. 10 to No. 40 sieve (2.00mm – 0.425mm) Fine (F) No. 40 to No. 200 sieve (0.425 – 0.074mm)
Silt/Clay	Less Than a No. 200 sieve (<0.074mm)

Relative Proportions

<u>Description Term</u>	<u>Percent</u>
Trace	1 - 10
Little	11 - 20
Some	21 - 35
And	36 - 50

COHESIVE SOILS

(Silt, Clay & Combinations)

<u>Consistency</u>	<u>N (blows)*</u>
Very Soft	3 or less
Soft	4 to 5
Medium Stiff	6 to 10
Stiff	11 to 15
Very Stiff	16 to 30
Hard	31 or more

Plasticity

<u>Degree of Plasticity</u>	<u>Plasticity Index</u>
None to Slight	0 - 4
Slight	5 - 7
Medium	8 - 22
High to Very High	> 22

ROCK

(Rock Cores)

<u>Rock Quality Designation (RQD), %</u>	<u>Rock Quality Description</u>
0-25	Very Poor
25-50	Poor
50-75	Fair
75-90	Good
90-100	Excellent

***N - Standard Penetration Resistance.** Driving a 2.0" O.D., 1-3/8" I.D. sampler a distance of 18 inches into undisturbed soil with a 140 pound hammer free falling a distance of 30.0 inches. The number of hammer blows to drive the sampler through each 6 inch interval is recorded; the number of blows required to drive the sampler through the final 12 inch interval is termed the Standard Penetration Resistance (SPR) N-value. For example, blow counts of 6/8/9 (through three 6-inch intervals) results in an SPR N-value of 17 (8+9).

Groundwater observations were made at the times indicated. Groundwater elevations fluctuate throughout a given year, depending on actual field porosity and variations in seasonal and annual precipitation.

UNIFIED SOIL CLASSIFICATION SYSTEM [Casagrande (1948)]

Major Divisions		Group Symbols	Typical Descriptions	Laboratory Classifications				
Coarse Grained Soils (More than half of material is larger than No. 200 sieve)	Gravels (More than half of coarse fraction is larger than No. 4 sieve size)	Clean gravel (Little or no fines)	GW Well-graded gravels, gravel-sand mixtures, little or no fines	Determine Percentage of sand and gravel from grain size curve. Depending on Percentage of fines (fraction smaller than No. 200 sieve), coarse-grained soils are classified as follows: Less than 5 percent GW, GP, SW, SP More than 12 percent GM, GC, SM, SC 5 to 12 percent Borderline cases requiring dual symbols ⁽¹⁾	$C_u = \frac{D_{60}}{D_{10}}$ greater than 4: $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and 3			
		GP Poorly graded gravels, gravel-sand mixtures, little or no fines	Not meeting C_u or C_c requirements for GW					
		Gravel with fines (Appreciable amount of fines)	GM Silty gravels, gravel-sand-silt mixtures		Atterberg limits below A Line or I_p less than 4	Limits plotting in hatched zone with I_p between 4 and 7 are borderline cases requiring use of dual symbols		
			GC Clayey gravels, gravel-sand-clay mixtures				Atterberg limits above A line with I_p greater than 7	
	Sands (More than half of coarse fraction is smaller than No. 4 Sieve)	Clean sands (Little or no fines)	SW Well graded sands, gravelly sands, little or no fines		$C_u = \frac{D_{60}}{D_{10}}$ greater than 6: $C_c = \frac{(D_{30})^2}{D_{10} \times D_{60}}$ between 1 and 3			
			SP Poorly graded sands, gravelly sands, little or no fines		Not meeting C_u or C_c requirements for SW			
		Sands with fines (Appreciable amount of fines)	SM Silty sands, sand-silt mixtures		Atterberg limits below A Line or I_p less than 4	Limits Plotting in hatched zone with I_p between 4 and 7 are borderline cases requiring use of dual symbols		
			SC Clayey sands, sand-clay mixtures		Atterberg limits above A line with I_p greater than 7			
						For soils plotting nearly on A line use dual symbols i.e., $I_p = 29.5$, $w_L = 60$ gives CH-MH. When w_L is near 50 use CL-CH or ML-MH. Take near as ± 2 percent.		
		Fine-grained soils (More than half of material is smaller than No. 200 sieve)	Silt and clays (Liquid limit less than 50)		ML Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey silts with slight plasticity			
CL Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays								
OL Organic silts and organic silty clays of low plasticity								
Silt and Clays (Liquid limit greater than 50)	MH Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts							
	CH Inorganic clays of high plasticity, fat clays							
	OH Organic clays of medium to high plasticity, organic silts							
Highly organic soils	Pt Peat and other highly organic soils							

(1) Borderline classifications, used for soils possessing characteristics of two groups, are designated by combinations of group symbols. For example: GW-GC. well-graded gravel-sand mixture with clay binder.