



- DESIGN AND CONSTRUCTION:**
- CONTRACTOR SHALL FIELD VERIFY DEPTH OF ALL EXISTING UTILITIES SHOWN OR NOT SHOWN ON THIS DRAWING.
 - THE MINIMUM SEPARATION DISTANCE FROM EXISTING SUBSURFACE UTILITIES SHALL NOT BE LESS THAN 10 FEET AS MEASURED FROM THE OUTSIDE EDGE OF THE UTILITY TO OUTSIDE OF PROPOSED PIPELINE.
 - DESIGNED IN ACCORDANCE WITH CFR 49 195 & ASME B31.4
 - CROSSING PIPE SPECIFICATION:
 HDD HORZ. LENGTH (L)=5800'
 HDD PIPE LENGTH (S)=5841'
 20" x 0.456" W.T., X-65, API5L, PSL2, ERW, BFW
 COATING: 14-16 MILS FBE WITH 40 MILS MIN. ARO (POWERCRETE R95)
 - INTERNAL DESIGN PRESSURE 1480 PSIG (SEAM FACTOR 1.0, DESIGN FACTOR 0.50 (HOOP STRESS)).
 - INSTALLATION METHOD: HORIZONTAL DIRECTIONAL DRILL (HDD).
 - PIPELINE WARNING MARKERS SHALL BE INSTALLED ON BOTH SIDES OF ALL ROAD, RAILWAY, AND STREAM CROSSINGS.
 - CARRIER PIPE NOT ENCASED.
 - PIPE / AMBIENT TEMPERATURE MUST BE NO LESS THAN 30°F DURING PULLBACK WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER.
 - CONDUCT 4-HOUR PRE-INSTALLATION HYDROTEST OF HDD PIPE STRING TO MINIMUM 1850 PSIG.
 - PIPELINE AND CROSSING TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH LAST APPROVED AMERICAN RAILWAY ENGINEERING AND MAINTENANCE OF WAY ASSOCIATION SPECIFICATIONS FOR PIPELINES CONVEYING FLAMMABLE AND NON-FLAMMABLE SUBSTANCES.
 - BLASTING NOT PERMITTED.
 - SEE SUNOCO PENNSYLVANIA PIPELINE PROJECT ESRI WEBMAP FOR ACCESS ROAD ALIGNMENT.

| NOTES | | REF. DRAWING | | REVISIONS | | | | | | SUNOCO PIPELINE, L.P. | | |
|---|--------|--------------|------------|-------------------------|-----|----------------------------|-----|----------|-----|-----------------------|---|--|
| 1. ALL COORDINATES SHOWN ARE IN LATITUDE AND LONGITUDE. ALL MSL ELEVATIONS ARE NAD83 | | ES-4.20 | TO ES-4.04 | EROSION & SEDIMENT PLAN | | | | | | | Sunoco Logistics Partners L.P. | 20-INCH HORIZONTAL DIRECTIONAL DRILL SUSQUEHANNA RIVER PENNSYLVANIA PIPELINE PROJECT |
| 2. STATIONING IS BASED ON HORIZONTAL DISTANCES | | SHEET 13 | TO SHEET 2 | AERIAL SITE PLAN | EP1 | REVISED PER PADEP COMMENTS | MRS | 05/17/16 | RMB | 05/17/16 | | |
| 3. ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP ARE NOT RESPONSIBLE FOR LOCATION OF FOREIGN UTILITIES SHOWN IN PLOT PLAN OR PROFILE. THE INFORMATION SHOWN HEREON IS FURNISHED WITHOUT LIABILITY ON THE PART OF ROONEY ENGINEERING, INC. AND SUNOCO PIPELINE, LP, FOR ANY DAMAGES RESULTING FROM ERRORS OR OMISSIONS THEREIN. | | | | | EP | | JTW | 11/13/15 | RMB | 11/13/15 | AAW | 11/13/15 |
| 4. CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES. CONTACT ONE CALL AT 811 PRIOR TO DIGGING. | | | | | C | ADDED GEOTECH INFO | MRS | 09/17/15 | RMB | 09/17/15 | AAW | 09/17/15 |
| 5. SUNOCO EMERGENCY HOTLINE NUMBER IS #1-800-786-7440. | | | | | B | ISSUED FOR BID | DLM | 07/31/15 | RMB | 07/31/15 | AAW | 07/31/15 |
| | | | | | A | ISSUED FOR REVIEW | RTT | 02/18/15 | RMB | 02/18/15 | AAW | 02/18/15 |
| DWG NO | DWG NO | DESCRIPTION | NO. | DESCRIPTION | BY | DATE | CHK | DATE | APP | DATE | SCALE: 1"=250' | |



SCALE: 1"=250' DWG. NO: PA-YO-0063.0000-RRa